

SIGNING

STATION / LOCATION			SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT
STATION	DESCRIPTION	LT/RT	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)
IL 13						
1729+50	SPEED LIMIT 45	LT		12.00		17
1729+50	SPEED LIMIT 45	MED		12.00		17
1729+69	RIGHT TURN LANE	RT	4.00		16	
1734+77	LEFT TURN SIGNAL	LT	7.50			
1735+24	LEFT TURN SIGNAL	RT	7.50			
1736+20	LEFT TURN SIGNAL	LT	7.50			
1736+57	LEFT TURN SIGNAL	RT	7.50			
1737+85	SPEED LIMIT 45	RT		12.00		17
1742+30	RIGHT TURN LANE	LT	4.00			
1743+00	SPEED LIMIT 45	MED		12.00		17
1743+40	LEFT TURN LANE	MED	4.00		16	
1755+00	SPEED LIMIT 45	LT		12.00		17
1755+00	SPEED LIMIT 45	MED		12.00		17
1757+10	LEFT TURN LANE	MED	4.00		16	
1761+86	NO TURN ON RED	LT		12.00		
1762+18	LEFT TURN SIGNAL	RT	7.50			
1763+18	LEFT TURN SIGNAL	LT	7.50			
1763+29	LEFT TURN SIGNAL	RT	7.50			
1763+40	LEFT TURN SIGNAL	LT	7.50			
1766+00	SPEED LIMIT 45	MED		12.00		17
1766+00	SPEED LIMIT 45	RT		12.00		17
1768+27	RIGHT TURN LANE	LT	4.00		16	
FRONTAGE ROAD						
461+53	STOP	LT	9.00			16
464+75	STOP AHEAD	LT	6.25		17	
466+75	SKYLINE DR AHEAD	LT	8.00			16
471+42	MARATHON DR AHEAD	RT	8.00			16
473+42	RR CROSSING	RT	9.00			16
474+28	DO NOT STOP ON TRACKS	MED	5.00		15	
475+27	DO NOT STOP ON TRACKS	LT	5.00		16	
476+27	RR CROSSING	LT	9.00			16
482+00	MARATHON DR AHEAD	LT	8.00			16
493+75	WALTON WAY AHEAD	RT	8.00			16
495+75	STOP AHEAD	RT	6.25		16	
SKYLINE DRIVE (SOUTH)						
1+03	LEFT TURN YIELD ON GREEN	RT	7.50			
1+06	LEFT TURN YIELD ON GREEN	LT	7.50			
2+30	RIGHT LANE MUST TURN RIGHT	RT	6.25		16	
5+00	RIGHT LANE MUST TURN RIGHT	LT	6.25		16	
SKYLINE DRIVE (NORTH)						
10+42	LEFT TURN YIELD ON GREEN	LT	7.50			
10+42	LEFT TURN YIELD ON GREEN	RT	7.50			
11+90	MERGE	RT	9.00			17
MARATHON DRIVE						
7+60	STOP AHEAD	LT	6.25		17	
12+00	STOP AHEAD	RT	6.25		17	
TOTALS			225.50	108.00	194	265

EARTHWORK

LOCATION	EARTH EXCAVATION	FOR INFORMATION ONLY			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	FURNISHED EXCAVATION
		EARTH EXCAVATION ADJUSTED FOR 25% SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)		
STATION TO STATION	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
STAGE 1						
IL 13						
1729+56.07 - 1738+00.00	1,158	869	2,721	-1,853		1,853
1738+00.00 - 1746+00.00	5,670	4,253	21,685	-17,433		17,433
1746+00.00 - 1754+00.00	3,232	2,424	30,267	-27,843		27,843
1754+00.00 - 1761+00.00	2,886	2,165	14,563	-12,399		12,399
1761+00.00 - 1767+07.23	2,834	2,126	43	2,083		-2,083
FRONTAGE ROAD	376	282	5,467	-5,185	61	5,246
SKYLINE DRIVE (SOUTH)	941	706	208	498		-498
STAGE 1 SUBTOTALS	17,097	12,823	74,954	-62,131	61	62,192
STAGE 2						
IL 13						
1729+56.07 - 1738+00.00	1,078	809	3,523	-2,715	178	2,893
1738+00.00 - 1746+00.00	2,418	1,814	28,950	-27,137		27,137
1746+00.00 - 1754+00.00	4,156	3,117	14,618	-11,501		11,501
1754+00.00 - 1761+00.00	296	222	18,624	-18,402	67	18,469
1761+00.00 - 1767+07.23	2,009	1,507	460	1,047		-1,047
SKYLINE DRIVE (NORTH)	397	298	737	-439		439
MARATHON DRIVE	1,149	862	968	-106		106
STAGE 2 SUBTOTALS	11,503	8,627	67,880	-59,253	245	59,498
TOTALS	28,600	21,450	142,834	-121,384	306	121,690