

**TEMPORARY CONCRETE BARRIER WALL**

STATION / LOCATION			TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TL2	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TL2	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TL2	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TL2	MODULAR GLARE SCREEN SYSTEM	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR
STATION	TO	STATION	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(FOOT)	(EACH)
STAGE 1B										
IL 13										
1725+00.00	-	1738+00.00	1,092		1	3			937	21
1738+00.00	-	1751+00.00	2,680			4			1,167	39
1751+00.00	-	1764+00.00	2,436			2			1,131	37
1764+00.00	-	1755+00.00	1,118						626	19
STAGE 1B SUBTOTALS			7,326	0	1	9	0	0	3,861	116
STAGE 2A										
IL 13										
1725+00.00	-	1738+00.00		790			1	1	598	
1738+00.00	-	1751+00.00		2,211				1	1,247	
1751+00.00	-	1764+00.00		2,102				3	1,148	
1764+00.00	-	1755+00.00		572				1	572	
STAGE 2A SUBTOTALS			0	5,675	0	0	1	6	3,565	0
TOTALS			7,326	5,675	1	9	1	6	7,426	116

**TEMPORARY PAVING**

STATION / LOCATION			PAVEMENT REMOVAL	HMA PAVEMENT (FULL DEPTH), 10"	SUBBASE GRANULAR MATERIAL, TYPE B 4"	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TEMPORARY RAMPS	BITUMINOUS MATERIALS (PRIME COAT)
STATION	TO	STATION	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(GAL)
STAGE 1A								
IL 13								
1725+00.00	-	1738+00.00	2,062	2,062	2,414			824.8
1738+00.00	-	1751+00.00	4,202	4,121	4,470	9.0		1,648.4
1751+00.00	-	1764+00.00	2,356	2,356	2,755			942.4
1764+00.00	-	1775+00.00	872	872	1,004			348.8
STAGE 1B								
IL 13								
1725+00.00	-	1738+00.00	172	172	213			68.8
1738+00.00	-	1751+00.00	208	11	19	22.0		4.4
1751+00.00	-	1764+00.00	45			5.0		
STAGE 1C								
IL 13								
1725+00.00	-	1738+00.00	142	142	168		1,142	56.8
STAGE 1D								
SKYLINE DR. (SOUTH)								
	-						93	
STAGE 1F								
IL 13								
1725+00.00	-	1738+00.00	349	349	447			139.6
1764+00.00	-	1775+00.00	421	421	519			168.4
STAGE 2A								
IL 13								
1751+00.00	-	1764+00.00	104	104	119			41.6
STAGE 2C								
SKYLINE DR. (NORTH)								
12+73.17	-	13+13.17					54	
STAGE 2D								
SKYLINE DR. (NORTH)								
12+73.17	-	14+15.00					141	
STAGE 2E								
IL 13								
1725+00.00	-	1738+00.00	92	92	107			36.8
TOTALS			11,025	10,702	12,235	36.0	1,430	4,280.8