



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

March 1, 2018

SUBJECT: FAI Route 55 (I-55 & Weber Rd)
Project NHPP-STP-TJQZ(898)
Section (99-1HB-1)R-1
Will County
Contract No. 60X10
Item No. 117, March 9, 2018 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ix of the Table of Contents to the Special Provisions
3. Revised page 470 of the Special Provisions
4. Added page 635 to the Special Provisions
5. Revised sheets 5,10,11,19,20,25,26,29-36,38,41-44,46,48-51, 1005,1006, & 1008 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.
Acting Bureau Chief
Bureau of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Anthony Quigley, Region 1, District 1; Tim Kell; D. Carl Puzey;
Estimates

MS/ck

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	583
SURFACE TESTING OF HOT-MIX ASPHALT OVERLAYS (BDE).....	584
TEMPORARY PAVEMENT MARKING (BDE).....	584
TRAINING SPECIAL PROVISIONS (BDE)	587
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION	589
TRAVERSABLE PIPE GRATE FOR CONCRETE END SECTIONS (BDE).....	592
WARM MIX ASPHALT (BDE)	593
WEEKLY DBE TRUCKING REPORTS (BDE).....	595
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE).....	596
FUEL COST ADJUSTMENT (BDE).....	597
STEEL COST ADJUSTMENT (BDE).....	600
STORM WATER POLLUTION PREVENTION PLAN	603
USACE SECTION 404 PERMIT	619
COMBINATION CONCRETE CURB AND GUTTER.....	635
PORTLAND CEMENT CONCRETE PAVEMENT (JOINTED).....	635

TEMPORARY WOOD POLE, 60 FT, CLASS 4, 8 FT MAST ARM

Description:

This item will consist of furnishing, installing and removing a temporary wood pole with 8 foot mast arm, used for the temporary surveillance system of the size and description as shown on the plans, and shall include all hardware and accessories required for the intended temporary use of the pole

Material:

The wood pole must be 60 feet in length and meet the requirements of Article 1069.04 of the Standard Specifications. The mast arm assembly's must be 8 feet in length, together with mounting hardware and meet the requirements of Article 1069.02 (a).

Provide a ground rod which shall be not less than 5/8 inch in diameter and not less than 10 feet in length and copper ground wire as follows:

Item	Article/Section
(a) Ground Rod	1087.01(b)
(b) Copper Ground Wire	1087.01(a)

Installation:

The wood pole must be installed as described in Article 830.03(c) of the Standard Specifications and/or as directed by the engineer. The Contractor shall provide all hardware to install the pole as specified herein and indicated on the plans.

Removal:

The wood pole shall remain the property of the Contractor and shall be removed when directed by the Engineer. The work shall be performed in accordance with Article 841.02 of the Standard Specifications with the exception that no luminaires must be salvaged.

Method of Measurement:

This work will be measured for payment in units per each for LIGHT POLE, WOOD, 60 FT, CLASS 4, 8 FT MAST ARM.

Basis of Payment:

This work will be paid for at the contract unit price per each for LIGHT POLE, WOOD, 60 FT, CLASS 4, 8 FT MAST ARM, which shall be payment in full for furnishing, installing and removing the equipment as shown on the plans.

COMBINATION CONCRETE CURB AND GUTTER

Description. This work shall consist of constructing combination concrete curb and gutter in accordance with Section 606 of the Standard Specifications, the Highway Standards and details included in the contract plans and the following:

Tie bars shall be epoxy coated reinforcement bars in accordance with Article 1006.10 of the Standard Specifications.

Method of Measurement. This work shall be measured for payment in accordance with Article 606.14.

Basis of Payment. This work shall be paid for in accordance with Article 606.15 and the following:

Tie bars shall be included in the contract unit cost for COMBINATION CONCRETE CURB AND GUTTER, of the type specified.

PORTLAND CEMENT CONCRETE PAVEMENT (JOINTED)

Description. This work shall consist of constructing jointed portland cement concrete pavement in accordance with Section 420 of the Standard Specifications, the Highway Standards and details included in the contract plans and the following:

Tie bars shall be epoxy coated reinforcement bars in accordance with Article 1006.10 of the Standard Specifications.

Method of Measurement. This work shall be measured for payment in accordance with Article 420.19.

Basis of Payment. This work shall be paid for in accordance with Article 420.20 and the following:

Tie bars shall be included in the contract unit cost for PORTLAND CEMENT CONCRETE PAVEMENT (JOINTED), of the thickness specified.

Added 3-1-18