142

Letting March 9, 2018

Notice to Bidders, Specifications and Proposal



Springfield, Illinois 62764

Contract No. 97663 ST. CLAIR County Section 14-00042-00-PV (Fairview Heights) Route FAU 9326 (Market Place) Project VQW9-866 () District 8 Construction Funds

Prepared by

Checked by

F



NOTICE TO BIDDERS

- 1. TIME AND PLACE OF OPENING BIDS. Electronic bids are to be submitted to the electronic bidding system (iCX-Integrated Contractors Exchange). All bids must be submitted to the iCX system prior to 10:00 a.m. March 9, 2018 at which time the bids will be publicly opened from the iCX SecureVault.
- 2. DESCRIPTION OF WORK. The proposed improvement is identified and advertised for bids in the Invitation for Bids as:

Contract No. 97663 ST. CLAIR County Section 14-00042-00-PV (Fairview Heights) Project VQW9-866 () Route FAU 9326 (Market Place) District 8 Construction Funds

Intersection improvement at Market Place and Plaza Drive in the City of Fairview Heights.

- **3. INSTRUCTIONS TO BIDDERS.** (a) This Notice, the invitation for bids, proposal and letter of award shall, together with all other documents in accordance with Article 101.09 of the Standard Specifications for Road and Bridge Construction, become part of the contract. Bidders are cautioned to read and examine carefully all documents, to make all required inspections, and to inquire or seek explanation of the same prior to submission of a bid.
 - (b) State law, and, if the work is to be paid wholly or in part with Federal-aid funds, Federal law requires the bidder to make various certifications as a part of the proposal and contract. By execution and submission of the proposal, the bidder makes the certification contained therein. A false or fraudulent certification shall, in addition to all other remedies provided by law, be a breach of contract and may result in termination of the contract.
- 4. AWARD CRITERIA AND REJECTION OF BIDS. This contract will be awarded to the lowest responsive and responsible bidder considering conformity with the terms and conditions established by the Department in the rules, Invitation for Bids and contract documents. The issuance of plans and proposal forms for bidding based upon a prequalification rating shall not be the sole determinant of responsibility. The Department reserves the right to determine responsibility at the time of award, to reject any or all proposals, to readvertise the proposed improvement, and to waive technicalities.

By Order of the Illinois Department of Transportation

Randall S. Blankenhorn, Secretary

CONTRACT 97663

INDEX FOR SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS

Adopted January 1, 2018

This index contains a listing of SUPPLEMENTAL SPECIFICATIONS, frequently used RECURRING SPECIAL PROVISIONS, and LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS.

ERRATA Standard Specifications for Road and Bridge Construction (Adopted 4-1-16) (Revised 1-1-18)

SUPPLEMENTAL SPECIFICATIONS

Std. Spec. Sec. Page No. Control of Materials..... Bituminous Surface Treatment (Class A-1, A-2, A-3) Engineer's Field Office and Laboratory 40 Work Zone Traffic Control and Protection 41 Raised Reflective Pavement Markers 44 Pedestrian Push-Button 45 Fine Aggregates 46 Coarse Aggregates 47 Portland Cement Concrete 51 Hot-Mix Asphalt Equipment 59

CHECK SHEET FOR RECURRING SPECIAL PROVISIONS

The following RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

RECURRING SPECIAL PROVISIONS

<u>CHI</u>	ECK	<u>SHEET #</u>	PAGE NO.
1	Х	Additional State Requirements for Federal-Aid Construction Contracts	64
2	Х	Subletting of Contracts (Federal-Aid Contracts)	67
3	Х	EEO	68
4		Specific EEO Responsibilities Non Federal-Aid Contracts	78
5		Required Provisions - State Contracts	83
6		Asbestos Bearing Pad Removal	89
7		Asbestos Waterproofing Membrane and Asbestos HMA Surface Removal	90
8		Temporary Stream Crossings and In-Stream Work Pads	91
9		Construction Layout Stakes Except for Bridges	92
10		Construction Layout Stakes	95
11		Use of Geotextile Fabric for Railroad Crossing	98
12		Subsealing of Concrete Pavements	100
13		Hot-Mix Asphalt Surface Correction	104
14		Pavement and Shoulder Resurfacing	106
15		Patching with Hot-Mix Asphalt Overlay Removal	107
16		Polymer Concrete	109
17		PVC Pipeliner	111
18		Bicycle Racks	112
19		Temporary Portable Bridge Traffic Signals	114
20		Work Zone Public Information Signs	116
21		Nighttime Inspection of Roadway Lighting	117
22		English Substitution of Metric Bolts	118
23		Calcium Chloride Accelerator for Portland Cement Concrete	119
24		Quality Control of Concrete Mixtures at the Plant	120
25		Quality Control/Quality Assurance of Concrete Mixtures	128
26		Digital Terrain Modeling for Earthwork Calculations	144
27		Reserved	146
28		Preventive Maintenance – Bituminous Surface Treatment (A-1)	147
29		Reserved	153
30		Reserved	154
31		Reserved	155
32		Temporary Raised Pavement Markers	156
33		Restoring Bridge Approach Pavements Using High-Density Foam	157
34		Portland Cement Concrete Inlay or Overlay	160
35		Portland Cement Concrete Partial Depth Hot-Mix Asphalt Patching	164

CHECK SHEET FOR LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS

The following LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS

CHECK SHEET # PAGE NO.						
LRS 1 Reserved	168					
LRS 2 Furnished Excavation	169					
LRS 3 🛛 Work Zone Traffic Control Surveillance	170					
LRS 4 🛛 Flaggers in Work Zones	171					
LRS 5 Contract Claims	172					
LRS 6 Didding Requirements and Conditions for Contract Proposals	173					
LRS 7 Didding Requirements and Conditions for Material Proposals	179					
LRS 8 Reserved	185					
LRS 9 Dituminous Surface Treatments	186					
LRS 10 Reserved						
LRS 11 🔲 Employment Practices						
LRS 12 🔲 Wages of Employees on Public Works						
LRS 13 🔲 Selection of Labor	192					
LRS 14 🔲 Paving Brick and Concrete Paver Pavements and Sidewalks	193					
LRS 15 🗌 Partial Payments	196					
LRS 16 Protests on Local Lettings	197					
LRS 17 🗌 Substance Abuse Prevention Program	198					
LRS 18 🔲 Multigrade Cold Mix Asphalt	199					

SPECIAL PROVISIONS

INTERSECTION IMPROVEMENTS MARKET PLACE AND PLAZA DRIVE FAU ROUTE 9326 (MARKET PLACE) SECTION: 14-00042-00-PV PROJECT: VQW9(866) FAIRVIEW HEIGHTS, ILLINOIS

INDEX TO SPECIAL PROVISIONS

DESCRIPTION OF WORK	1
SHOP DRAWINGS	1
CONSTRUCTION STAKING	2
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT	3
SEQUENCE OF CONSTRUCTION OPERATIONS	
TRAFFIC CONTROL PLAN	
PUBLIC NOTICE	
TRENCH BACKFILL	5
INCIDENTAL HOT-MIX ASPHALT SURFACING	6
PORTLAND CEMENT CONCRETE PAVEMENT (JOINTED) THICKNESS SPECIFIE	ED6
TIE BARS & REINFORCEMENT BARS	7
EXPANSION JOINTS	7
DETECTABLE WARNINGS	8
STORM SEWER REMOVAL, SIZE SPECIFIED	9
TYPE 3 FRAME AND GRATE	
CONSTRUCTION AND MAINTENANCE SIGN SUPPORTS	
CHANGEABLE MESSAGE SIGN PROTECTION AND RESTORATION OF TRAFFIC SIGNS	. 10
SIGN PANEL TYPE 1 AND TELESCOPING STEEL SIGN SUPPORT	
DETECTOR LOOP REPLACEMENT	
REMOVE AND REINSTALL LIGHTING EQUIPMENT	
CONCRETE CURB (SPECIAL)	. 12
TRAFFIC CONTROL AND PRÓTECTION, (SPECIAL)	
TEMPORARY PAVEMENT MARKING REMOVAL	
DRAINAGE STRUCTURE ADJUSTMENT (SPECIAL)	
PAINT CURB STATUS OF UTILITIES TO BE ADJUSTED	. 14
STATUS OF UTILITIES TO BE ADJUSTED	. 15
LR107-4	
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	
SUBMITTAL OF EEO/LABOR DOCUMENTATION	
IDOT TPG	.20

BDE SPECIAL PROVISIONS

The following special provisions indicated by an "X" are applicable to this contract. An * indicates a new or revised special provision for the letting.

B0099 Accessible Pedestrian Signals (APS) April 1, 2003 Jan. 1, 2014 80382 22 Adjusting Frames and Grates April 1, 2017 April 1, 2017 April 1, 2018 April 1, 2016 April 1, 2010 April 1, 2016 April 1, 2010 April 1, 2016 April 1, 2016 <t< th=""><th></th><th><u>File</u> lame</th><th><u>Pg.</u></th><th>-</th><th>Special Provision Title</th><th>Effective</th><th><u>Revised</u></th></t<>		<u>File</u> lame	<u>Pg.</u>	-	Special Provision Title	Effective	<u>Revised</u>
80382 22 X Adjusting Frames and Grates April 1, 2017 80274 Aggregate Subgrade Improvement April 1, 2018 April 1, 2018 80173 Bituminous Materials Cost Adjustments Nov. 2, 2006 Aug. 1, 2017 80241 Bridge Demolition Debris July 1, 2009 April 1, 2010 50261 Building Removal-Case I (Non-Friable Asbestos) Sept. 1, 1990 April 1, 2010 50481 Building Removal-Case II (Non-Friable Asbestos) Sept. 1, 1990 April 1, 2010 50531 Building Removal-Case IV (No Asbestos) Sept. 1, 1990 April 1, 2010 80386 Calcium Aluminate Cement for Class PP-5 Concrete Patching July 1, 2016 80386 Calcium Aluminate Cement for Class PP-5 Concrete Patching June 2, 2017 80386 Compensable Delay Costs June 2, 2017 80381 Concrete Exclose for Pipe Culverts Jan. 1, 2018 80393 Concrete Exclose for Pipe Culverts Jan. 1, 2013 April 1, 2016 80377 Concrete Exclose for Pipe Culverts Jan. 1, 2013 April 1, 2016 80374 Z X Dosetearer <td>-</td> <td></td> <td></td> <td></td> <td>Accessible Pedestrian Signals (APS)</td> <td>April 1, 2003</td> <td>Jan. 1, 2014</td>	-				Accessible Pedestrian Signals (APS)	April 1, 2003	Jan. 1, 2014
80274 Aggregate Subgrade Improvement April 1, 2012 April 1, 2016 80192 Automated Flaggre Assistance Device Jan. 1, 2008 Aug. 1, 2017 80241 Bridge Demolition Debris Jun. 1, 2009 Aug. 1, 2017 80241 Bridge Demolition Debris July 1, 2009 April 1, 2010 50261 Building Removal-Case II (Non-Friable Asbestos) Sept. 1, 1990 April 1, 2010 50491 Building Removal-Case II (Friable Asbestos) Sept. 1, 1990 April 1, 2010 50531 Building Removal-Case II (Friable Asbestos) Sept. 1, 1990 April 1, 2010 80386 Calcium Aluminate Cement for Class PP-5 Concrete Patching July 1, 2016 Nov. 1, 2017 80386 Canpletion Date (via calendar days) June 2, 2017 Completion Date (via calendar days) April 1, 2008 80311 Concrete MX Design Files Concrete MX Design Files 5 April 1, 2016 April 1, 2016 80271 Concrete MX Design Files Concrete MX Design Files 5 April 1, 2016 April 1, 2016 80311 Concrete MX Design Files Concrete MX Design Files Concrete MX Design Files Concrete MX Design Percent Within Linis June 1, 2012 April 1, 2			22	Х			
80173 Bituminous Materials Cost Adjustments Nov. 2, 2006 Aug. 1, 2017 80241 Bridge Demolition Debris July 1, 2009 April 1, 2010 50261 Building Removal-Case II (Non-Friable Asbestos) Sept. 1, 1990 April 1, 2010 50481 Building Removal-Case II (Friable Asbestos) Sept. 1, 1990 April 1, 2010 50531 Building Removal-Case IV (No Asbestos) Sept. 1, 1990 April 1, 2010 80386 Editum Anuminate Cament for Class PP-5 Concrete Patching Nov. 1, 2017 80386 Calcium Aluminate Cament for Class PP-5 Concrete Patching Nov. 1, 2018 80384 24 Complexiton Date (via calendar days) June 2, 2017 80198 Complexiton Date (via calendar days) June 2, 2017 80381 Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2008 80231 Concrete Cox Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2016 80261 28 Concrete Rox Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2016 80261 28 Concrete Rox Culverts with Skews > 30 Degrees and Design Fills ≤ 1 April 1, 2016		80274				•	April 1, 2016
80241 Bridge Demolition Debris July 1, 2009 July 1, 2009 50261 Building Removal-Case II (Non-Friable Asbestos) Sept. 1, 1990 April 1, 2010 50481 Building Removal-Case II (Non-Friable Asbestos) Sept. 1, 1990 April 1, 2010 50491 Building Removal-Case IV (No Asbestos) Sept. 1, 1990 April 1, 2010 80386 Calcium Aluminate Cament for Class PP-5 Concrete Patching July 1, 2016 80386 Calcium Aluminate Cament for Class PP-5 Concrete Patching June 2, 2017 80386 Calcium Aluminate Cament for Class PP-5 Concrete Patching June 2, 2017 80386 Completion Date (via calendar days) April 1, 2008 80199 Completion Date (via calendar days) April 1, 2008 80293 Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2016 80217 Concrete Mix Design – Department Provided Jan. 1, 2013 April 1, 2016 80277 Concrete Mix Design – Department Provided Jan. 1, 2014 April 3, 2016 80378 42 X Desidvantaged Business Enterprise Participation Sept. 1, 2000 July 2, 2016 <td< td=""><td></td><td>80192</td><td></td><td></td><td></td><td>•</td><td>•</td></td<>		80192				•	•
50261 Building Removal-Case II (Non-Friable and Friable Asbestos) Sept. 1, 1990 April 1, 2010 50481 Building Removal-Case III (Non-Friable Asbestos) Sept. 1, 1990 April 1, 2010 50531 Building Removal-Case III (Non-Friable Asbestos) Sept. 1, 1990 April 1, 2010 80366 But Joints July 1, 2016 Sept. 1, 1990 April 1, 2010 80386 Calcium Aluminate Cement for Class PP-5 Concrete Patching Nov. 1, 2017 80386 Calcium Aluminate Cement for Class PP-5 Concrete Patching June 2, 2017 80386 Canpletion Date (via calendar days) June 3, 2017 80387 Completion Date (via calendar days) Plus Working Days April 1, 2008 80311 Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2016 April 1, 2016 80327 Concrete Mix Design – Department Provided Jan. 1, 2013 April 1, 2016 80378 Z Construction Air Quality – Diesel Retrofit June 1, 2010 Nov. 1, 2017 80388 Y Eguipment Parking and Storage Nov. 1, 2017 July 2, 2016 80387 Z Dowel Bar Inserter Jan. 1, 2010 April 1, 2018		80173				Nov. 2, 2006	Aug. 1, 2017
50481 Building Removal-Case II (Non-Friable Asbestos) Sept. 1, 1990 April 1, 2010 50491 Building Removal-Case II (Non-Friable Asbestos) Sept. 1, 1990 April 1, 2010 80366 Calcium Aluminate Cement for Class PP-5 Concrete Patching July 1, 2016 80386 Calcium Aluminate Cement for Class PP-5 Concrete Patching July 1, 2016 80384 24 Compensable Delay Costs Jun 2, 2017 80398 Completion Date (via calendar days) April 1, 2008 80199 Completion Date (via calendar days) April 1, 2012 80293 Concrete Box Culverts with Skews > 30 Degrees and Design Fills \$ 5 April 1, 2016 80217 Concrete Ind Sections for Pipe Culverts Jan. 1, 2013 April 1, 2016 80221 Construction Air Quality – Diesel Retrofit June 1, 2010 Nov. 1, 2014 80384 42 X Construction Air Quality – Diesel Retrofit June 1, 2010 Nov. 1, 2014 80391 Concrete Maxing and Storage Nov. 1, 2017 Fuel Cost Adjustment April 1, 2016 80388 49 Equipment Parking and Storage Nov. 1, 2017 Nov. 1, 2017 80384 42 Dowel Bar Inserter Jan. 1,		80241			Bridge Demolition Debris	July 1, 2009	-
50491 Building Removal-Case III (Friable Asbestos) Sept. 1, 1990 April 1, 2010 80386 Butt Joints July 1, 2016 April 1, 2010 80386 Calcium Aluminate Cement for Class PP-5 Concrete Patching Nov. 1, 2017 80386 Calcium Aluminate Cement for Class PP-5 Concrete Patching June 2, 2017 80384 24 Compensable Delay Costs June 2, 2017 80198 Completion Date (via calendar days) Plus Working Days April 1, 2008 80293 Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2016 80311 Concrete End Sections for Pipe Culverts Jan. 1, 2013 April 1, 2016 80277 Contracte Mix Design – Department Provided Jan. 1, 2014 April 1, 2016 80261 28 Construction Af Quality – Disel Retrofit June 1, 2010 Nov. 1, 2014 80387 42 X Dowel Bar Inserter Jan. 1, 2017 Jan. 1, 2018 80378 42 X Dowel Bar Inserter Jan. 1, 2017 Jan. 1, 2017 80378 42 X Dowel Bar Inserter Jan. 1, 2017 Jan. 1, 2018 80388 49 X Equipment		5026l			Building Removal-Case I (Non-Friable and Friable Asbestos)	Sept. 1, 1990	April 1, 2010
50531 Building Removal-Case IV (No Asbestos) Sept. 1, 1990 April 1, 2010 80386 Calcium Aluminate Cement for Class PP-5 Concrete Patching Nov. 1, 2017 80386 Calsa A and B Patching Jan. 1, 2018 80384 24 X Compensable Delay Costs June 2, 2017 80198 Completion Date (via calendar days) Plus Working Days April 1, 2008 80293 Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2012 July 1, 2016 80311 Concrete End Sections for Pipe Culverts Jan. 1, 2012 April 1, 2016 802217 Construction Air Quality – Diesel Retrofit June 1, 2010 Nov. 1, 2017 80221 28 Construction Air Quality – Diesel Retrofit Jan. 1, 2017 Nov. 1, 2017 80229 11 Z Disadvantaged Busiment April 1, 2016 April 1, 2016 80388 49 X Equipment Parking and Storage Nov. 1, 2017 Jan. 1, 2017 Jan. 1, 2018 80388 49 X Equipment Parking and Storage Nov. 1, 2017 Nov. 1, 2017 Nov. 1, 2017 80383 Hot-Mix Asphalt – Density Testing of Longitudinal Joints Jan. 1, 2010		5048I				Sept. 1, 1990	April 1, 2010
80386Butt JointsJuly 1, 201680386Calcium Aluminate Cement for Class PP-5 Concrete PatchingNov. 1, 201780386Class A and B PatchingJan. 1, 20188038424XCompletion Date (via calendar days)April 1, 200880199Completion Date (via calendar days) Plus Working DaysApril 1, 200880293Completion Date (via calendar days) Plus Working DaysApril 1, 201380311Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5April 1, 201380277Concrete End Sections for Pipe CulvertsJan. 1, 2013April 1, 201680277Concrete Mix Design – Department ProvidedJan. 1, 2011April 1, 201680287Construction Air Quality – Diesel RetrofitJune 1, 2010Nov. 1, 201780287SequenceJan. 1, 2017Nov. 1, 201780287April R (Justavantaged Business Enterprise ParticipationSept. 1, 2000July 2, 2016* 8037842Dowel Bar InserterJan. 1, 2017Jan. 1, 20188038449XEquipment Parking and StorageNov. 1, 2017Nov. 1, 20178024650Hot-Mix Asphalt – Density Testing of Longitudinal JointsJan. 1, 2014Jan. 1, 201880383Hot-Mix Asphalt – Davity Control for PerformanceApril 1, 2017Nov. 1, 20178037651XHot-Mix Asphalt – Curstify Ortrol for PerformanceApril 1, 2014Jan. 1, 201880383Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 2018Jan. 1, 201880394Matriel Tr		5049I			Building Removal-Case III (Friable Asbestos)	Sept. 1, 1990	April 1, 2010
80386 Calcium Aluminate Cement for Class PP-5 Concrete Patching Nov. 1, 2017 80384 24 Cass A and B Patching Jan. 1, 2018 80384 24 X Compensable Delay Costs April 1, 2008 80198 Completion Date (via calendar days) Plus Working Days April 1, 2008 80293 Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2012 July 1, 2016 80311 Concrete End Sections for Pipe Culverts Jan. 1, 2013 April 1, 2016 80277 Concrete End Sections for Pipe Culverts Jan. 1, 2017 April 1, 2016 80277 Concrete Mix Design – Department Provided Jan. 1, 2017 Nov. 1, 2017 80378 42 X Construction Air Quality – Diesel Retroft June 1, 2010 Nov. 1, 2017 80384 9 X Equipment Parking and Storage Nov. 1, 2017 Jan. 1, 2017 Nov. 1, 2017 80384 9 X Equipment Parking and Storage Nov. 1, 2014 April 1, 2016 80384 9 X Equipment Parking and Storage Nov. 1, 2014 April 1, 2016 80383 Hot-Mix Asphalt – Density Testing of Longitudinal Joints <		5053I			Building Removal-Case IV (No Asbestos)	Sept. 1, 1990	April 1, 2010
* 80396 Class A and B Patching Jan. 1, 2018 80384 24 X Completion Date (via calendar days) April 1, 2008 80199 Completion Date (via calendar days) April 1, 2008 April 1, 2008 80199 Completion Date (via calendar days) Plus Working Days April 1, 2016 80311 Concrete Dox Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2012 April 1, 2016 80277 Concrete Mix Design – Department Provided Jan. 1, 2013 April 1, 2016 80287 Construction Air Quality – Diseal Retrofit June 1, 2010 Nov. 1, 2014 80387 Contrast Preformed Plastic Pavement Marking Nov. 1, 2017 Jan. 1, 2017 Jan. 1, 2018 80378 42 X Dowel Bar Inserter Jan. 1, 2017 Mov. 1, 2017 80388 49 X Equipment Parking and Storage Nov. 1, 2017 Nov. 1, 2017 80380 4 X Dowel Bar Inserter Jan. 1, 2018 Nov. 1, 2014 Jan. 1, 2018 80383 49 X Equipment Parking and Storage Nov. 1, 2017 Nov. 1, 2017 80384 45 X <t< td=""><td></td><td></td><td></td><td></td><td>Butt Joints</td><td>July 1, 2016</td><td></td></t<>					Butt Joints	July 1, 2016	
80384 24 X Competable Delay Costs June 2, 2017 80198 Completion Date (via calendar days) April 1, 2008 80293 Completion Date (via calendar days) April 1, 2008 80293 Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2012 July 1, 2016 80311 Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2013 April 1, 2016 80277 Construction Air Quality - Dissel Retrofit Jan. 1, 2013 April 1, 2016 80287 Construction Air Quality - Dissel Retrofit Jan. 1, 2017 Nov. 1, 2017 80388 42 X Dowel Bart Inserter Jan. 1, 2017 Nov. 1, 2017 80388 49 X Equipment Parking and Storage Nov. 1, 2017 Nov. 1, 2017 80388 49 X Equipment Parking and Storage Nov. 1, 2017 Nov. 1, 2017 80388 49 X Equipment Parking and Storage Nov. 1, 2014 Jan. 1, 2018 Jan. 1, 2018 80388 49 X Equipment Parking and Storage Nov. 1, 2017 Nov. 1, 2017 80383 Hot-Mix Asphatt – Density Testing of Longitudi							
80198 Completion Date (via calendar days) April 1, 2008 80199 Completion Date (via calendar days) Plus Working Days April 1, 2008 80293 Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2013 80311 Concrete End Sections for Pipe Culverts Jan. 1, 2013 April 1, 2016 80261 28 Concrete Mix Design – Department Provided Jan. 1, 2011 Nov. 1, 2014 80387 Construction Air Quality – Diesel Retrofit June 1, 2010 Nov. 1, 2014 80387 Constrated Business Enterprise Participation Sept. 1, 2000 July 2, 2016 80378 42 X Dowel Bar Inserter Jan. 1, 2017 Jan. 1, 2017 80384 49 X Equipment Parking and Storage Nov. 1, 2017 80304 Grooving for Recessed Pavement Markings Nov. 1, 2012 Nov. 1, 2017 80304 Grooving for Recessed Pavement Markings Nov. 1, 2010 April 1, 2016 80383 Hot-Mix Asphalt – Density Testing of Longitudinal Joints Jan. 1, 2018 Jobsite Sampling 80383 Hot-Mix Asphalt – Quality Control for Performance April 1, 2014 April 1, 2016 80384 <td< td=""><td>*</td><td></td><td></td><td></td><td></td><td></td><td></td></td<>	*						
80199 80293Completion Date (via calendar days) Plus Working Days Concrete Box Culverts with Skews > 30 Degrees and Design Fills \$ 5 April 1, 2012April 1, 2013 			24	Х			
80293 Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5 April 1, 2012 July 1, 2016 80311 Concrete End Sections for Pipe Culverts Jan. 1, 2013 April 1, 2016 80287 Concrete Mix Design – Department Provided Jan. 1, 2012 April 1, 2016 80281 X Construction Air Quality – Diesel Retrofit June 1, 2010 Nov. 1, 2017 80383 Contrast Preformed Plastic Pavement Marking Nov. 1, 2017 July 2, 2016 80384 42 X Dowel Bar Inserter Jan. 1, 2017 July 2, 2016 80384 49 X Equipment Parking and Storage Nov. 1, 2017 Fuel Cost Adjustment April 1, 2009 Aug. 1, 2017 80344 Grooving for Recessed Pavement Markings Nov. 1, 2017 Nov. 1, 2017 Nov. 1, 2017 80345 Hot-Mix Asphalt – Pav for Performance Using Percent Within Limits - John. 1, 2016 April 1, 2016 April 1, 2016 80346 X Lingitts on Barricades Jan. 1, 2018 Nov. 1, 2017 80347 Hot-Mix Asphalt – Tack Coat Nov. 1, 2017 Nov. 1, 2017 80336 Lingitts on B						•	
FeetJan. 1, 2013April 1, 201680311Concrete End Sections for Pipe CulvertsJan. 1, 2013April 1, 20168026128Construction Air Quality – Diesel RetrofitJune 1, 2010Nov. 1, 201480387Contrast Preformed Plastic Pavement MarkingNov. 1, 2017Nov. 1, 20168037842XDowel Bar InserterJan. 1, 2017Jan. 1, 20178032931XDisadvantaged Business Enterprise ParticipationSept. 1, 2000July 2, 20168037842XDowel Bar InserterJan. 1, 2017Jan. 1, 20178038849XEquipment Parking and StorageNov. 1, 201780340Grooving for Recessed Pavement MarkingsNov. 1, 2017Nov. 1, 201780341Hot-Mix Asphalt – Density Testing of Longitudinal JointsJan. 1, 2010April 1, 201680383Hot-Mix Asphalt – Quality Control for PerformanceApril 1, 2017Nov. 1, 201780386Longitudinal Joint and Crack PatchingApril 1, 2018Nov. 1, 201780383Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 2018April 1, 201680384Material Transfer DeviceJan. 1, 2018April 1, 2016April 1, 201680383Material Transfer DeviceJan. 1, 2018April 1, 201680384Material Transfer DeviceJan. 1, 2018April 1, 201680385Material Transfer DeviceJan. 1, 2018April 1, 201680384Metal Flared End Section for Pipe CulvertsJan. 1, 201880165Mosture Cur							
80277Concrete Mix Design – Department ProvidedJan. 1, 2012April 1, 20168026128XConstruction Air Quality – Diesel RetrofitJune 1, 2010Nov. 1, 201480387Contrast Preformed Plastic Pavement MarkingNov. 1, 2017Sept. 1, 2000July 2, 2016*8037842XDowel Bar InserterJan. 1, 2017Jan. 1, 2017800229Fuel Cost AdjustmentApril 1, 2009Aug. 1, 20178038849XEquipment Parking and StorageNov. 1, 201780304Grooving for Recessed Pavement MarkingsNov. 1, 201780347Hot-Mix Asphati – Density Testing of Longitudinal JointsJan. 1, 201880383Hot-Mix Asphati – Pay for Performance Using Percent Within Limits - Jobsite SamplingNov. 1, 201780383Hot-Mix Asphati – Quality Control for PerformanceApril 1, 201480383Longitudinal Joint and Crack PatchingApril 1, 201480383Longitudinal Joint and Crack PatchingApril 1, 201480384Material Transfer DeviceJune 15, 1999Aug. 1, 201780385Material Transfer DeviceJune 15, 1999Aug. 1, 2016* 80394Metal Flared End Section for Pipe CulvertsJan. 1, 201880375S4XPavement Marking RemovalJuly 1, 2016* 80390S5XPavement Marking RemovalJuly 1, 2016* 80390S5XPavement ConcreteNov. 1, 201780376Portland Cement Concrete Bridge Deck CuringApril 1, 2016* 8039		80293				April 1, 2012	July 1, 2016
80277Concrete Mix Design – Department ProvidedJan. 1, 2012April 1, 20168026128Construction Air Quality – Diesel RetrofitJune 1, 2010Nov. 1, 20178002931XDisadvantaged Business Enterprise ParticipationSept. 1, 2000July 2, 2016*8037842XDowel Bar InserterJan. 1, 2017Jan. 1, 20178002931XDisadvantaged Business Enterprise ParticipationSept. 1, 2000July 2, 2016*8037842XDowel Bar InserterJan. 1, 2017Jan. 1, 201780229Fuel Cost AdjustmentApril 1, 2009Aug. 1, 20178024650XHot-Mix Asphati – Density Testing of Longitudinal JointsJan. 1, 201480383Hot-Mix Asphati – Pay for Performance Using Percent Within Limits - Jobsite SamplingNov. 1, 2017Nov. 1, 201780383Hot-Mix Asphati – Quality Control for PerformanceApril 1, 2018Nov. 1, 201780383Hot-Mix Asphati – Tack CoatNov. 1, 2018Nov. 1, 201780386Longitudinal Joint and Crack PatchingApril 1, 2014April 1, 2016* 80393Matholes, Valve Vaults, and Flat Slab TopsJan. 1, 2018April 1, 2016* 80394Material Transfer DeviceJune 15, 1999Aug. 1, 2017* 80394Metal Flared End Section for Pipe CulvertsJan. 1, 2018April 1, 2016* 80394Metal Flared End Section for Pipe CulvertsJan. 1, 2016Jan. 1, 2016* 8039055XPavement Marking RemovalJul		80311			Concrete End Sections for Pipe Culverts	Jan. 1, 2013	April 1, 2016
8026128XConstruction Air Quality – Diesel RetrofitJune 1, 2010Nov. 1, 201480387Contrast Preformed Plastic Pavement MarkingNov. 1, 2017802931XDisadvantaged Business Enterprise ParticipationSept. 1, 20008037842XDowel Bar InserterJan. 1, 201780229Fuel Cost AdjustmentApril 1, 2009Aug. 1, 20178024650XHot-Mix Asphalt – Density Testing of Longitudinal JointsJan. 1, 201080387Grooving for Recessed Pavement MarkingsNov. 1, 2017April 1, 201080347Hot-Mix Asphalt – Density Testing of Longitudinal JointsJan. 1, 2014Jan. 1, 201880383Hot-Mix Asphalt – Quality Control for PerformanceApril 1, 2017Nov. 1, 20178037651XHot-Mix Asphalt – Quality Control for PerformanceApril 1, 2017Nov. 1, 201780386Longitudinal Joint and Crack PatchingApril 1, 2014April 1, 2016Nov. 1, 20178039252XLights on BarricadesJan. 1, 2018Material Transfer DeviceJune 15, 1999Aug. 1, 201480393Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 2018Mosture Cured Urethane Paint SystemNov. 1, 2016April 1, 201680394Metail Flared End Section for Pipe CulvertsJan. 1, 2018April 1, 2016April 1, 201680394Metail Blackout TapeNov. 2, 2017April 1, 2016April 1, 20168039754XPavement Marking RemovalJuly 1, 2016April 1, 2017<		80277					•
8002931XDisadvantaged Business Enterprise ParticipationSept. 1, 2000July 2, 2016*8037842XDowel Bar InserterJan. 1, 2017Jan. 1, 2017Jan. 1, 20188038849XEquipment Parking and StorageNov. 1, 2017Jan. 1, 2017Jan. 1, 201780229Fuel Cost AdjustmentApril 1, 2009Aug. 1, 2017Nov. 1, 2012Nov. 1, 201780304Grooving for Recessed Pavement MarkingsNov. 1, 2012Nov. 1, 2017Nov. 1, 20178024650XHot-Mix Asphalt – Density Testing of Longitudinal JointsJan. 1, 2010April 1, 2016* 80347Hot-Mix Asphalt – Pay for Performance Using Percent Within Limits - Jobsite SamplingNov. 1, 2014April 1, 2017* 8037651XHot-Mix Asphalt – Tack CoatNov. 1, 2016* 80393Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 2018* 80394Material Transfer DeviceJune 15, 1999Aug. 1, 2016* 80394Metal Flared End Section for Pipe CulvertsJan. 1, 2018* 80349Pavement Marking Blackout TapeNov. 1, 2016* 8039154XPavement Marking RemovalJuly 1, 2016* 8039557XPortland Cement ConcreteNov. 1, 20178037558YPortland Cement Concrete Bridge Deck CuringApril 1, 20158030059XProgress PaymentsAug. 1, 20178032859XProgress Payment Marking Type D - InlaidApril 1, 2012803		80261	28	Х			•
* 80378 42 X Dowel Bar Inserter Jan. 1, 2017 Jan. 1, 2018 80388 49 X Equipment Parking and Storage Nov. 1, 2017 80299 Fuel Cost Adjustment April 1, 2009 Aug. 1, 2017 80240 Grooving for Recessed Pavement Markings Nov. 1, 2017 April 1, 2009 Aug. 1, 2017 80246 50 X Hot-Mix Asphalt – Density Testing of Longitudinal Joints Jan. 1, 2010 April 1, 2016 * 80347 Hot-Mix Asphalt – Pay for Performance Using Percent Within Limits - Jobsite Sampling Nov. 1, 2014 Jan. 1, 2018 * 80376 51 X Hot-Mix Asphalt – Tack Coat Nov. 1, 2016 * 80392 52 X Lights on Barricades Jan. 1, 2018 * 80393 Manholes, Valve Vaults, and Flat Slab Tops Jan. 1, 2018 April 1, 2014 * 80394 Metai Flared End Section for Pipe Culverts Jan. 1, 2018 Jan. 1, 2018 * 80394 Metai Flared End Section for Pipe Culverts Jan. 1, 2016 April 1, 2016 *		80387					
8038849XEquipment Parking and StorageNov. 1, 201780229Fuel Cost AdjustmentApril 1, 2009Aug. 1, 201780304Grooving for Recessed Pavement MarkingsNov. 1, 2012Nov. 1, 20128024650XHot-Mix Asphalt – Density Testing of Longitudinal JointsJan. 1, 2010April 1, 2016*80347Hot-Mix Asphalt – Pay for Performance Using Percent Within Limits - Jobsite SamplingNov. 1, 2014Jan. 1, 201880383Hot-Mix Asphalt – Quality Control for PerformanceApril 1, 2017Nov. 1, 20178037651XHot-Mix Asphalt – Tack CoatNov. 1, 201880386Longitudinal Joint and Crack PatchingApril 1, 2014April 1, 2016*80393Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 201880045Material Transfer DeviceJune 15, 1999Aug. 1, 201080364Motatrial Transfer DeviceJune 15, 1999Aug. 1, 201080349Pavement Marking Blackout TapeNov. 1, 2016Jan. 1, 2016*8039055XPayments to SubcontractorsNov. 1, 2016*8039055Payments to SubcontractorsNov. 1, 20178037756XPortland Cement ConcreteNov. 1, 201780375S8Portland Cement Concrete SidewalkAug. 1, 20178038957XPortland Cement Concrete SidewalkAug. 1, 20178038959XProgress PaymentsMarking Type D - InlaidApril 1, 201780329 <td< td=""><td></td><td>80029</td><td>31</td><td>Х</td><td>Disadvantaged Business Enterprise Participation</td><td>Sept. 1, 2000</td><td>July 2, 2016</td></td<>		80029	31	Х	Disadvantaged Business Enterprise Participation	Sept. 1, 2000	July 2, 2016
80229Fuel Cost AdjustmentApril 1, 2009Aug. 1, 201780304Grooving for Recessed Pavement MarkingsNov. 1, 2012Nov. 1, 20128024650XHot-Mix Asphalt – Density Testing of Longitudinal JointsJan. 1, 2010April 1, 2016* 80347Hot-Mix Asphalt – Dansity Testing of Performance Using Percent Within Limits - Jobsite SamplingNov. 1, 2014Jan. 1, 201880383Hot-Mix Asphalt – Quality Control for PerformanceApril 1, 2017Nov. 1, 20178037651XHot-Mix Asphalt – Tack CoatNov. 1, 2016* 8039252XLights on BarricadesJan. 1, 201880336Longitudinal Joint and Crack PatchingApril 1, 2014April 1, 2014* 80393Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 201880045Material Transfer DeviceJune 15, 1999Aug. 1, 2010* 80394Metail Flared End Section for Pipe CulvertsJan. 1, 201880165Moisture Cured Urethane Paint SystemNov. 1, 2014April 1, 2016* 8039055XPavement Marking RemovalJuly 1, 2016* 8039055XPavement Marking RemovalJuly 1, 2016* 8039055XPortland Cement ConcreteNov. 1, 20178037756XPortland Cement Concrete Bridge Deck CuringApril 1, 2015Nov. 1, 20178038957XPortland Cement Concrete Bridge Deck CuringApril 1, 2015Nov. 1, 20178038958XPortland Cement Concrete Bridge Deck Curing	*	80378	42	Х	Dowel Bar Inserter	Jan. 1, 2017	Jan. 1, 2018
80304Grooving for Recessed Pavement MarkingsNov. 1, 2012Nov. 1, 20178024650XHot-Mix Asphalt – Density Testing of Longitudinal JointsJan. 1, 2010April 1, 2016*80347Hot-Mix Asphalt – Pay for Performance Using Percent Within Limits - Jobsite SamplingNov. 1, 2017Nov. 1, 201780383Hot-Mix Asphalt – Quality Control for PerformanceApril 1, 2017Nov. 1, 20178037651XHot-Mix Asphalt – Tack CoatNov. 1, 2016*8039252XLights on BarricadesJan. 1, 201880336Longitudinal Joint and Crack PatchingApril 1, 2014April 1, 2014*80393Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 201880045Material Transfer DeviceJune 15, 1999Aug. 1, 2014*80349Metal Flared End Section for Pipe CulvertsJan. 1, 201880165Moisture Cured Urethane Paint SystemNov. 1, 2006Jan. 1, 2016*8039055XPavement Marking RemovalJuly 1, 2016*8039055XPortable Changeable Message SignsNov. 1, 20178037756XPortable Changeable Message SignsNov. 1, 20178038558XPortland Cement ConcreteNov. 1, 20178038558XPortland Cement Concrete Bridge Deck CuringApril 1, 20158038957XPortland Cement Concrete Bridge Deck CuringApril 1, 20178038558XPortland Cement Concrete Sidewa		80388	49	Х	Equipment Parking and Storage	Nov. 1, 2017	
8024650XHot-Mix Asphalt – Density Testing of Longitudinal JointsJan. 1, 2010April 1, 2016*80347Hot-Mix Asphalt – Pay for Performance Using Percent Within Limits - Jobsite SamplingNov. 1, 2014Jan. 1, 201880383Hot-Mix Asphalt – Quality Control for PerformanceApril 1, 2017Nov. 1, 20178037651XHot-Mix Asphalt – Tack CoatNov. 1, 2016*8038252XLights on BarricadesJan. 1, 201880366Longitudinal Joint and Crack PatchingApril 1, 2014April 1, 2016*80393Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 201880045Material Transfer DeviceJune 15, 1999Aug. 1, 2014*80349Metal Flared End Section for Pipe CulvertsJan. 1, 201480165Moisture Cured Urethane Paint SystemNov. 1, 2014April 1, 2016*8039055XPayment Marking Blackout TapeNov. 1, 20148037756XPortland Cement ConcreteNov. 1, 201780359Portland Cement Concrete Bridge Deck CuringApril 1, 2016April 1, 201780359XPortland Cement Concrete SidewalkAug. 1, 20178032959XProgress PaymentsNov. 2, 2013		80229			Fuel Cost Adjustment	April 1, 2009	Aug. 1, 2017
*80347Hot-Mix Asphalt – Pay for Performance Using Percent Within Limits - Jobsite SamplingNov. 1, 2014Jan. 1, 201880383 80383 80386Hot-Mix Asphalt – Quality Control for PerformanceApril 1, 2017Nov. 1, 20178037651XHot-Mix Asphalt – Tack CoatNov. 1, 2016Nov. 1, 2016*8039252XLights on BarricadesJan. 1, 2018April 1, 2014April 1, 2014*80336Longitudinal Joint and Crack PatchingJan. 1, 2018Matholes, Valve Vaults, and Flat Slab TopsJan. 1, 2018*80394Material Transfer DeviceJune 15, 1999Aug. 1, 2014*80394Metal Flared End Section for Pipe CulvertsJan. 1, 201880165Moisture Cured Urethane Paint SystemNov. 1, 2006Jan. 1, 2016*8039055XPayement Marking Blackout TapeNov. 1, 2014*8039055XPayments to SubcontractorsNov. 2, 20178037756XPortland Cement ConcreteNov. 1, 20178038957XPortland Cement Concrete Sidege Deck CuringApril 1, 201580300RPortland Cement Concrete SidewalkAug. 1, 20178038558XPortland Cement Marking Type D - InlaidApril 1, 20128032059XProgress PaymentsNov. 2, 2013		80304			Grooving for Recessed Pavement Markings	Nov. 1, 2012	Nov. 1, 2017
Jobsite Sampling80383Hot-Mix Asphalt – Quality Control for PerformanceApril 1, 2017Nov. 1, 20178037651XHot-Mix Asphalt – Tack CoatNov. 1, 2016*8039252XLights on BarricadesJan. 1, 201880336Longitudinal Joint and Crack PatchingApril 1, 2014April 1, 2014*80393Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 201880045Material Transfer DeviceJune 15, 1999Aug. 1, 2014*80394Metal Flared End Section for Pipe CulvertsJan. 1, 201880165Moisture Cured Urethane Paint SystemNov. 1, 2006Jan. 1, 20168037154XPavement Marking Blackout TapeNov. 1, 2016*8039055XPayments to SubcontractorsNov. 2, 20178037756XPortland Cement ConcreteNov. 1, 20178038957XPortland Cement Concrete Bridge Deck CuringApril 1, 2015Nov. 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 201780300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013		80246	50	Х	Hot-Mix Asphalt – Density Testing of Longitudinal Joints	Jan. 1, 2010	April 1, 2016
80383Hot-Mix Asphalt – Quality Control for PerformanceApril 1, 2017Nov. 1, 20178037651XHot-Mix Asphalt – Tack CoatNov. 1, 2016*8039252XLights on BarricadesJan. 1, 201880336Longitudinal Joint and Crack PatchingApril 1, 2014April 1, 2014*80393Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 201880045Material Transfer DeviceJune 15, 1999Aug. 1, 2014*80394Metal Flared End Section for Pipe CulvertsJan. 1, 201880165Moisture Cured Urethane Paint SystemNov. 1, 2006Jan. 1, 201080349Pavement Marking Blackout TapeNov. 1, 2014April 1, 2016*8039055XPayments to SubcontractorsNov. 2, 20178037756XPortland Cement ConcreteNov. 1, 2017April 1, 20178038957XPortland Cement Concrete Bridge Deck CuringApril 1, 2017Nov. 1, 20178038558XPortland Cement Concrete Bridge Deck CuringApril 1, 2017April 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 2017April 1, 201680300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013April 1, 2016	*	80347				Nov. 1, 2014	Jan. 1, 2018
*8039252XLights on BarricadesJan. 1, 201880336Longitudinal Joint and Crack PatchingApril 1, 2014April 1, 2016*80393Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 201880045Material Transfer DeviceJune 15, 1999Aug. 1, 2014*80394Metal Flared End Section for Pipe CulvertsJan. 1, 201880165Moisture Cured Urethane Paint SystemNov. 1, 2006Jan. 1, 201080349Pavement Marking Blackout TapeNov. 1, 2014April 1, 2016*8039055XPayments to SubcontractorsNov. 2, 20178037756XPortable Changeable Message SignsNov. 1, 2016April 1, 20178038957XPortland Cement ConcreteNov. 1, 2017April 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 2017April 1, 20178032859XProgress PaymentsNarking Type D - InlaidApril 1, 2012April 1, 2016		80383				April 1, 2017	Nov. 1, 2017
80336Longitudinal Joint and Crack PatchingApril 1, 2014April 1, 2014*80393Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 201880045Material Transfer DeviceJune 15, 1999Aug. 1, 2014*80394Metal Flared End Section for Pipe CulvertsJan. 1, 201880165Moisture Cured Urethane Paint SystemNov. 1, 2006Jan. 1, 201080349Pavement Marking Blackout TapeNov. 1, 2014April 1, 2016*8039055XPayments to SubcontractorsNov. 2, 20178037756XPortland Cement ConcreteNov. 1, 2016April 1, 201780359Portland Cement Concrete Bridge Deck CuringApril 1, 2017Nov. 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 201780300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013April 1, 2016		80376	51	Х	Hot-Mix Asphalt – Tack Coat	Nov. 1, 2016	
*80393 80045Manholes, Valve Vaults, and Flat Slab TopsJan. 1, 201880045Material Transfer DeviceJune 15, 1999Aug. 1, 2014*80394Metal Flared End Section for Pipe CulvertsJan. 1, 201880165Moisture Cured Urethane Paint SystemNov. 1, 2006Jan. 1, 201080349Pavement Marking Blackout TapeNov. 1, 2014April 1, 2016*8039055XPayments to SubcontractorsNov. 2, 20178037756XPortable Changeable Message SignsNov. 1, 2016April 1, 20178038957XPortland Cement ConcreteNov. 1, 2017April 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 2017Nov. 1, 201780300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013April 1, 2016	*	80392	52	Х	Lights on Barricades	Jan. 1, 2018	
80045Material Transfer DeviceJune 15, 1999Aug. 1, 2014*80394Metal Flared End Section for Pipe CulvertsJan. 1, 201880165Moisture Cured Urethane Paint SystemNov. 1, 2006Jan. 1, 201080349Pavement Marking Blackout TapeNov. 1, 2014April 1, 20168037154XPavement Marking RemovalJuly 1, 2016*8039055XPayments to SubcontractorsNov. 2, 20178037756XPortable Changeable Message SignsNov. 1, 2016April 1, 20178038957XPortland Cement ConcreteNov. 1, 2017April 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 2017Nov. 1, 201780300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013April 1, 2016		80336			Longitudinal Joint and Crack Patching	April 1, 2014	April 1, 2016
*80394Metal Flared End Section for Pipe CulvertsJan. 1, 201880165Moisture Cured Urethane Paint SystemNov. 1, 2006Jan. 1, 201080349Pavement Marking Blackout TapeNov. 1, 2014April 1, 20168037154XPavement Marking RemovalJuly 1, 2016*8039055XPayments to SubcontractorsNov. 2, 20178037756XPortable Changeable Message SignsNov. 1, 2016April 1, 20178038957XPortland Cement ConcreteNov. 1, 2017April 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 2017Nov. 1, 201780300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013April 1, 2016	*	80393			Manholes, Valve Vaults, and Flat Slab Tops	Jan. 1, 2018	
80165Moisture Cured Urethane Paint SystemNov. 1, 2006Jan. 1, 201080349Pavement Marking Blackout TapeNov. 1, 2014April 1, 20168037154XPavement Marking RemovalJuly 1, 2016*8039055XPayments to SubcontractorsNov. 2, 20178037756XPortable Changeable Message SignsNov. 1, 2016April 1, 20178038957XPortland Cement ConcreteNov. 1, 2017April 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 2017Nov. 1, 201780300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013April 1, 2016		80045			Material Transfer Device	June 15, 1999	Aug. 1, 2014
80349Pavement Marking Blackout TapeNov. 1, 2014April 1, 20168037154XPavement Marking RemovalJuly 1, 2016*8039055XPayments to SubcontractorsNov. 2, 20178037756XPortable Changeable Message SignsNov. 1, 2016April 1, 20178038957XPortland Cement ConcreteNov. 1, 2017April 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 2017Nov. 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 2017April 1, 201680300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013April 1, 2013	*	80394			Metal Flared End Section for Pipe Culverts	Jan. 1, 2018	
8037154XPavement Marking RemovalJuly 1, 2016*8039055XPayments to SubcontractorsNov. 2, 20178037756XPortable Changeable Message SignsNov. 1, 2016April 1, 20178038957XPortland Cement ConcreteNov. 1, 2017Nov. 1, 201780359Portland Cement Concrete Bridge Deck CuringApril 1, 2015Nov. 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 201780300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013		80165			Moisture Cured Urethane Paint System	Nov. 1, 2006	Jan. 1, 2010
*8039055XPayments to SubcontractorsNov. 2, 20178037756XPortable Changeable Message SignsNov. 1, 2016April 1, 20178038957XPortland Cement ConcreteNov. 1, 2017Nov. 1, 201780359Portland Cement Concrete Bridge Deck CuringApril 1, 2015Nov. 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 201780300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013		80349			Pavement Marking Blackout Tape	Nov. 1, 2014	April 1, 2016
8037756XPortable Changeable Message SignsNov. 1, 2016April 1, 20178038957XPortland Cement ConcreteNov. 1, 2017Nov. 1, 201780359Portland Cement Concrete Bridge Deck CuringApril 1, 2015Nov. 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 201780300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013		80371	54	Х	Pavement Marking Removal	July 1, 2016	
8038957XPortland Cement ConcreteNov. 1, 201780359Portland Cement Concrete Bridge Deck CuringApril 1, 2015Nov. 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 201780300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013	*	80390	55	Х	Payments to Subcontractors	Nov. 2, 2017	
80359Portland Cement Concrete Bridge Deck CuringApril 1, 2015Nov. 1, 20178038558XPortland Cement Concrete SidewalkAug. 1, 201780300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013		80377	56	Х	Portable Changeable Message Signs	Nov. 1, 2016	April 1, 2017
8038558XPortland Cement Concrete SidewalkAug. 1, 201780300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013		80389	57	Х	Portland Cement Concrete	Nov. 1, 2017	
80300Preformed Plastic Pavement Marking Type D - InlaidApril 1, 2012April 1, 20168032859XProgress PaymentsNov. 2, 2013		80359			Portland Cement Concrete Bridge Deck Curing	April 1, 2015	Nov. 1, 2017
80328 59 X Progress Payments Nov. 2, 2013		80385	58	Х	Portland Cement Concrete Sidewalk	Aug. 1, 2017	
		80300			Preformed Plastic Pavement Marking Type D - Inlaid	April 1, 2012	April 1, 2016
0400L Deline d Destactive Liebility lasymenes		80328	59	Х	Progress Payments	Nov. 2, 2013	
		3426I			Railroad Protective Liability Insurance	Dec. 1, 1986	Jan. 1, 2006
80157 Railroad Protective Liability Insurance (5 and 10) Jan. 1, 2006		80157			Railroad Protective Liability Insurance (5 and 10)	Jan. 1, 2006	

ļ	<u>File</u> Name	<u>Pg.</u>	Special Provision Title	Effective	<u>Revised</u>
*	80306	60	X Reclaimed Asphalt Pavement (RAP) and Reclaimed Asphalt Shingles (RAS)	Nov. 1, 2012	Jan. 1, 2018
*	80395		Sloped Metal End Section for Pipe Culverts	Jan. 1, 2018	
	80340		Speed Display Trailer	April 2, 2014	Jan. 1, 2017
	80127		Steel Cost Adjustment	April 2, 2014	Aug. 1, 2017
*	80391	70	X Subcontractor Mobilization Payments	Nov. 2, 2017	
	80317		Surface Testing of Hot-Mix Asphalt Overlays	Jan. 1, 2013	April 1, 2016
	80298	71	X Temporary Pavement Marking (NOTE: This special provision was previously named <i>"Pavement Marking Tape Type IV"</i> .)	April 1, 2012	April 1, 2017
	20338	74	X Training Special Provision	Oct. 15, 1975	
*	80318		Traversable Pipe Grate for Concrete End Sections (Note: This special provision was previously named " <i>Traversable Pipe Grate</i> ".)	Jan. 1, 2013	Jan. 1, 2018
	80288		Warm Mix Asphalt	Jan. 1, 2012	April 1, 2016
	80302	77	X Weekly DBE Trucking Reports	June 2, 2012	April 2, 2015
	80071	78	X Working Days	Jan. 1, 2002	

The following special provisions are in the 2018 Supplemental Specifications and Recurring Special Provisions.

<u>File</u>	Special Provision Title	New Location	Effective	<u>Revised</u>
<u>Name</u>				
80368	Light Tower	Article 1069.08	July 1, 2016	
80369	Mast Arm Assembly and Pole	Article 1077.03(a)(1)	July 1, 2016	
80338	Portland Cement Concrete Partial Depth Hot-Mix Asphalt Patching	Recurring CS #35	April 1, 2014	April 1, 2016
80379	Steel Plate Beam Guardrail	Articles 630.02, 630.05, 630.06, and 630.08	Jan. 1, 2017	
80381	Traffic Barrier Terminal, Type 1 Special	Article 631.04	Jan. 1, 2017	
80380	Tubular Markers	Articles 701.03, 701.15, 701.18, and 1106.02	Jan. 1, 2017	

SPECIAL PROVISIONS

INTERSECTION IMPROVEMENTS MARKET PLACE AND PLAZA DRIVE FAU ROUTE 9326 (MARKET PLACE) SECTION: 14-00042-00-PV PROJECT: VQW9(866) FAIRVIEW HEIGHTS, ILLINOIS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction", Adopted January 1, 2016, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways" and the "Manual of Test Procedures of Materials" in effect on the date of the invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of FAU 9326 (MARKET PLACE INTERSECTION IMPROVEMENTS), Section 14-00042-00-PV, Fairview Heights, Illinois, and in case of conflict with any part, or parts, of said Specifications, the said Special Provisions shall take precedence and shall govern.

DESCRIPTION OF WORK

The proposed intersection improvement is located along Market Place starting 900' west of the intersection of IL Route 159 proceeding easterly to the afore-mentioned intersection in Fairview Heights, Illinois. The project length is 900 feet (0.171 miles).

The work on this project consists of PCC pavement, PCC base course widening, installation of a raised median on Market Place and channelizing medians on Plaza Drive, storm sewer adjustments, HMA mill and overlay, curb and gutter construction and sidewalk installation with ADA ramps, paint pavement markings and all incidental and collateral work necessary to complete the work in the above-described Section according to the plans, specifications and special provisions.

SHOP DRAWINGS

The Contractor shall submit shop drawings of the following items according to Articles 1042.03(b) and 105.04 of the "Standard Specifications for Road and Bridge Construction":

Detectable Warnings Precast Concrete Inlets Precast Concrete Manholes Type 3 Frame and Grate

Submit shop drawings for review and approval to:

Mr. Chris Volkman, City Engineer City of Fairview Heights 10025 Bunkum Road Fairview Heights, Illinois 62208 Concurrent with the required shop drawing submittals to the City, the Contractor shall also submit a copy of each submittal to the Department. A maximum of two reviews by the Engineer will be provided for each shop drawing submittal. If any additional reviews are required, the Contractor shall pay the Engineer for all costs incurred at an hourly rate of \$150. Payment for additional reviews shall be made directly to the City.

CONSTRUCTION STAKING

This work shall consist of construction staking according to Article 105.09 of the "Standard Specifications for Road and Bridge Construction", except as modified herein.

The Local Agency will provide adequate reference points to the centerline of survey and bench marks as shown on the plans and listed herein. All additional control points set by the Local Agency will be identified in the field to the Contractor and all field notes will be kept in the office of the Resident Engineer.

The Contractor shall provide labor, equipment and material to set all additional stakes for this project, which are needed to establish offset stakes, reference points, and all other horizontal or vertical controls, including supplementary bench marks, necessary to secure a correct layout for the roadway portion of the work.

The Contractor shall be responsible for having the finished work conform to the lines, grades, elevations and dimensions called for on the plans. Inspection or checking of the Contractor's layout by the Engineer and the acceptance of all or any part of it shall not relieve the Contractor of his/her responsibility to secure the proper dimensions, grades and elevations of the several parts of the work. The Contractor shall exercise care in the preservation of stakes and benchmarks and shall have them reset at his/her expense when any are disturbed.

Responsibility of the Local Agency

- Control points referenced to the survey centerline will be provided at intervals not exceeding 1000 ft.
- Bench marks will be established along the project outside of the construction limits lines not exceeding 1000 ft. intervals horizontally and 20 ft. vertically.
- Proposed right of way limits will be staked at break points and on tangent at intervals not to exceed 100 ft.
- Curb and gutter widening, commercial entrances, and channelizing medians will be set at intervals not to exceed 50 ft. Depth of cut and/or fill heights and horizontal offset will be referenced to the finish pavement grade at the proposed profile grade line.
- Drainage structures will be staked by the Local Agency to establish the proposed horizontal and vertical locations for the drainage system.
- The radius point of intersection corner turning radii will also be staked.
- The locations of the light foundations will be staked for pavement removal limits for these foundations.
- The Local Agency will accept responsibility for the accuracy of the initial control points and stakes as provided herein. The Contractor shall assume full responsibility for all dimensions and measurements taken or derived by the

Contractor from control points or stakes set by the Local Agency. It is not the responsibility of the Local Agency, except as provided herein, to check the correctness of the Contractor's stakes.

• The Local Agency will set all stakes that are the responsibility of the Local Agency one time only. If any additional staking or restaking is required, the Contractor shall pay the Local Agency for all costs incurred at an hourly rate of \$150. Payment for additional staking shall be made directly to the City.

Responsibility of the Contractor

- The Contractor shall provide written requests for all staking to be provided by the Local Agency. A minimum 48 hour advance notice will be required prior to the commencement of all requested staking activities.
- The Contractor shall establish from the given survey points and bench marks, all additional control points necessary to construct the individual project elements. It is the Contractor's responsibility to tie in centerline control points in order to preserve them during construction operations.
- The Contractor shall provide all additional staking required to assure completion of the work in substantial conformance with the plans.
- The Contractor shall be responsible for re-establishing all stakes removed or disturbed by construction operations.
- All work shall be according to normally accepted surveying practices. Field notes shall be kept in standard survey field notebooks and those books shall become the property of the Local Agency at the completion of the project. All notes shall be neat, orderly, and in accepted form.

This work will not be measured separately for payment. The cost incurred by the Contractor in complying with this requirement shall be considered as included in the contract unit prices bid for the various items of work.

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT

An independent IEPA National Pollution Discharge Elimination System (NPDES) storm water permit is not required for this project; however, work shall conform to the City of Fairview Height's existing General Storm Water Permit for Small Municipal Separate Storm Sewer Systems (MS4). Erosion control items shall be constructed according to the Erosion Control Plan, the Standard Specifications for Road and Bridge Construction, and the Illinois Urban Manual.

The Erosion Control Plan must be kept on site during working hours. Compliance with this special provision shall be considered as included in the various items of work involved.

SEQUENCE OF CONSTRUCTION OPERATIONS

The Contractor shall conduct his work within the approved Sequence of Construction Operations at all times. The work shall be done in a manner that will minimize the inconvenience to local traffic.

The Contractor shall conduct his operations to insure local access to all properties throughout the project limits according to Article 107.09 and Section 701 and 703 of the "Standard Specifications for Road and Bridge Construction".

The Contractor will be permitted to close the commercial entrances at Sta. 109+98 (left and right) and Plaza Drive (left and right), but these two locations cannot be closed simultaneously. All road closures must be approved in advance by the City of Fairview Heights Department of Public Works. The Contractor shall notify the City of Fairview Heights Fire and Police Departments at least 48 hours prior to enacting any road closures.

SUGGESTED SEQUENCE

During construction, the Contractor will be required to maintain access to all properties affected by this work. The Contractor will not be allowed to begin subsequent construction operations until the preceding work is substantially complete. The construction sequence shall be compressed as much as possible to minimize the inconvenience to local traffic.

The construction schedule shall progress according to Section 108 of the "Standard Specifications for Road and Bridge Construction", except that the CONTRACTOR shall have to cease all construction activities during the following shutdown dates:

July 15 - August 31 of any given year November 1 - January 15 of the following year of any given year

During the time periods listed above, the entrances at Sta. 109+98 LT and RT and the Plaza Drive roadway LT and RT shall be open in both directions to vehicle traffic. Working days will not be charged during the shutdown period listed above.

Unless authorized by the Engineer, the Contractor shall complete the construction in the suggested sequence mentioned in the traffic control plans. The Contractor may submit an alternate sequence of operations and traffic control plan that would expedite construction and still maintain traffic control. Any and all changes to these plans must be submitted in writing and approved in advance by the Engineer. No additional compensation will be allowed if alternate plans are approved.

TRAFFIC CONTROL PLAN

Traffic control shall be according to the applicable Sections of the "Standard Specifications for Road and Bridge Construction", the applicable guidelines contained in the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", these special provisions, and all special details and Highway Standards contained herein and on the plans.

At the preconstruction meeting, the Contractor shall furnish the name of the individual in his/her direct employ who is responsible for the installation and maintenance of the traffic control for this project. If the actual installation and maintenance are to be accomplished by the Subcontractor, consent shall be requested of the Engineer at the time of the preconstruction meeting according to Article 108.01 of the "Standard Specifications for Road"

and Bridge Construction". This shall not relieve the Contractor of the foregoing requirement for a responsible individual in his direct employ. The Department will provide the Contractor the name of its representative who will be responsible for the observation of the Traffic Control Plan.

The Contractor shall furnish, erect, maintain and remove all warning signs, flags, barricades and lights according to Article 107.14 and Sections 701 and 703 of the "Standard Specifications for Road and Bridge Construction", the latest edition of the "Manual of Uniform Traffic Control Devices for Construction and Maintenance Operations", the Special Provisions, and/or as directed by the Engineer.

Articles 107.09 and 107.14 and Sections 701 and 703 of the "Standard Specifications for Road and Bridge Construction" and the following Highway Standards relating to traffic control apply to this contract:

701101	701106	701301	701311	701606	701801
701901					

Market Place shall have one lane of traffic in each direction open at all times. The commercial entrances at Sta. 109+98 shall not be closed at the same time as Plaza Drive. All work for the median reconstruction on IL Route 159 shall take place at night during the hours as listed in the traffic control plan sheets.

In addition, the following special provision(s) will also govern traffic control for this project:

SEQUENCE OF CONSTRUCTION OPERATIONS TRAFFIC CONTROL AND PROTECTION, (SPECIAL) CONSTRUCTION AND MAINTENANCE SIGN SUPPORTS CHANGEABLE MESSAGE SIGN WORK ZONE TRAFFIC CONTROL SURVEILLANCE FLAGGERS IN WORK ZONES

PUBLIC NOTICE

Each Wednesday, the Contractor shall furnish his schedule for the next week's work. Handbill notices approved by the Engineer shall be delivered to each business located within the work zone detailing any lane closures, at least 48 hours prior to commencing work. Notices shall explain the proposed work and request the business's forbearance of the inconvenience. All complaints should be directed to the Contractor. Residents may contact the City if their concerns are not resolved satisfactorily by the Contractor.

This work will not be paid for separately, and the cost shall be considered as included in the contract unit prices bid for the various items of work involved.

TRENCH BACKFILL

This work shall be constructed according to Section 208 of the "Standard Specifications for Road and Bridge Construction", except as modified herein:

Fine aggregate according to Article 1003.04 may be used for bedding only, except as follows: Fine aggregate will be required for trench backfill within 2 ft. of all gas mains and gas service lines that are exposed during trenching operations.

Material for trench backfill shall be coarse aggregate gradation CA 6, CA 10 or CA 18 as specified in Article 1004.05.

Trench backfill material shall be compacted according to Method 1, as specified in Article 550.07(a) of the "Standard Specifications for Road and Bridge Construction".

This work will be paid for at the contract unit price per cubic yard for TRENCH BACKFILL, measured as specified in Article 208.03 of the "Standard Specifications for Road and Bridge Construction".

INCIDENTAL HOT-MIX ASPHALT SURFACING

This work shall consist of the preparation of the base, the application of bituminous priming material and aggregate, and the construction of a hot-mix asphalt (HMA) surface on a prepared base at the locations shown on the plans according to Section 408 the "Standard Specifications for Road and Bridge Construction."

Bituminous prime coat and prime coat aggregate are required, but will not be measured separately for payment.

This work will be paid for at the contract unit price per ton for INCIDENTAL HOT-MIX ASPHALT SURFACING, which price shall include the bituminous priming material and aggregate for covering the prime coat.

PORTLAND CEMENT CONCRETE PAVEMENT (JOINTED) THICKNESS SPECIFIED

This work shall consist of constructing a Portland cement concrete pavement according to Section 420 of the "Standard Specifications for Road and Bridge Construction," except as modified herein.

All references to Sections or Articles in this specification shall be understood to mean a specified Section or Article of the "Standard Specifications for Road and Bridge Construction".

- Article 420.03(b). A formless paver will not be required.
- Article 420.03(c). A mechanical concrete spreader will not be required.
- Article 420.03(d). A finishing machine will not be required.
- Article 420.03(e). A mechanical longitudinal float will not be required.
- Article 420.03(f). A concrete finisher float will not be required.

Article 420.03(h). Power driven finishing machines, including vibratory screeds and truss-type vibratory screeds, which are specifically designed for finishing concrete pavement and meet the approval of the Engineer, will be allowed.

Hand held fogging equipment capable of spraying a uniform application of membrane curing compound and maintaining constant pressure meeting the approval of the Engineer, will be allowed.

Article 420.09(a) (1). Revise this Article as follows:

After the concrete has been struck off, it shall be given the required consolidation by the vibratory method or by other means which will obtain a uniform and satisfactory density throughout the pavement. If the vibratory method is used, the vibrating impulses shall be applied directly to the concrete through an apparatus especially designed for this purpose in a manner that the vibratory impulses are transmitted through the concrete mass with sufficient intensity to consolidate it throughout its entire depth and width. Not more than one pass of the vibratory equipment shall be made through the pavement.

Article 420.09(a) (3). Revise the first sentence of this Article to read as follows:

Vibrating screed. An approved vibrating screed may be used to strike off, consolidate and finish pavement.

TIE BARS & REINFORCEMENT BARS

This work shall consist of furnishing and placing tie bars and reinforcement bars in concrete pavement and concrete curb and gutter according to Sections 420 and 606 of the "Standard Specifications for Road and Bridge Construction", except as modified herein:

All tie bars and reinforcement bars used in Portland cement concrete pavement and concrete curb and gutter shall be epoxy coated.

This work will not be paid for separately, but shall be included in the contract unit price of the various concrete pavement and concrete curb and gutter items for which the tie bars and reinforcement bars are required.

EXPANSION JOINTS

This work shall consist of constructing expansion joints in concrete driveway pavement and sidewalk according to Articles 423.07 and 424.07 of the "Standard Specifications for Road and Bridge Construction" and Highway Standard 424001 except as modified herein: Expansion joints required under Article 423.07 and 424.07(b) shall be preformed fiber joint filler according to Article 1051.04 of the "Standard Specifications for Road and Bridge Construction" and shall have a perforated tear off wood or plastic strip to provide a uniform 3/4 in. reservoir/channel for the required sealant.

Expansion joints required under Article 424.07(a) shall consist of preformed flexible foam expansion joint filler according to Article 1051.09 of the "Standard Specifications for Road and Bridge Construction" and shall have a pre-scored removable strip to provide a uniform 1/2 in. reservoir/channel for the required sealant.

Expansion joint filler and backer rod materials shall be a non-impregnated type that will not bond with the sealant.

Expansion joints shall be sealed with self-leveling (pour grade), or nonsag (gun) grade urethane sealant. The color of the sealant shall be limestone, unless otherwise approved by the Engineer.

This work will not be paid separately, but shall be included in the contract unit price of the various concrete items for which the expansion joints are required.

DETECTABLE WARNINGS

This work shall consist of constructing detectable warning surfaces in curb ramps and other locations shown on the plans according to Articles 424.09 of the "Standard Specifications for Road and Bridge Construction" and Highway Standard 424001 and as modified herein:

Materials shall be the following type:

<u>Precast concrete</u> panels, reinforced with stainless steel prestressed tendons. Concrete shall contain a waterproofing admixture and be surface treated with penetrating sealer, incorporating raised, truncated domes.

Color shall be red.

Panel sections shall be of equal size and dimensions with no fragments unless approved by the Engineer.

Detectable warning panels shall be protected when applying curing compound to the adjoining concrete sidewalk. Any overspray on the panels shall be cleaned immediately to the satisfaction of the Engineer.

Joints between panels and around the perimeter of the panels shall be caulked with a self-leveling (pour grade), or nonsag (gun) grade urethane sealant. The color of the sealant shall be limestone, unless otherwise approved by the Engineer.

The concrete thickness under the panels shall be increased 1 inch. The subgrade shall be well-drained and properly compacted. Forms shall be positioned for proper grade, slope, and uniform slab thickness.

Detectable warning panels shall be placed as shown in the drawings and shall have visual contrast with the adjoining concrete surface. Adequate drainage shall be provided to prevent the accumulation of water and debris at the bottom of the ramp.

Panels shall be installed immediately in fresh concrete and adjusted to grade to ensure 100% surface contact with square edges of panels butted tightly together. The base of the truncated domes shall be set flush with the adjoining concrete surface. The maximum tolerance between the panels and the adjoining surface is 1/16 inch. Immediately after placement, the panels shall be checked for slope, elevation and proper grade. The concrete around the panels shall be edged with 1/8 in. radius edger and finished according to the contract specifications.

This work will be paid for at the contract unit price per square foot for DETECTABLE WARNINGS as specified herein.

STORM SEWER REMOVAL, SIZE SPECIFIED

This work shall consist of removing storm sewer sections at various locations as shown on the plans according to Section 551 of the "Standard Specifications for Road and Bridge Construction."

It shall be the Contractor's responsibility to protect the existing storm sewer sections to remain in place. Any damage to the storm sewer pipe sections shall be repaired by the Contractor to the satisfaction of the Engineer at no additional cost to the Department.

This work will be paid for at the contract unit price per foot for STORM SEWER REMOVAL, of the size specified.

TYPE 3 FRAME AND GRATE

This work shall consist of furnishing and installing cast iron frames and grates, together with the necessary inlets and manholes as shown on the plans according to Section 602 of the "Standard Specifications for Road and Bridge Construction", except as modified herein.

All Type 3 Frames and grates shall conform to Highway Standard 604006, except the curb box shall have a single opening extending across the full width of the casting. The Contractor shall submit a shop drawing of the proposed frame and grate to the Engineer for approval according to Article 505.03 of the "Standard Specifications for Road and Bridge Construction".

This work will not be measured separately for payment. The cost of this work shall be included in the contract unit price per each INLET or MANHOLE, of the type and diameter specified.

CONSTRUCTION AND MAINTENANCE SIGN SUPPORTS

This work shall be done according to Section 1106 of the "Standard Specifications for Road and Bridge Construction" and Highway Standard 701901 except as modified herein.

All construction signs mounted on permanent support for use in temporary traffic control having an area of 10 square feet or more shall be mounted on two 4 in. x 4 in. or two 4 in. x 6 in. wood posts.


Type A metal posts (two for each sign) conforming to Article 1006.29 of the "Standard Specifications for Road and Bridge Construction" may be used in lieu of wood posts. Type A metal posts used for these signs may be unfinished.

The cost incurred by the Contractor in complying with this requirement shall be considered included in the contract unit prices bid for the various items of traffic control work involved.


CHANGEABLE MESSAGE SIGN

The Contractor shall provide and maintain two trailer mounted variable message signs. Each sign shall have the capability to display three lines of eight characters. The signs shall be placed as shown in the traffic control plans. The locations of these signs shall be approved by the Engineer.

The message displayed on the sign shall inform the motorists when construction will begin and when lane closures will occur on Market Place. An example message follows:



An example for lane closures follows:



Each screen shall be displayed for 2 seconds. The messages displayed on the signs will be approved by the Engineer.

This work will not be measured separately for payment, but shall be included in the cost of TRAFFIC CONTROL AND PROTECTION (SPECIAL).

PROTECTION AND RESTORATION OF TRAFFIC SIGNS

Protection and restoration of traffic signs shall be according to Article 107.25 of the "Standard Specifications for Road and Bridge Construction" and as supplemented herein:

All signs and supports that are replaced by a new sign or are in conflict with a new sign shall also be removed at the direction of the Engineer. Signs and supports that are no longer desired along the final roadway shall be properly disposed of by the Contractor.

Existing sign panels to be reused shall be carefully removed to prevent damage. Each sign which is damaged by the Contractor due to negligence shall be replaced by the Contractor at his/her expense. Signs used for replacement shall be the same size and type as the sign being replaced.

Sign supports that were removed shall be properly backfilled to the satisfaction of the Engineer.

This work will not be measured separately for payment and the cost shall be considered as included in the unit prices bid for the various items of work involved.

SIGN PANEL TYPE 1 AND TELESCOPING STEEL SIGN SUPPORT

This item shall be performed according to Sections 720, 729 and 1006 of the "Standard Specification for Road and Bridge Construction" except as modified herein.

Metal posts and sign panel backs shall be either **enameled or polyester coated with a black finish**. The application rates of Sections 1006.29(b)(4) and 1006.29(b)(5) shall apply.

This work will be measured according to Article 729.04 of the "Standard Specifications for Road and Bridge Construction".

This work will be paid for at the contract unit price per square foot for SIGN PANEL TYPE 1 or per foot for TELESCOPING STEEL SIGN SUPPORT.

DETECTOR LOOP REPLACEMENT

This work shall consist of furnishing and installing a detector loop, Type 1, in the pavement at the locations shown on the plans according to Sections 886 and 873 of the "Standard Specifications for Road and Bridge Construction" and Highway Standards 886001 and 886006, except as modified herein.

The depth of the sawed slot shall be as required to provide a minimum of 1 in. clearance between the surface of the pavement and the top of the backer rod. When loops are placed in the binder or base course of HMA pavement and will be covered by an additional surface course, the clearance may be reduced to $\frac{1}{2}$ in.

At all locations where pavement joints that are not doweled or pavement separation cracks (including areas where HMA pavement abuts concrete pavement) are

encountered by the slots sawed for the placement of the detector loops or lead-ins, a cored expansion hole shall be made per Highway Standard 886001. The cored expansion holes are included in this pay item. The location of all detector loops shall be approved by the Engineer before any slots are sawed in the pavement.

Detector loops shall be placed in the pavement after milling and prior to resurfacing.

Detector loops shall be spliced into the existing lead-in cables in the handhole. The splices shall be made per Section 873 of the "Standard Specifications for Road and Bridge Construction". Rosin-core solder shall be used. The cost of labor and material for removing existing detector loop cables from the conduit and splicing into the existing lead-in cables shall be included in the contract unit price for DETECTOR LOOP REPLACEMENT.

This work will be paid for at the contract unit price per foot for DETECTOR LOOP REPLACEMENT, measured along the sawed slot in the pavement containing the loops and lead-in, rather than the actual length of wire in the slot, which price shall be payment in full for furnishing, installing and testing the detector loop complete in place.

REMOVE AND REINSTALL LIGHTING EQUIPMENT

This work shall consist of removing and relocating existing flood lights with new fixtures supplied by the Owner as shown on the plans and according to the local building code.

The existing fixtures shall become the property of the CONTRACTOR. Any additional underground conduit or electrical wire needed to relocate the fixtures shall be included in the unit price for this work. The CONTRACTOR shall coordinate with the property facility manager in gaining access to the fixture controller cabinet as needed.

This work will be paid for at the contract unit price lump sum for REMOVE AND REINSTALL LIGHTING EQUIPMENT.

CONCRETE CURB (SPECIAL)

This work shall consist of constructing a concrete curb for the raised median portions of the project as shown on the plan and details, and according to Section 606 of the "Standard Specifications for Road and Bridge Construction".

All tie bars cast into the curb and the anchors that are drilled and epoxied into the existing pavement, shall be epoxy coated. Control joints shall be cut into the curb to align with the joints in the existing PCC pavement. Ramped noses will be constructed as shown in the plans and shall be poured as one monolithic item.

This work will be paid for at the contract unit price per foot for CONCRETE CURB SPECIAL, measured along the face of curb. The ramped noses will also be paid for as CONCRETE CURB SPECIAL, measured along the front face of the curb.

TRAFFIC CONTROL AND PROTECTION, (SPECIAL)

This work shall consist of furnishing, installing, maintaining and removing all traffic control devices for traffic control and protection, (this shall also include but not be limited to the detour signing and changeable message boards) as shown on Highway Standards 701101, 701106, 701301, 701311, 701606, 701801, and 701901 included in the plans, according to the TRAFFIC CONTROL PLAN, according to Section 701 of the "Standard Specifications for Road and Bridge Construction", as directed by the Engineer and as specified herein.

Throughout the construction period, all material piles, equipment, open excavations or other obstructions or hazards to motorists or pedestrians shall be enclosed by fences or protected by barricades and proper lighting.

Traffic Control and Protection required for the successful completion of this project will be furnished, installed, maintained, removed, measured and paid for at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION, (SPECIAL), which price shall include all work as specified herein and all other provisions required by law for the protection and safety of property and individuals in a construction zone.

TEMPORARY PAVEMENT MARKING REMOVAL

This work shall consist of removing temporary pavement markings as shown on the plans and according to Section 783 of the "Standard Specifications for Road and Bridge Construction".

The method used for pavement marking removal shall be water blasting with vacuum recovery as detailed in Article 783.02 (c). No other removal technique will be allowed.

This work will be paid for at the contract unit price per square foot for TEMPORARY PAVEMENT MARKING REMOVAL, which price shall include the work as specified herein.

DRAINAGE STRUCTURE ADJUSTMENT (SPECIAL)

This work shall consist of adjusting the lid of the existing drainage structure shown on the plans and the plan details and according to Section 602 of the "Standard Specifications for Road and Bridge Construction".

The walls shall be brought to the proper height as shown on the detail using cast in place concrete and rebar. The rebar shall have bent bars around the corners of the wall extension. The overlap between the corner bars and longitudinal bars shall be 18". Preformed mastic shall be placed on the top of the finished walls of the structure prior to resetting the flat slab top.

This work will be paid for at the contract unit price per each for DRAINAGE STRUCTURE ADJUSTMENT (SPECIAL), which price shall include the work as specified herein.

PAINT CURB

This work shall consist of furnishing and applying paint pavement marking on curbs at the locations shown on the plans according to Section 780 of the "Standard Specifications for Road and Bridge Construction".

The top and face of curbs shall be painted yellow or white as shown on the plans.

This work will be paid for at the contract unit price per foot for PAINT CURB, measured along the face of curb.

STATUS OF UTILITIES TO BE ADJUSTED

NAME AND ADDRESS OF UTILITY	TYPE	LOCATION	<u>ESTIMATED</u> DATE OF COMPLETION
<u>Caseyville Township Sewer</u> #1 Ecology Drive O'Fallon, IL 62269 Contact Person: Joe Hogg	Sewer	The existing sanitary sewer will not be in conflict.	N/A
<u>City of Fairview Heights</u> 700 Oakwood Avenue Alton, IL 62002 Bunkum Road Contact Person: Chris Volkman	Storm Sewer	The existing storm sewer system will be modified as shown in the plans, otherwise no other conflicts are anticipated.	N/A
<u>City of O'Fallon</u> 255 S. Lincoln Ave O'Fallon, IL 62269 Contact Person: Jeff Taylor	Water	The water line is not within the project limits.	N/A
<u>Ameren (Gas)</u> 1050 West Blvd Belleville, IL 62221 Contact Person: Ken Keleher	Gas	No gas lines within the project limits.	N/A
Ameren (Electric) 500 E. Broadway East St. Louis, IL 62201 Contact Person: Ken Lake	Electric	Power supply to the flood light at Sta. 109+68 to be relocated will need to be located and moved to the relocated flood light location by the Contractor. Cost to do this work shall be included in the unit prices for the other areas of the project, and shall not be paid for separately.	N/A
<u>AT&T</u> 1420 Frontage Road O'Fallon, IL 62269 Contact Person: Jason Lehde	Comm	No communication lines within the project limits.	N/A
<u>Charter</u> 815 Charter Commons Town & Country, MO 63017 Contact Person: Lisa Ward	Comm	No communication lines within the project limits.	N/A
<u>Buckeye Partners, LP</u> Five TEK Park 9999 Hamilton Boulevard Breiningsville, PA 18031 Contact Person: Beth Auman	Gas	No gas lines within the project limits.	N/A

Minor adjustments of residential service lines may be necessary to accommodate construction. All such adjustments will be made by their respective owners during construction.

Underground facilities, structures and utilities have been plotted from available surveys and records. Their locations must be considered to be approximate only. It is possible there may be others, the existence of which is not presently known or shown. Such information represents only the opinion of the Local Agency and their Engineer as to the location of such utilities and is only included for the convenience of the bidder. The Local Agency and their Engineer assume no responsibility in respect to the sufficiency or the accuracy of the information shown on the plans relative to the location of underground utility facilities.

State of Illinois Department of Transportation Bureau of Local Roads and Streets

SPECIAL PROVISION FOR INSURANCE

Effective: February 1, 2007 Revised: August 1, 2007

All references to Sections or Articles in this specification shall be construed to mean specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

The Contractor shall name the following entities as additional insured under the Contractor's general liability insurance policy in accordance with Article 107.27:

City of Fairview Heights, Illinois

I

The entities listed above and their officers, employees, and agents shall be indemnified and held harmless in accordance with Article 107.26.

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

This work shall be according to Article 669 of the Standard Specifications and the following:

<u>Qualifications</u>. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

<u>General.</u> This Special Provision will likely require the Contractor to subcontract for the execution of certain activities.

All contaminated materials shall be managed as either "uncontaminated soil" or non-special waste. <u>This work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances.</u> The Environmental Firm shall continuously monitor all soil excavation for worker protection and soil contamination. **Phase I Preliminary Engineering information is available through the District's Environmental Studies Unit.** Soil samples or analysis without the approval of the Engineer will be at no additional cost to the Department. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less.

The Contractor shall manage any excavated soils and sediment within the following areas:

Site 3209-1: Commercial Building

 Station 112+80 to Station 115+30 (CL Market Place), 0 to 50 feet LT (PESA Site 3209-1, Men's Warehouse, 6631 – 6651 N. Illinois Street, Fairview Heights (northwest corner of Illinois Street and Market Place)). This material meets the criteria of Article 669.09(a)(5) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

Site 3209-3: ROW, 6000 Block of N. Illinois Street

Station 115+30 to Station 116+40 (CL Market Place), 0 to 80 feet RT/ 0 to 50 feet LT (PESA Site 3209-3, ROW 6600 Block of N. Illinois Street, Fairview Heights). This material meets the criteria of Article 669.09(a)(5) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

Site 3209-4: Taco Bell Restaurant

 Station 112+80 to Station 115+30 (CL Market Place), 0 to 50 feet RT (PESA Site 3209-1, Taco Bell Restaurant, 6599 N. Illinois Street, Fairview Heights (southwest corner of Illinois Street and Market Place)). This material meets the criteria of Article 669.09(a)(5) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

SUBMITTAL OF EEO/LABOR DOCUMENTATION

Effective: April 2016

This work shall be done in accordance with Check Sheets No. 1, 3 and 5 of the IDOT Supplemental Specifications and Recurring Special Provisions and the "Weekly DBE Trucking Reports (BDE)" Special Provision, except as here-in modified.

PAYROLL AND STATEMENT OF COMPLIANCE:

Certified payroll, (FORM SBE 48 OR AN APPROVED FACSIMILE) and the Statement of Compliance, (FORM SBE 348) shall be submitted by two methods:

- 1. By Mail (United States Postal Service): The ORIGINAL of the certified payroll and the Statement of Compliance for the Prime Contractor and each Subcontractor shall be submitted by mail to the Regional Engineer for District 8.
- 2. Electronically: Scan both the ORIGINAL of the certified payroll and the Statement of Compliance to the same PDF file and email to the District at the email address designated by the District EEO Officer.

SBE 48 and SBE 348 forms shall be submitted weekly and will be considered late if received after midnight seven (7) business days after the payroll ending date.

WEEKLY DBE TRUCKING REPORT:

The Weekly DBE Trucking Report, (FORM SBE 723) shall be submitted electronically. Scan the form to a PDF file and email to the District at the email address designated by the District EEO Officer.

SBE 723 forms shall be submitted weekly and will be considered late if received after midnight ten (10) business days following the reporting period.

MONTHLY LABOR SUMMARY & MONTHLY CONTRACT ACTIVITY REPORTS:

The Monthly Labor Summary Report (MLSR) shall be submitted by one of two methods:

- 1. For contractors having IDOT contracts valued in the aggregate at \$250,000 or less, the report may be typed or clearly handwritten using Form D8 PI0148. Submit the ORIGINAL report by mail to the Regional Engineer for District Eight. Contractors also have the option of using the method #2 outlined below.
- For contractors having IDOT contracts valued in the aggregate at more than \$250,000, the report must be submitted in a specific "Fixed Length Comma Delimited ASCII Text File Format". This file shall be submitted by e-mail using specific file formatting criteria provided by the District EEO Officer. Contractors must submit a sample text file to District 8 for review at least fourteen (14) days prior to the start of construction.

The Monthly Contract Activity Report (MCAR) may be typed or clearly handwritten using Form D8 PI0149.

<u>The Monthly Labor Summary Report and the Monthly Contract Activity Report shall be</u> <u>submitted concurrently</u>. If the method of transmittal is method #1 above then both the MLSR and the MCAR shall be mailed together in the same envelope. If the method of transmittal is method #2 above then the MCAR shall be scanned to a .pdf file and attached to the email containing the MLSR .txt file.

The MLSR and MCAR must be submitted for each consecutive month, for the duration of the project, and will be considered late if received after midnight ten (10) calendar days following the reporting period.

REQUEST FOR APPROVAL OF SUBCONTRACTOR:

The ORIGINAL and one copy of the Request for Approval of Subcontractor (FORM BC 260A) shall be submitted to the District at the IDOT Preconstruction Conference.

SUBSTANCE ABUSE PREVENTION PROGRAM CERTIFICATION:

The ORIGINAL and one copy of the Substance Abuse Prevention Program Certification (FORM BC 261) shall be submitted to the District at the IDOT Preconstruction Conference.

The Contractor is required to follow submittal procedures as provided by the EEO Officer at the preconstruction conference and to follow all revisions to those procedures as issued thereafter.

If a report is rejected, it is the contractor's responsibility to make required adjustments and/or corrections and resubmit the report. Reports not submitted and accepted within the established timeframes will be considered late.

Disclosure of this information is necessary to accomplish the statutory purpose as outlined under 23CFR part 230 and 41CFR part 60.4 and the Illinois Human Rights Act. Disclosure of this information is REQUIRED. Failure to comply with this special provision may result in the withholding of payments to the contractor, and/or cancellation, termination, or suspension of the contract in whole or part.

This Special Provision must be included in each subcontract agreement.

ALL HARD COPY FORMS TO BE SUBMITTED TO:

Region 5 Engineer Illinois Department of Transportation ATTN: EEO/LABOR OFFICE 1102 Eastport Plaza Drive Collinsville, IL 62234-6198

Compliance with this Special Provision shall be included in the cost of the contract and no additional compensation will be allowed for any costs incurred.

IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION (TPG)

Effective: August 1, 2012

Revised: February 1, 2014

In addition to the Contractor's equal employment opportunity affirmative action efforts undertaken as elsewhere required by this Contract, the Contractor is encouraged to participate in the incentive program to provide additional on-the-job training to certified graduates of IDOT funded pre-apprenticeship training programs outlined by this Special Provision.

It is the policy of IDOT to fund IDOT pre-apprenticeship training programs throughout Illinois to provide training and skill-improvement opportunities to assure the increased participation of minority groups, disadvantaged persons and women in all phases of the highway construction industry. The intent of this IDOT Training Program Graduate (TPG) Special Provision is to place certified graduates of these IDOT funded pre-apprentice training programs on IDOT project sites when feasible, and provide the graduates with meaningful on-the-job training intended to lead to journey-level employment. IDOT and its sub-recipients, in carrying out the responsibilities of a state contract, shall determine which construction contracts shall include "Training Program Graduate Special Provisions." To benefit from the incentives to encourage the participation in the additional on-the-job training under this Training Program Graduate Special Provision, the Contractor shall make every reasonable effort to employ certified graduates of IDOT funded Pre-apprenticeship Training Programs to the extent such persons are available within a reasonable recruitment area.

Participation pursuant to IDOT's requirements by the Contractor or subcontractor in this Training Program Graduate (TPG) Special Provision entitles the Contractor or subcontractor to be reimbursed at \$15.00 per hour for training given a certified TPG on this contract. As approved by the Department, reimbursement will be made for training persons as specified herein. This reimbursement will be made even though the Contractor or subcontractor may receive additional training program funds from other sources for other trainees, provided such other source does not specifically prohibit the Contractor or subcontractor from receiving other reimbursement. For purposes of this Special Provision the Contractor is not relieved of requirements under applicable federal law, the Illinois Prevailing Wage Act, and is not eligible for other training fund reimbursements in addition to the Training Program Graduate (TPG) Special Provision reimbursement.

No payment shall be made to the Contractor if the Contractor or subcontractor fails to provide the required training. It is normally expected that a TPG will begin training on the project as soon as feasible after start of work utilizing the skill involved and remain on the project through completion of the contract, so long as training opportunities exist in his work classification or until he has completed his training program. Should the TPG's employment end in advance of the completion of the contract, the Contractor shall promptly notify the designated IDOT staff member under this Special Provision that the TPG's involvement in the contract has ended and supply a written report of the reason for the end of the involvement, the hours completed by the TPG under the Contract and the number of hours for which the incentive payment provided under this Special Provision will be or has been claimed for the TPG.

The Contractor will provide for the maintenance of records and furnish periodic reports documenting its performance under this Special Provision.

METHOD OF MEASUREMENT: The unit of measurement is in hours.

BASIS OF PAYMENT: This work will be paid for at the contract unit price of \$15.00 per hour for certified TRAINEES TRAINING PROGRAM GRADUATE. The estimated total number of hours, unit price and total price have been included in the schedule of prices.

The Contractor shall provide training opportunities aimed at developing full journeyworker in the type of trade or job classification involved. The initial number of TPGs for which the incentive is available under this contract is 1. During the course of performance of the Contract the Contractor may seek approval from the Department for additional incentive eligible TPGs. In the event the Contractor subcontracts a portion of the contract work, it shall determine how many, if any, of the TPGs are to be trained by the subcontractor, provided however, that the Contractor shall retain the primary responsibility for meeting the training requirements imposed by this Special Provision. The Contractor shall also insure that this Training Program Graduate Special Provision is made applicable to such subcontract if the TPGs are to be trained by a subcontractor and that the incentive payment is passed on to each subcontractor.

For the Contractor to meet the obligations for participation in this TPG incentive program under this Special Provision, the Department has contracted with several entities to provide screening, tutoring and pre-training to individuals interested in working in the applicable construction classification and has certified those students who have successfully completed the program and are eligible to be TPGs. A designated IDOT staff member, the Director of the Office of Business and Workforce Diversity (OBWD), will be responsible for providing assistance and referrals to the Contractor for the applicable TPGs. For this contract, the Director of OBWD is designated as the responsible IDOT staff member to provide the assistance and referral services related to the placement for this Special Provision. For purposes of this Contract, contacting the Director of OBWD and interviewing each candidate he/she recommends constitutes reasonable recruitment.

Prior to commencing construction, the Contractor shall submit to the Department for approval the TPGs to be trained in each selected classification. Furthermore, the Contractor shall specify the starting time for training in each of the classifications. No employee shall be employed as a TPG in any classification in which he/she has successfully completed a training course leading to journeyman status or in which he/she has been employed as a journeyman. Notwithstanding the on-the-job training purpose of this TPG Special Provision, some offsite training is permissible as long as the offsite training is an integral part of the work of the contract and does not comprise a significant part of the overall training.

Training and upgrading of TPGs of IDOT pre-apprentice training programs is intended to move said TPGs toward journeyman status and is the primary objective of this Training Program Graduate Special Provision. Accordingly, the Contractor shall make every effort to enroll TPGs by recruitment through the IDOT funded TPG programs to the extent such persons are available within a reasonable area of recruitment. The Contractor will be responsible for demonstrating the steps that it has taken in pursuance thereof, prior to a determination as to whether the Contractor is in compliance and entitled to the Training Program Graduate Special Provision \$15.00 an hour incentive.

The Contractor or subcontractor shall provide each TPG with a certificate showing the type and length of training satisfactorily completed.

ADJUSTING FRAMES AND GRATES (BDE)

Effective: April 1, 2017

Add the following to Article 602.02 of the Standard Specifications:

"(s) High Density Expanded Polystyrene Adjusting Rings	
with Polyurea Coating (Note 4)	1043.04
(4) Free and a Data many dama (FDD) Adjusting Discus (Nata F)	4040.05

(t) Expanded Polypropylene (EPP) Adjusting Rings (Note 5) 1043.05

Note 4. High density expanded polystyrene adjusting rings with polyurea coating shall meet the design load requirements of AASHTO HS20/25. The rings may be used to adjust the frames and grates of drainage and utility structures up to a maximum of 6 in. (150 mm). They shall be installed and sealed underneath the frames according to the manufacturer's specifications.

Note 5. Riser rings fabricated from EPP may be used to adjust the frames and grates of drainage and utility structures up to a maximum of 6 in. (150 mm). An adhesive meeting ASTM C 920, Type S, Grade N5, Class 25 shall be used with EPP adjustment rings. The top ring of the adjustment stack shall be a finish ring with grooves on the lower surface and flat upper surface. The joints between all manhole adjustment rings and the frame and cover shall be sealed using the approved adhesive. In lieu of the use of an adhesive, an internal or external mechanical frame-chimney seal may be used for watertight installation. EPP adjustment rings shall not be used with heat shrinkable infiltration barriers."

Add the following to Section 1043 of the Standard Specifications:

"1043.04 High Density Expanded Polystyrene Adjusting Rings with Polyurea Coating. High density expanded polystyrene adjustment rings with polyurea coating shall be designed and tested to meet or exceed an HS25 wheel load according to the AASHTO Standard Specifications for Highway Bridges (AASHTO M306 HS-25). The raw material suppliers shall provide certifications of quality or testing using the following ASTM standards, and upon request, certify that only virgin material was used in the manufacturing of the expanded polystyrene rings.

Dhysical Property	Test Standard	Value		
Physical Property	Test Standard	3.0 lb/cu ft	4.5 lb/cu ft	
Compression Resistance	ASTM D 1621			
at 10% deformation		50 - 70	70 - 90	
at 5% deformation		45 - 60	60 - 80	
at 2% deformation		15 - 20	20 - 40	
Flexural Strength	ASTM D 790	90 - 120	130 - 200	
Water Absorption	ASTM D 570	2.0%	1.7%	
Coefficient of Linear Expansion	ASTM D 696	2.70E-06 in./in./ºF	2.80E-06 in./in./ºF	
Sheer Strength	ASTM D 732	55	80	

Tensile Strength	ASTM D 1623	70 - 90	130 - 140
Water Vapor Transmission	ASTM C 355	0.82 – 0.86	6 perm – in.

High density expanded polystyrene adjustment rings with polyurea coating shall have no void areas, cracks, or tears. The actual diameter or length shall not vary more than 0.125 in. (3 mm) from the specified diameter or length. Variations in height are limited to \pm 0.063 in. (\pm 1.6 mm). Variations shall not exceed 0.25 in. (6 mm) from flat (dish, bow, or convoluting edge) or 0.125 in. (3 mm) for bulges or dips in the surface.

1043.05 Expanded Polypropylene (EPP) Adjusting Rings. The EPP adjusting rings shall be manufactured using a high compression molding process to produce a minimum finished density of 7.5 lb/cu ft (120 g/l). The EPP rings shall be made of materials meeting ASTM D 3575 and ASTM D 4819-13. The grade adjustments shall be designed and tested according to the AASHTO Standard Specifications for Highway Bridges (AASHTO M 306 HS-25).

Grade rings shall contain upper and lower keyways (tongue and groove) for proper vertical alignment and sealing. The top ring, for use directly beneath the cast iron frame, shall have keyways (grooves) on the lower surface with a flat upper surface.

Adhesive or sealant used for watertight installation of the manhole grade adjustment rings shall meet ASTM C 920, Type S, Grade NS, Class 25, Uses NT, T, M, G, A, and O.

EPP adjustment rings shall have no void areas, cracks, or tears. The actual diameter or length shall not vary more than 0.125 in. (3 mm) from the specified diameter or length. Variations in height are limited to \pm 0.063 in. (\pm 1.6 mm). Variations shall not exceed 0.25 in. (6 mm) from flat (dish, bow, or convoluting edge) or 0.125 in. (3 mm) for bulges or dips in the surface."

80382

COMPENSABLE DELAY COSTS (BDE)

Effective: June 2, 2017

Revise Article 107.40(b) of the Standard Specifications to read:

- "(b) Compensation. Compensation will not be allowed for delays, inconveniences, or damages sustained by the Contractor from conflicts with facilities not meeting the above definition; or if a conflict with a utility in an unanticipated location does not cause a shutdown of the work or a documentable reduction in the rate of progress exceeding the limits set herein. The provisions of Article 104.03 notwithstanding, compensation for delays caused by a utility in an unanticipated location will be paid according to the provisions of this Article governing minor and major delays or reduced rate of production which are defined as follows.
 - (1) Minor Delay. A minor delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two hours, but not to exceed two weeks.
 - (2) Major Delay. A major delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two weeks.
 - (3) Reduced Rate of Production Delay. A reduced rate of production delay occurs when the rate of production on the work in conflict with the utility in an unanticipated location decreases by more than 25 percent and lasts longer than seven calendar days."

Revise Article 107.40(c) of the Standard Specifications to read:

- "(c) Payment. Payment for Minor, Major, and Reduced Rate of Production Delays will be made as follows.
 - (1) Minor Delay. Labor idled which cannot be used on other work will be paid for according to Article 109.04(b)(1) and (2) for the time between start of the delay and the minimum remaining hours in the work shift required by the prevailing practice in the area.

Equipment idled which cannot be used on other work, and which is authorized to standby on the project site by the Engineer, will be paid for according to Article 109.04(b)(4).

(2) Major Delay. Labor will be the same as for a minor delay.

Equipment will be the same as for a minor delay, except Contractor-owned equipment will be limited to two weeks plus the cost of move-out to either the Contractor's yard or another job and the cost to re-mobilize, whichever is less.

Rental equipment may be paid for longer than two weeks provided the Contractor presents adequate support to the Department (including lease agreement) to show retaining equipment on the job is the most economical course to follow and in the public interest.

(3) Reduced Rate of Production Delay. The Contractor will be compensated for the reduced productivity for labor and equipment time in excess of the 25 percent threshold for that portion of the delay in excess of seven calendar days. Determination of compensation will be in accordance with Article 104.02, except labor and material additives will not be permitted.

Payment for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be determined according to Article 109.13."

Revise Article 108.04(b) of the Standard Specifications to read:

- "(b) No working day will be charged under the following conditions.
 - (1) When adverse weather prevents work on the controlling item.
 - (2) When job conditions due to recent weather prevent work on the controlling item.
 - (3) When conduct or lack of conduct by the Department or its consultants, representatives, officers, agents, or employees; delay by the Department in making the site available; or delay in furnishing any items required to be furnished to the Contractor by the Department prevents work on the controlling item.
 - (4) When delays caused by utility or railroad adjustments prevent work on the controlling item.
 - (5) When strikes, lock-outs, extraordinary delays in transportation, or inability to procure critical materials prevent work on the controlling item, as long as these delays are not due to any fault of the Contractor.
 - (6) When any condition over which the Contractor has no control prevents work on the controlling item."

Revise Article 109.09(f) of the Standard Specifications to read:

"(f) Basis of Payment. After resolution of a claim in favor of the Contractor, any adjustment in time required for the work will be made according to Section 108. Any adjustment in the costs to be paid will be made for direct labor, direct materials, direct equipment, direct jobsite overhead, direct offsite overhead, and other direct costs allowed by the resolution. Adjustments in costs will not be made for interest charges, loss of anticipated profit, undocumented loss of efficiency, home office overhead and unabsorbed overhead other than as allowed by Article 109.13, lost opportunity, preparation of claim expenses and other consequential indirect costs regardless of method of calculation.

The above Basis of Payment is an essential element of the contract and the claim cost recovery of the Contractor shall be so limited."

Add the following to Section 109 of the Standard Specifications.

"**109.13 Payment for Contract Delay.** Compensation for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be allowed when such costs result from a delay meeting the criteria in the following table.

Contract Type	Cause of Delay	Length of Delay
Working Days	Article 108.04(b)(3) or Article 108.04(b)(4)	No working days have been charged for two consecutive weeks.
Completion Date	Article 108.08(b)(1) or Article 108.08(b)(7)	The Contractor has been granted a minimum two week extension of contract time, according to Article 108.08.

Payment for each of the various costs will be according to the following.

- (a) Escalated Material and/or Labor Costs. When the delay causes work, which would have otherwise been completed, to be done after material and/or labor costs have increased, such increases will be paid. Payment for escalated material costs will be limited to the increased costs substantiated by documentation furnished by the Contractor. Payment for escalated labor costs will be limited to those items in Article 109.04(b)(1) and (2), except the 35 percent and 10 percent additives will not be permitted.
- (b) Extended Project Overhead. For the duration of the delay, payment for extended project overhead will be paid as follows.
 - (1) Direct Jobsite and Offsite Overhead. Payment for documented direct jobsite overhead and documented direct offsite overhead, including onsite supervisory and administrative personnel, will be allowed according to the following table.

Original Contract Amount	Supervisory and Administrative Personnel	
Up to \$5,000,000	One Project Superintendent	
Over \$ 5,000,000 - up to \$25,000,000	One Project Manager, One Project Superintendent or Engineer, and One Clerk	
Over \$25,000,000 - up to \$50,000,000	One Project Manager, One Project Superintendent, One Engineer, and	

	One Clerk
Over \$50,000,000	One Project Manager,
	Two Project Superintendents,
	One Engineer, and
	One Clerk

- (2) Home Office and Unabsorbed Overhead. Payment for home office and unabsorbed overhead will be calculated as 8 percent of the total delay cost.
- (c) Extended Traffic Control. Traffic control required for an extended period of time due to the delay will be paid. For working day contracts the payment will be made according to Article 109.04. For completion date contracts, an adjustment will be determined as follows.

Extended Traffic Control occurs between April 1 and November 30:

ETCP Adjustment () = TE x ($%/100 \times CUP / OCT$)

Extended Traffic Control occurs between December 1 and March 31:

ETCP Adjustment (\$) = TE x 1.5 (%/100 x CUP / OCT)

Where: TE = Duration of approved time extension in calendar days.

% = Percent maintenance for the traffic control, % (see table below).

CUP = Contract unit price for the traffic control pay item in place during the delay.

OCT = Original contract time in calendar days.

Original Contract Amount	Percent Maintenance
Up to \$2,000,000	65%
\$2,000,000 to \$10,000,000	75%
\$10,000,000 to \$20,000,000	85%
Over \$20,000,000	90%

When an ETCP adjustment is paid under this provision, an adjusted unit price as provided for in Article 701.20(a) for increase or decrease in the value of work by more than ten percent will not be paid.

Upon payment for a contract delay under this provision, the Contractor shall assign subrogation rights to the Department for the Department's efforts of recovery from any other party for monies paid by the Department as a result of any claim under this provision. The Contractor shall fully cooperate with the Department in its efforts to recover from another party any money paid to the Contractor for delay damages under this provision."

80384

CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)

Effective: June 1, 2010

Revised: November 1, 2014

The reduction of emissions of particulate matter (PM) for off-road equipment shall be accomplished by installing retrofit emission control devices. The term "equipment" refers to diesel fuel powered devices rated at 50 hp and above, to be used on the jobsite in excess of seven calendar days over the course of the construction period on the jobsite (including rental equipment).

Contractor and subcontractor diesel powered off-road equipment assigned to the contract shall be retrofitted using the phased in approach shown below. Equipment that is of a model year older than the year given for that equipment's respective horsepower range shall be retrofitted:

Effective Dates	Horsepower Range	Model Year
June 1, 2010 ^{1/}	600-749	2002
	750 and up	2006
June 1, 2011 ^{2/}	100-299	2003
	300-599	2001
	600-749	2002
	750 and up	2006
June 1, 2012 ^{2/}	50-99	2004
	100-299	2003
	300-599	2001
	600-749	2002
	750 and up	2006

1/ Effective dates apply to Contractor diesel powered off-road equipment assigned to the contract.

2/ Effective dates apply to Contractor and subcontractor diesel powered off-road equipment assigned to the contract.

The retrofit emission control devices shall achieve a minimum PM emission reduction of 50 percent and shall be:

- a) Included on the U.S. Environmental Protection Agency (USEPA) *Verified Retrofit Technology List* (<u>http://www.epa.gov/cleandiesel/verification/verif-list.htm</u>), or verified by the California Air Resources Board (CARB) (<u>http://www.arb.ca.gov/diesel/verdev/vt/cvt.htm</u>); or
- b) Retrofitted with a non-verified diesel retrofit emission control device if verified retrofit emission control devices are not available for equipment proposed to be used on the project, and if the Contractor has obtained a performance certification from the retrofit

device manufacturer that the emission control device provides a minimum PM emission reduction of 50 percent.

Note: Large cranes (Crawler mounted cranes) which are responsible for critical lift operations are exempt from installing retrofit emission control devices if such devices adversely affect equipment operation.

Diesel powered off-road equipment with engine ratings of 50 hp and above, which are unable to be retrofitted with verified emission control devices or if performance certifications are not available which will achieve a minimum 50 percent PM reduction, may be granted a waiver by the Department if documentation is provided showing good faith efforts were made by the Contractor to retrofit the equipment.

Construction shall not proceed until the Contractor submits a certified list of the diesel powered off-road equipment that will be used, and as necessary, retrofitted with emission control devices. The list(s) shall include (1) the equipment number, type, make, Contractor/rental company name; and (2) the emission control devices make, model, USEPA or CARB verification number, or performance certification from the retrofit device manufacturer. Equipment reported as fitted with emissions control devices shall be made available to the Engineer for visual inspection of the device installation, prior to being used on the jobsite.

The Contractor shall submit an updated list of retrofitted off-road construction equipment as retrofitted equipment changes or comes on to the jobsite. The addition or deletion of any diesel powered equipment shall be included on the updated list.

If any diesel powered off-road equipment is found to be in non-compliance with any portion of this special provision, the Engineer will issue the Contractor a diesel retrofit deficiency deduction.

Any costs associated with retrofitting any diesel powered off-road equipment with emission control devices shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed. The Contractor's compliance with this notice and any associated regulations shall not be grounds for a claim.

Diesel Retrofit Deficiency Deduction

When the Engineer determines that a diesel retrofit deficiency exists, a daily monetary deduction will be imposed for each calendar day or fraction thereof the deficiency continues to exist. The calendar day(s) will begin when the time period for correction is exceeded and end with the Engineer's written acceptance of the correction. The daily monetary deduction will be \$1,000.00 for each deficiency identified.

The deficiency will be based on lack of diesel retrofit emissions control.

If a Contractor accumulates three diesel retrofit deficiency deductions for the same piece of equipment in a contract period, the Contractor will be shutdown until the deficiency is corrected.

Such a shutdown will not be grounds for any extension of the contract time, waiver of penalties, or be grounds for any claim.

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)

Effective: September 1, 2000 Revised: July 2, 2016

<u>FEDERAL OBLIGATION</u>. The Department of Transportation, as a recipient of federal financial assistance, is required to take all necessary and reasonable steps to ensure nondiscrimination in the award and administration of contracts. Consequently, the federal regulatory provisions of 49 CFR Part 26 apply to this contract concerning the utilization of disadvantaged business enterprises. For the purposes of this Special Provision, a disadvantaged business enterprise (DBE) means a business certified by the Department in accordance with the requirements of 49 CFR Part 26 and listed in the Illinois Unified Certification Program (IL UCP) DBE Directory.

<u>STATE OBLIGATION</u>. This Special Provision will also be used by the Department to satisfy the requirements of the Business Enterprise for Minorities, Females, and Persons with Disabilities Act, 30 ILCS 575. When this Special Provision is used to satisfy state law requirements on 100 percent state-funded contracts, the federal government has no involvement in such contracts (not a federal-aid contract) and no responsibility to oversee the implementation of this Special Provision by the Department on those contracts. DBE participation on 100 percent state-funded contracts will not be credited toward fulfilling the Department's annual overall DBE goal required by the US Department of Transportation to comply with the federal DBE program requirements.

<u>CONTRACTOR ASSURANCE</u>. The Contractor makes the following assurance and agrees to include the assurance in each subcontract that the Contractor signs with a subcontractor.

The Contractor, subrecipient, or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The Contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of contracts funded in whole or in part with federal or state funds. Failure by the Contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate, which may include, but is not limited to:

- (a) Withholding progress payments;
- (b) Assessing sanctions;
- (c) Liquidated damages; and/or
- (d) Disqualifying the Contractor from future bidding as non-responsible.

<u>OVERALL GOAL SET FOR THE DEPARTMENT</u>. As a requirement of compliance with 49 CFR Part 26, the Department has set an overall goal for DBE participation in its federally assisted contracts. That goal applies to all federal-aid funds the Department will expend in its federally assisted contracts for the subject reporting fiscal year. The Department is required to make a

good faith effort to achieve the overall goal. The dollar amount paid to all approved DBE companies performing work called for in this contract is eligible to be credited toward fulfillment of the Department's overall goal.

<u>CONTRACT GOAL TO BE ACHIEVED BY THE CONTRACTOR</u>. This contract includes a specific DBE utilization goal established by the Department. The goal has been included because the Department has determined that the work of this contract has subcontracting opportunities that may be suitable for performance by DBE companies. The determination is based on an assessment of the type of work, the location of the work, and the availability of DBE companies to do a part of the work. The assessment indicates that, in the absence of unlawful discrimination, and in an arena of fair and open competition, DBE companies can be expected to perform <u>12.00</u>% of the work. This percentage is set as the DBE participation goal for this contract. Consequently, in addition to the other award criteria established for this contract, the Department will only award this contract to a bidder who makes a good faith effort to meet this goal of DBE participation in the performance of the work. A bidder makes a good faith effort to meet this goal of DBE participation if either of the following is done in accordance with the procedures set for in this Special Provision:

- (a) The bidder documents that enough DBE participation has been obtained to meet the goal or,
- (b) The bidder documents that a good faith effort has been made to meet the goal, even though the effort did not succeed in obtaining enough DBE participation to meet the goal.

<u>DBE LOCATOR REFERENCES</u>. Bidders shall consult the IL UCP DBE Directory as a reference source for DBE-certified companies. In addition, the Department maintains a letting and item specific DBE locator information system whereby DBE companies can register their interest in providing quotes on particular bid items advertised for letting. Information concerning DBE companies willing to quote work for particular contracts may be obtained by contacting the Department's Bureau of Small Business Enterprises at telephone number (217) 785-4611, or by visiting the Department's website at:

http://www.idot.illinois.gov/doing-business/certifications/disadvantaged-business-enterprisecertification/il-ucp-directory/index.

<u>BIDDING PROCEDURES</u>. Compliance with this Special Provision is required prior to the award of the contract and the failure of the low bidder to comply will render the bid not responsive.

In order to assure the timely award of the contract, the low bidder shall submit:

- (a) The bidder shall submit a DBE Utilization Plan on completed Department forms SBE 2025 and 2026.
 - (1) The final Utilization Plan must be submitted within five calendar days after the date of the letting in accordance with subsection (a)(2) of Bidding Procedures herein.

(2) To meet the five day requirement, the bidder may send the Utilization Plan electronically by scanning and sending to <u>DOT.DBE.UP@illinois.gov</u> or faxing to (217) 785-1524. The subject line must include the bid Item Number and the Letting date. The Utilization Plan should be sent as one .pdf file, rather than multiple files and emails for the same Item Number. It is the responsibility of the bidder to obtain confirmation of email or fax delivery.

Alternatively, the Utilization Plan may be sent by certified mail or delivery service within the five calendar day period. If a question arises concerning the mailing date of a Utilization Plan, the mailing date will be established by the U.S. Postal Service postmark on the certified mail receipt from the U.S. Postal Service or the receipt issued by a delivery service when the Utilization Plan is received by the Department. It is the responsibility of the bidder to ensure the postmark or receipt date is affixed within the five days if the bidder intends to rely upon mailing or delivery to satisfy the submission day requirement. The Utilization Plan is to be submitted to:

Illinois Department of Transportation Bureau of Small Business Enterprises Contract Compliance Section 2300 South Dirksen Parkway, Room 319 Springfield, Illinois 62764

The Department will not accept a Utilization Plan if it does not meet the five day submittal requirement and the bid will be declared not responsive. In the event the bid is declared not responsive due to a failure to submit a Utilization Plan or failure to comply with the bidding procedures set forth herein, the Department may elect to cause the forfeiture of the penal sum of the bidder's proposal guaranty, and may deny authorization to bid the project if re-advertised for bids. The Department reserves the right to invite any other bidder to submit a Utilization Plan at any time for award consideration.

- (b) The Utilization Plan shall indicate that the bidder either has obtained sufficient DBE participation commitments to meet the contract goal or has not obtained enough DBE participation commitments in spite of a good faith effort to meet the goal. The Utilization Plan shall further provide the name, telephone number, and telefax number of a responsible official of the bidder designated for purposes of notification of Utilization Plan approval or disapproval under the procedures of this Special Provision.
- (c) The Utilization Plan shall include a DBE Participation Commitment Statement, Department form SBE 2025, for each DBE proposed for the performance of work to achieve the contract goal. For bidding purposes, submission of the completed SBE 2025 forms, signed by the DBEs and scanned or faxed to the bidder will be acceptable as long as the original is available and provided upon request. All elements of information indicated on the said form shall be provided, including but not limited to the following:

- (1) The names and addresses of DBE firms that will participate in the contract;
- (2) A description, including pay item numbers, of the work each DBE will perform;
- (3) The dollar amount of the participation of each DBE firm participating. The dollar amount of participation for identified work shall specifically state the quantity, unit price, and total subcontract price for the work to be completed by the DBE. If partial pay items are to be performed by the DBE, indicate the portion of each item, a unit price where appropriate and the subcontract price amount;
- (4) DBE Participation Commitment Statements, form SBE 2025, signed by the bidder and each participating DBE firm documenting the commitment to use the DBE subcontractors whose participation is submitted to meet the contract goal;
- (5) If the bidder is a joint venture comprised of DBE companies and non-DBE companies, the Utilization Plan must also include a clear identification of the portion of the work to be performed by the DBE partner(s); and,
- (6) If the contract goal is not met, evidence of good faith efforts; the documentation of good faith efforts must include copies of each DBE and non-DBE subcontractor quote submitted to the bidder when a non-DBE subcontractor is selected over a DBE for work on the contract.

GOOD FAITH EFFORT PROCEDURES. The contract will not be awarded until the Utilization Plan submitted by the apparent successful bidder is approved. All information submitted by the bidder must be complete, accurate and adequately document that enough DBE participation has been obtained or document that good faith efforts of the bidder, in the event enough DBE participation has not been obtained, before the Department will commit to the performance of the contract by the bidder. The Utilization Plan will be approved by the Department if the Utilization Plan documents sufficient commercially useful DBE work to meet the contract goal or the bidder submits sufficient documentation of a good faith effort to meet the contract goal pursuant to 49 CFR Part 26, Appendix A. The Utilization Plan will not be approved by the Department if the Utilization Plan does not document sufficient DBE participation to meet the contract goal unless the apparent successful bidder documented in the Utilization Plan that it made a good faith effort to meet the goal. This means that the bidder must show that all necessary and reasonable steps were taken to achieve the contract goal. Necessary and reasonable steps are those which, by their scope, intensity and appropriateness to the objective, could reasonably be expected to obtain sufficient DBE participation, even if they were not successful. The Department will consider the quality, quantity, and intensity of the kinds of efforts that the bidder has made. Mere pro forma efforts, in other words, efforts done as a matter of form, are not good faith efforts; rather, the bidder is expected to have taken genuine efforts that would be reasonably expected of a bidder actively and aggressively trying to obtain DBE participation sufficient to meet the contract goal.

(a) The following is a list of types of action that the Department will consider as part of the evaluation of the bidder's good faith efforts to obtain participation. These listed factors

are not intended to be a mandatory checklist and are not intended to be exhaustive. Other factors or efforts brought to the attention of the Department may be relevant in appropriate cases, and will be considered by the Department.

- (1) Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBE companies that have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBE companies to respond to the solicitation. The bidder must determine with certainty if the DBE companies are interested by taking appropriate steps to follow up initial solicitations.
- (2) Selecting portions of the work to be performed by DBE companies in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the prime Contractor might otherwise prefer to perform these work items with its own forces.
- (3) Providing interested DBE companies with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.
- (4) a. Negotiating in good faith with interested DBE companies. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBE companies that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBE companies to perform the work.
 - b. A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBE companies is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also the ability or desire of a bidder to perform the work of a contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Bidders are not, however, required to accept higher quotes from DBE companies if the price difference is excessive or unreasonable. In accordance with subsection (c)(6) of the above Bidding Procedures, the documentation of good faith efforts must include copies of each DBE and non-DBE subcontractor quote submitted to the bidder when a non-DBE subcontractor was selected over a DBE for work on the contract.

- (5) Not rejecting DBE companies as being unqualified without sound reasons based on a thorough investigation of their capabilities. The bidder's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non-solicitation of bids in the bidder's efforts to meet the project goal.
- (6) Making efforts to assist interested DBE companies in obtaining bonding, lines of credit, or insurance as required by the recipient or Contractor.
- (7) Making efforts to assist interested DBE companies in obtaining necessary equipment, supplies, materials, or related assistance or services.
- (8) Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBE companies.
- (b) If the Department determines that the apparent successful bidder has made a good faith effort to secure the work commitment of DBE companies to meet the contract goal, the Department will award the contract provided that it is otherwise eligible for award. If the Department determines that the bidder has failed to meet the requirements of this Special Provision or that a good faith effort has not been made, the Department will notify the responsible company official designated in the Utilization Plan that the bid is not responsive. The notification shall include a statement of reasons for the determination. If the Utilization Plan is not approved because it is deficient as a technical matter, unless waived by the Department, the bidder will be notified and will be allowed no more than a five calendar day period in order to cure the deficiency.
- (c) The bidder may request administrative reconsideration of a determination adverse to the bidder within the five working days after the receipt of the notification date of the determination by delivering the request to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764 (Telefax: (217) 785-1524). Deposit of the request in the United States mail on or before the fifth business day shall not be deemed delivery. The determination shall become final if a request is not made and delivered. A request may provide additional written documentation or argument concerning the issues raised in the determination statement of reasons, provided the documentation and arguments address efforts made prior to submitting the bid. The request will be forwarded to the Department's Reconsideration Officer. The Reconsideration Officer will extend an opportunity to the bidder to meet in person in order to consider all issues of documentation and whether the bidder made a good faith effort to meet the goal. After the review by the Reconsideration Officer, the bidder will be sent a written decision within ten working days after receipt of the request for consideration, explaining the basis for finding that the bidder did or did not meet the goal or make adequate good faith efforts to do so. A final decision by the Reconsideration

Officer that a good faith effort was made shall approve the Utilization Plan submitted by the bidder and shall clear the contract for award. A final decision that a good faith effort was not made shall render the bid not responsive.

<u>CALCULATING DBE PARTICIPATION</u>. The Utilization Plan values represent work anticipated to be performed and paid for upon satisfactory completion. The Department is only able to count toward the achievement of the overall goal and the contract goal the value of payments made for the work actually performed by DBE companies. In addition, a DBE must perform a commercially useful function on the contract to be counted. A commercially useful function is generally performed when the DBE is responsible for the work and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. The Department and Contractor are governed by the provisions of 49 CFR Part 26.55(c) on questions of commercially useful functions as it affects the work. Specific counting guidelines are provided in 49 CFR Part 26.55, the provisions of which govern over the summary contained herein.

- (a) DBE as the Contractor: 100 percent goal credit for that portion of the work performed by the DBE's own forces, including the cost of materials and supplies. Work that a DBE subcontracts to a non-DBE does not count toward the DBE goals.
- (b) DBE as a joint venture Contractor: 100 percent goal credit for that portion of the total dollar value of the contract equal to the distinct, clearly defined portion of the work performed by the DBE's own forces.
- (c) DBE as a subcontractor: 100 percent goal credit for the work of the subcontract performed by the DBE's own forces, including the cost of materials and supplies, excluding the purchase of materials and supplies or the lease of equipment by the DBE subcontractor from the prime Contractor or its affiliates. Work that a DBE subcontractor in turn subcontracts to a non-DBE does not count toward the DBE goal.
- (d) DBE as a trucker: 100 percent goal credit for trucking participation provided the DBE is responsible for the management and supervision of the entire trucking operation for which it is responsible. At least one truck owned, operated, licensed, and insured by the DBE must be used on the contract. Credit will be given for the following:
 - (1) The DBE may lease trucks from another DBE firm, including an owner-operator who is certified as a DBE. The DBE who leases trucks from another DBE receives credit for the total value of the transportation services the lessee DBE provides on the contract.
 - (2) The DBE may also lease trucks from a non-DBE firm, including from an owneroperator. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission is receives as a result of the lease arrangement.
- (e) DBE as a material supplier:

- (1) 60 percent goal credit for the cost of the materials or supplies purchased from a DBE regular dealer.
- (2) 100 percent goal credit for the cost of materials of supplies obtained from a DBE manufacturer.
- (3) 100 percent credit for the value of reasonable fees and commissions for the procurement of materials and supplies if not a DBE regular dealer or DBE manufacturer.

<u>CONTRACT COMPLIANCE</u>. Compliance with this Special Provision is an essential part of the contract. The Department is prohibited by federal regulations from crediting the participation of a DBE included in the Utilization Plan toward either the contract goal or the Department's overall goal until the amount to be applied toward the goals has been paid to the DBE. The following administrative procedures and remedies govern the compliance by the Contractor with the contractual obligations established by the Utilization Plan. After approval of the Utilization Plan and award of the contract, the Utilization Plan and individual DBE Participation Statements become part of the contract. If the Contract goal, and the Utilization Plan was approved and contract awarded based upon a determination of good faith, the total dollar value of DBE work calculated in the approved Utilization Plan as a percentage of the awarded contract value shall be come the amended contract goal. All work indicated for performance by an approved DBE shall be performed, managed, and supervised by the DBE executing the DBE Participation Commitment Statement.

- (a) <u>NO AMENDMENT</u>. No amendment to the Utilization Plan may be made without prior written approval from the Department's Bureau of Small Business Enterprises. All requests for amendment to the Utilization Plan shall be submitted to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764. Telephone number (217) 785-4611. Telefax number (217) 785-1524.
- (b) <u>CHANGES TO WORK</u>. Any deviation from the DBE condition-of-award or contract plans, specifications, or special provisions must be approved, in writing, by the Department as provided elsewhere in the Contract. The Contractor shall notify affected DBEs in writing of any changes in the scope of work which result in a reduction in the dollar amount condition-of-award to the contract. Where the revision includes work committed to a new DBE subcontractor, not previously involved in the project, then a Request for Approval of Subcontractor, Department form BC 260A or AER 260A, must be signed and submitted. If the commitment of work is in the form of additional tasks assigned to an existing subcontract, than a new Request for Approval of Subcontractor shall not be required. However, the Contractor must document efforts to assure that the existing DBE subcontractor is capable of performing the additional work and has agreed in writing to the change.

- (c) <u>SUBCONTRACT</u>. The Contractor must provide DBE subcontracts to IDOT upon request. Subcontractors shall ensure that all lower tier subcontracts or agreements with DBEs to supply labor or materials be performed in accordance with this Special Provision.
- (d) <u>ALTERNATIVE WORK METHODS</u>. In addition to the above requirements for reductions in the condition of award, additional requirements apply to the two cases of Contractorinitiated work substitution proposals. Where the contract allows alternate work methods which serve to delete or create underruns in condition of award DBE work, and the Contractor selects that alternate method or, where the Contractor proposes a substitute work method or material that serves to diminish or delete work committed to a DBE and replace it with other work, then the Contractor must demonstrate one of the following:
 - (1) That the replacement work will be performed by the same DBE (as long as the DBE is certified in the respective item of work) in a modification of the condition of award; or
 - (2) That the DBE is aware that its work will be deleted or will experience underruns and has agreed in writing to the change. If this occurs, the Contractor shall substitute other work of equivalent value to a certified DBE or provide documentation of good faith efforts to do so; or
 - (3) That the DBE is not capable of performing the replacement work or has declined to perform the work at a reasonable competitive price. If this occurs, the Contractor shall substitute other work of equivalent value to a certified DBE or provide documentation of good faith efforts to do so.
- (e) <u>TERMINATION AND REPLACEMENT PROCEDURES</u>. The Contractor shall not terminate or replace a DBE listed on the approved Utilization Plan, or perform with other forces work designated for a listed DBE except as provided in this Special Provision. The Contractor shall utilize the specific DBEs listed to perform the work and supply the materials for which each is listed unless the Contractor obtains the Department's written consent as provided in subsection (a) of this part. Unless Department consent is provided for termination of a DBE subcontractor, the Contractor shall not be entitled to any payment for work or material unless it is performed or supplied by the DBE in the Utilization Plan.

As stated above, the Contractor shall not terminate or replace a DBE subcontractor listed in the approved Utilization Plan without prior written consent. This includes, but is not limited to, instances in which the Contractor seeks to perform work originally designated for a DBE subcontractor with its own forces or those of an affiliate, a non-DBE firm, or with another DBE firm. Written consent will be granted only if the Bureau of Small Business Enterprises agrees, for reasons stated in its concurrence document, that the Contractor has good cause to terminate or replace the DBE firm. Before transmitting to the Bureau of Small Business Enterprises any request to terminate and/or substitute a DBE subcontractor, the Contractor shall give notice in writing to the DBE subcontractor,

with a copy to the Bureau, of its intent to request to terminate and/or substitute, and the reason for the request. The Contractor shall give the DBE five days to respond to the Contractor's notice. The DBE so notified shall advise the Bureau and the Contractor of the reasons, if any, why it objects to the proposed termination of its subcontract and why the Bureau should not approve the Contractor's action. If required in a particular case as a matter of public necessity, the Bureau may provide a response period shorter than five days.

For purposes of this paragraph, good cause includes the following circumstances:

- (1) The listed DBE subcontractor fails or refuses to execute a written contract;
- (2) The listed DBE subcontractor fails or refuses to perform the work of its subcontract in a way consistent with normal industry standards. Provided, however, that good cause does not exist if the failure or refusal of the DBE subcontractor to perform its work on the subcontract results from the bad faith or discriminatory action of the prime contractor;
- (3) The listed DBE subcontractor fails or refuses to meet the prime Contractor's reasonable, nondiscriminatory bond requirements;
- (4) The listed DBE subcontractor becomes bankrupt, insolvent, or exhibits credit unworthiness;
- (5) The listed DBE subcontractor is ineligible to work on public works projects because of suspension and debarment proceedings pursuant 2 CFR Parts 180, 215 and 1200 or applicable state law.
- (6) You have determined that the listed DBE subcontractor is not a responsible contractor;
- (7) The listed DBE subcontractor voluntarily withdraws from the projects and provides to you written notice of its withdrawal;
- (8) The listed DBE is ineligible to receive DBE credit for the type of work required;
- (9) A DBE owner dies or becomes disabled with the result that the listed DBE subcontractor is unable to complete its work on the contract;
- (10) Other documented good cause that compels the termination of the DBE subcontractor. Provided, that good cause does not exist if the prime Contractor seeks to terminate a DBE it relied upon to obtain the contract so that the prime Contractor can self-perform the work for which the DBE contractor was engaged or so that the prime Contractor can substitute another DBE or non-DBE contractor after contract award.

When a DBE is terminated, or fails to complete its work on the Contract for any reason the Contractor shall make a good faith effort to find another DBE to substitute for the original DBE to perform at least the same amount of work under the contract as the terminated DBE to the extent needed to meet the established Contract goal. The good faith efforts shall be documented by the Contractor. If the Department requests documentation under this provision, the Contractor shall submit the documentation within seven days, which may be extended for an additional seven days if necessary at the request of the Contractor. The Department shall provide a written determination to the Contractor stating whether or not good faith efforts have been demonstrated.

- (f) PAYMENT RECORDS. The Contractor shall maintain a record of payments for work performed to the DBE participants. The records shall be made available to the Department for inspection upon request. After the performance of the final item of work or delivery of material by a DBE and final payment therefore to the DBE by the Contractor, but not later than thirty calendar days after payment has been made by the Department to the Contractor for such work or material, the Contractor shall submit a DBE Payment Agreement on Department form SBE 2115 to the Resident Engineer. If full and final payment has not been made to the DBE, the DBE Payment Agreement shall indicate whether a disagreement as to the payment required exists between the Contractor and the DBE or if the Contractor believes that the work has not been satisfactorily completed. If the Contractor does not have the full amount of work indicated in the Utilization Plan performed by the DBE companies indicated in the Utilization Plan and after good faith efforts are reviewed, the Department may deduct from contract payments to the Contractor the amount of the goal not achieved as liquidated and ascertained damages. The Contractor may request an administrative reconsideration of any amount deducted as damages pursuant to subsection (h) of this part.
- (g) <u>ENFORCEMENT</u>. The Department reserves the right to withhold payment to the Contractor to enforce the provisions of this Special Provision. Final payment shall not be made on the contract until such time as the Contractor submits sufficient documentation demonstrating achievement of the goal in accordance with this Special Provision or after liquidated damages have been determined and collected.
- (h) <u>RECONSIDERATION</u>. Notwithstanding any other provision of the contract, including but not limited to Article 109.09 of the Standard Specifications, the Contractor my request administrative reconsideration of a decision to deduct the amount of the goal not achieved as liquidated damages. A request to reconsider shall be delivered to the Contract Compliance Section and shall be handled and considered in the same manner as set forth in paragraph (c) of "Good Faith Effort Procedures" of this Special Provision, except a final decision that a good faith effort was not made during contract performance to achieve the goal agreed to in the Utilization Plan shall be the final administrative decision of the Department. The result of the reconsideration process is not administratively appealable to the U.S. Department of Transportation.

DOWEL BAR INSERTER (BDE)

Effective: January 1, 2017 Revised: January 1, 2018

Add the following to Article 420.03 of the Standard Specifications.

Revise the first paragraph of Article 420.05(b)(1) of the Supplemental Specifications to read:

"Preformed or Drilled Holes. If applicable, the tie bars shall be installed after the dowel bars have been tested with the MIT Scan-2 device according to Article 420.05(c)(2)b.2. The tie bars shall be installed with a nonshrink grout or chemical adhesive providing a minimum pull-out strength as follows."

Revise Article 420.05(c) of the Standard Specifications to read:

"(c) Transverse Contraction Joints. Transverse contraction joints shall consist of planes of weakness created by sawing grooves in the surface of the pavement and shall include load transfer devices consisting of dowel bars. Transverse contraction joints shall be according to the following."

Revise Article 420.05(c)(2) of the Standard Specifications to read:

- "(2) Dowel Bars. Dowel Bars shall be installed parallel to the centerline of the pavement and parallel to the proposed pavement surface. Installation shall be according to one of the following methods.
 - a. Dowel Bar Assemblies. The assembly shall act as a rigid unit with each component securely held in position relative to the other members of the assembly. The entire assembly shall be held securely in place by means of nails which shall penetrate the stabilized subbase. At least ten nails shall be used for each 10, 11, or 12 ft (3, 3.3, or 3.6 m) section of assembly.

Metal stakes shall be used instead of nails, with soil or granular subbase. The stakes shall loop over or attach to the top parallel spacer bar of the assembly and penetrate the subgrade or subbase at least 12 in. (300 mm).

At the location of each dowel bar assembly, the subgrade or subbase shall be reshaped and re-tamped when necessary.

Prior to placing concrete, any deviation of the dowel bars from the correct horizontal or vertical alignment (horizontal skew or vertical tilt) greater than 3/8 in. in 12 in (9 mm in 300 mm) shall be corrected and a light coating of oil shall be uniformly applied to all dowel bars.

Care shall be exercised in depositing the concrete at the dowel bar assemblies so the horizontal and vertical alignment will be retained.

b. Dowel Bar Insertion. The dowel bars may be placed in the pavement slab with a mechanical dowel bar inserter (DBI) attached to a formless paver for pavements ≥ 7.0 in. (175 mm) in thickness. A light coating of oil shall be uniformly applied to all dowel bars.

The DBI shall insert the dowel bars with vibration into the plastic concrete after the concrete has been struck off and consolidated without deformation of the slab. After the bars have been inserted, the concrete shall be refinished and no voids shall exist around the dowel bars. The forward movement of the paver shall not be interrupted by the inserting of the dowel bars.

The location of each row of dowel bars shall be marked in a manner to facilitate where to insert the bars, and where to saw the transverse joint.

- 1. Placement Tolerances for Dowel Bars. The DBI shall place the dowel bars in the concrete pavement within the following tolerances.
 - (a.)Longitudinal Translation (Mislocation). Longitudinal translation (mislocation) shall be defined as the position of the center of the dowel bar along the longitudinal axis, in relation to the sawed joint.

The quality control tolerance for longitudinal translation shall not exceed 2.0 in (50 mm). If this tolerance is exceeded, adjustments shall be made to the paving operation.

Any joint having two or more dowel bars with an embedment length less than 4.0 in. (100 mm) within 12 in. (300 mm) of the same wheelpath will be considered unacceptable. The left and right wheelpaths shall be determined by excluding the middle 2.5 ft (0.8 m) of the pavement lane, and by excluding the outer 1.0 ft (0.3 m) measured from each pavement lane edge. Any joint having an average dowel bar embedment length less than 5.25 in. (130 mm) will also be considered unacceptable. Embedment length shall be defined as the length of dowel bar embedded on the short side of the sawed joint. An unacceptable joint shall be replaced with a minimum of 6 ft (1.8 m) of pavement centered over the joint according to Section 442 for Class B patches.

(b.) Horizontal Translation (Mislocation). Horizontal translation (mislocation) shall be defined as the difference in the actual dowel bar location parallel to the longitudinal or edge joint from its theoretical position as shown on the plans.

The quality control tolerance for horizontal translation shall not exceed 2.0 in. (50 mm). If this tolerance is exceeded, adjustments shall be made to the paving operation.

Any joint having a dowel bar with a translation greater than 4.0 in. (100 mm) will be considered unacceptable, but may remain in place unless the Engineer determines the joint will not function. If the joint is unable to remain in place, the joint shall be replaced with a minimum of 6 ft (1.8 m) of pavement centered over the joint according to Section 442 for Class B patches.

(c.) Vertical Translation (Mislocation). Vertical translation (mislocation) shall be defined as the difference in the vertical position of the dowel bar relative to the theoretical midpoint of the slab.

The quality control tolerance for vertical translation shall be as shown in the following table. If these tolerances are exceeded, adjustments shall be made to the paving operation.

		Vertical	Vertical
Pavement Thickness	Dowel Bar	Translation	Translation
	Diameter	Tolerance	Tolerance
	Diameter	Above	Below
		Midpoint	Midpoint
≥7 in. to <8 in.	1.25 in.	0.25 in.	0.5 in.
(≥175 mm to <200 mm)	(31 mm)	(6 mm)	(13 mm)
≥8 in. to <9 in.	1.50 in.	0.25 in.	0.5 in.
(≥200 mm to <225 mm)	(38 mm)	(6 mm)	(13 mm)
≥9 in. to <10 in.	1.50 in.	0.75 in.	0.75 in.
(≥225 mm to <250 mm)	(38 mm)	(19 mm)	(19 mm)
≥10 in.	1.50 in.	0.75 in.	1.0 in.
(≥250 mm)	(38 mm)	(19 mm)	(25 mm)

Any joint having a dowel bar with top concrete cover less than T/3, where T is slab thickness, will be considered unacceptable. Any joint having 2 or more dowel bars with bottom concrete cover less than 2.0 in. (50 mm) will also be considered unacceptable. An unacceptable joint shall be replaced with a minimum of 6 ft (1.8 m) of pavement according to Section 442 for Class B patches.

(d.) Vertical Tilt or Horizontal Skew (Misalignment). Vertical tilt or horizontal skew (misalignment) shall be defined as the difference in position of the dowel bar ends with respect to each other. Vertical tilt is measured in the vertical axis whereas horizontal skew is measured in the horizontal axis. Misalignment shall be measured in terms of a joint score. The joint score shall be defined as the degree of misalignment evaluated for a single transverse joint for each lane of pavement. The joint score shall be determined as follows:

Joint Score =
$$\left(1 + \left(\frac{x}{x-n}\right)\sum_{i=1}^{x-n} W_i\right)$$

where:

- W_i = weighting factor (Table 1) for dowel *i*
- x = number of dowels in a single joint
- *n* = number of dowels excluded from the joint score calculation due to measurement interference

Single Dowel Misalignment – The degree of misalignment applicable to a single dowel bar, calculated as:

Single Dowel Misalignment = $\sqrt{(Horizontal Skew)^2 + (Vertical Tilt)^2}$

Table 1. Weighting Factors in Joint Score Determination	
Single Dowel Bar Misalignment (SDM)	W, Weighting Factor
SDM ≤ 0.6 in. (15 mm)	0
0.6 in. (15 mm) < SDM ≤ 0.8 in. (20 mm)	2
0.8 in. (20 mm) < SDM ≤ 1 in. (25 mm)	4
1 in. (25 mm) < SDM ≤ 1.5 in. (38 mm)	5
1.5 in. (38 mm) < SDM 10	

The quality control tolerance for vertical tilt or horizontal skew shall not exceed 0.6 in. (15 mm). If the tolerance is exceeded for either one, adjustments shall be made to the paving operation.

Any joint having a dowel bar with a vertical tilt or horizontal skew greater than 1.5 in. (38 mm) shall be cut. If more than one dowel bar is required to be cut in the joint, the joint will be considered unacceptable and shall be replaced with a minimum of 6 ft (1.8 m) of pavement centered over the joint according to Section 442 for Class B patches.

Single dowel bar misalignment shall be controlled to provide the joint scores shown in the following table.

Number of Dowel Bars in the Joint	Maximum Joint Score
< 5	4
≥ 5 but ≤ 9	8
> 9	12

A joint score greater than the specified maximum will be considered locked. Three consecutive joints with a score greater than the specified maximum total score will all be considered unacceptable.

Three consecutive locked joints shall be corrected by selecting one joint and cutting a dowel bar. Preference shall be given to cutting a dowel bar within the middle 2.5 ft (0.8 m) of the pavement lane to avoid the wheelpaths. If none of the three locked joints will have a joint score less than or equal to the specified maximum after selecting one dowel bar to cut, one of the joints shall be replaced with a minimum of 6 ft (1.8 m) of pavement centered over the joint according to Section 442 for Class B patches.

- (e.) For unacceptable work, the Contractor may propose alternative repairs for consideration by the Engineer.
- 2. Testing of Dowel Bar Placement. The placement of the dowel bars shall be tested within 24 hours of paving with a calibrated MIT Scan-2 device according to "Use of Magnetic Tomography Technology to Evaluate Dowel Placement" (Publication No. FHWA-IF-06-006) by the Federal Highway Administration.

A trained operator shall perform the testing, and all testing shall be performed in the presence of the Engineer. The device shall be calibrated to the type and size dowel bar used in the work according to the manufacturer's instructions. Calibration documentation shall be provided to the Engineer prior to construction. The device shall be recalibrated and/or validate readings as required by the Engineer. The device may be utilized as a process control and make necessary adjustments to ensure the dowel bars are placed in the correct location.

- (a.) Test Section. Prior to start of production paving, a test section consisting of 30 transverse joints shall be constructed. The test section may be performed on the actual pavement, but production paving shall not begin until an acceptable test section has been constructed. The test section will be considered acceptable when all of the following are met:
 - 90 percent of the dowel bars meet the quality control tolerance for longitudinal, horizontal, or vertical translation (mislocation);
 - (2.) 90 percent of the dowel bars meet the quality control tolerance for vertical tilt or horizontal skew deviation (misalignment); and
 - (3.) none of the joints are considered unacceptable prior to a corrective measure for mislocation or misalignment.

If the test section fails, another test section consisting of 30 joints shall be constructed.

The test section requirement may be waived by the Engineer if the Contractor has constructed an acceptable test section and successfully used the DBI on a Department contract within the same calendar year.

(b.) Production Paving. After the test section is approved, production paving may begin. The mislocation and misalignment of each dowel bar for the first ten joints constructed, and every tenth joint thereafter, shall be tested.

If two consecutive days of paving result in 5 percent or more of the joints on each day being unacceptable prior to a corrective measure, production paving shall be discontinued and a new test section shall be constructed.

If any joint is found to be unacceptable prior to a corrective measure, testing of additional joints on each side of the unacceptable joint shall be performed until acceptable joints are found.

- (c.) Test Report. Test reports shall be provided to the Engineer within two working days of completing each day's testing. The test report shall include the following.
 - (1.)Contract number, placement date, county-route-section, direction of traffic, scan date, Contractor, and name of individual performing the tests.
 - (2.) Provide the standard report generated from the on-board printer of the imaging technology used for every dowel and joint measured.
 - (3.) For every dowel measured, provide the joint identification number, lane number and station, dowel bar number or x-location, direction of testing and reference joint location/edge location, longitudinal translation, horizontal translation, vertical translation, vertical tilt, and horizontal skew.
 - (4.) Identify each dowel bar with a maximum longitudinal, horizontal, or vertical translation that has been exceeded. Identify each dowel bar with a maximum vertical tilt or horizontal skew deviation that has been exceeded.
 - (5.) Joint Score Details: Provide the joint identification number, lane number, station, and calculated joint score for each joint.

- (6.)Locked Joint Identification: Identify each joint where the maximum joint score is exceeded.
- (d.) Exclusions. Exclude the following from dowel bar mislocation and misalignment measurements.
 - (1.) Transverse construction joints (headers).
 - (2.)Dowel bars within 24 in. (610 mm) of metallic manholes, inlets, metallic castings, or other nearby or underlying steel reinforced objects.
 - (3.) The outside dowel bar when tie bars are installed with mechanical equipment in fresh concrete. For tie bar installations involving preformed or drilled holes, installation of the tie bar shall be performed after testing with the MIT Scan-2 device.
 - (4.) Joints located directly under high voltage power lines.
 - (5.)Subject to the approval of the Engineer, any other contributors to magnetic interference.
- (e.) Deficiency Deduction. When the Contractor has cut 25 dowel bars to correct unacceptable joints, the Contractor shall be liable and shall pay to the Department a deficiency deduction of \$500.00 for the cost of the bars. Thereafter, an additional deficiency deduction of \$20.00 for each additional bar cut will be assessed."

Add the following to Section 1103 of the Standard Specifications.

"**1103.20 Mechanical Dowel Bar Inserter.** The mechanical dowel bar inserter (DBI) shall be self-contained and supported on the formless paver with the ability to move separately from the paver. The DBI shall be equipped with insertion forks along with any other devices necessary for finishing the concrete the full width of the pavement. The insertion forks shall have the ability to vibrate at a minimum frequency of 3000 VPM."

EQUIPMENT PARKING AND STORAGE (BDE)

Effective: November 1, 2017

Replace the first paragraph of Article 701.11 of the Standard Specifications with the following.

"**701.11 Equipment Parking and Storage.** During working hours, all vehicles and/or nonoperating equipment which are parked, two hours or less, shall be parked at least 8 ft (2.5 m) from the open traffic lane. For other periods of time during working and for all nonworking hours, all vehicles, materials, and equipment shall be parked or stored as follows.

- (a) When the project has adequate right-of-way, vehicles, materials, and equipment shall be located a minimum of 30 ft (9 m) from the pavement.
- (b) When adequate right-of-way does not exist, vehicles, materials, and equipment shall be located a minimum of 15 ft (4.5 m) from the edge of any pavement open to traffic.
- (c) Behind temporary concrete barrier, vehicles, materials, and equipment shall be located a minimum of 24 in. (600 mm) behind free standing barrier or a minimum of 6 in. (150 mm) behind barrier that is either pinned or restrained according to Article 704.04. The 24 in. or 6 in. measurement shall be from the base of the non-traffic side of the barrier.
- (d) Behind other man-made or natural barriers meeting the approval of the Engineer."

HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE)

Effective: January 1, 2010 Revised: April 1, 2016

<u>Description</u>. This work shall consist of testing the density of longitudinal joints as part of the quality control/quality assurance (QC/QA) of hot-mix asphalt (HMA). Work shall be according to Section 1030 of the Standard Specifications except as follows.

<u>Quality Control/Quality Assurance (QC/QA)</u>. Delete the second and third sentence of the third paragraph of Article 1030.05(d)(3) of the Standard Specifications.

Add the following paragraphs to the end of Article 1030.05(d)(3) of the Standard Specifications:

"Longitudinal joint density testing shall be performed at each random density test location. Longitudinal joint testing shall be located at a distance equal to the lift thickness or a minimum of 4 in. (100 mm), from each pavement edge. (i.e. for a 5 in. (125 mm) lift the near edge of the density gauge or core barrel shall be within 5 in. (125 mm) from the edge of pavement.) Longitudinal joint density testing shall be performed using either a correlated nuclear gauge or cores.

- a. Confined Edge. Each confined edge density shall be represented by a oneminute nuclear density reading or a core density and shall be included in the average of density readings or core densities taken across the mat which represents the Individual Test.
- b. Unconfined Edge. Each unconfined edge joint density shall be represented by an average of three one-minute density readings or a single core density at the given density test location and shall meet the density requirements specified herein. The three one-minute readings shall be spaced 10 ft (3 m) apart longitudinally along the unconfined pavement edge and centered at the random density test location."

Revise the Density Control Limits table in Article 1030.05(d)(4) of the Standard Specifications to read:

"Mixture Composition	Parameter	Individual Test (includes confined	Unconfined Edge Joint Density
Composition		edges)	Minimum
IL-4.75	Ndesign = 50	93.0 - 97.4% 1/	91.0%
IL-9.5	Ndesign = 90	92.0 - 96.0%	90.0%
IL-9.5,IL-9.5L	Ndesign < 90	92.5 - 97.4%	90.0%
IL-19.0	Ndesign = 90	93.0 - 96.0%	90.0%
IL-19.0, IL-19.0L	Ndesign < 90	93.0 ^{2/} – 97.4%	90.0%
SMA	Ndesign = 50 & 80	93.5 - 97.4%	91.0%"

80246

HOT-MIX ASPHALT – TACK COAT (BDE)

Effective: November 1, 2016

Revise Article 1032.06(a) of the Standard Specifications to read:

"(a) Anionic Emulsified Asphalt. Anionic emulsified asphalts shall be according to AASHTO M 140. SS-1h emulsions used as a tack coat shall have the cement mixing test waived."

LIGHTS ON BARRICADES (BDE)

Effective: January 1, 2018

Revise Article 701.16 of the Standard Specifications to read:

***701.16 Lights.** Lights shall be used on devices as required in the plans, the traffic control plan, and the following table.

Circumstance	Lights Required
Daylight operations	None
First two warning signs on each approach to the work involving a nighttime lane closure and "ROUGH GROOVED SURFACE" (W8-I107) signs	Flashing mono-directional lights
Devices delineating isolated obstacles, excavations, or hazards at night (Does not apply to patching)	Flashing bi-directional lights
Devices delineating obstacles, excavations, or hazards exceeding 100 ft (30 m) in length at night (Does not apply to widening)	Steady burn bi-directional lights
Channelizing devices for nighttime lane closures on two-lane roads	None
Channelizing devices for nighttime lane closures on multi-lane roads	None
Channelizing devices for nighttime lane closures on multi-lane roads separating opposing directions of traffic	None
Channelizing devices for nighttime along lane shifts on multilane roads	Steady burn mono-directional lights
Channelizing devices for night time along lane shifts on two lane roads	Steady burn bi-directional lights
Devices in nighttime lane closure tapers on Standards 701316 and 701321	Steady burn bi-directional lights
Devices in nighttime lane closure tapers	Steady burn mono-directional lights
Devices delineating a widening trench	None
Devices delineating patches at night on roadways with an ADT less than 25,000	None
Devices delineating patches at night on roadways with an ADT of 25,000 or more	None

Batteries for the lights shall be replaced on a group basis at such times as may be specified by the Engineer."

Delete the fourth sentence of the first paragraph of Article 701.17(c)(2) of the Standard Specifications.

Revise the first paragraph of Article 603.07 of the Standard Specifications to read:

"603.07 Protection Under Traffic. After the casting has been adjusted and Class SI concrete has been placed, the work shall be protected by a barricade for at least 72 hours."

PAVEMENT MARKING REMOVAL (BDE)

Effective: July 1, 2016

Revise Article 783.02 of the Standard Specifications to read:

"783.02 Equipment. Equipment shall be according to the following.

Item	Article/Section
(a) Grinders (Note 1)	
(b) Water Blaster with Vacuum Recovery	

Note 1. Grinding equipment shall be approved by the Engineer."

Revise the first paragraph of Article 783.03 of the Standard Specifications to read:

"783.03 Removal of Conflicting Markings. Existing pavement markings that conflict with revised traffic patterns shall be removed. If darkness or inclement weather prohibits the removal operations, such operations shall be resumed the next morning or when weather permits. In the event of removal equipment failure, such equipment shall be repaired, replaced, or leased so removal operations can be resumed within 24 hours."

Revise the first and second sentences of the first paragraph of Article 783.03(a) of the Standard Specifications to read:

"The existing pavement markings shall be removed by the method specified and in a manner that does not materially damage the surface or texture of the pavement or surfacing. Small particles of tightly adhering existing markings may remain in place, if in the opinion of the Engineer, complete removal of the small particles will result in pavement surface damage."

Revise the first paragraph of Article 783.04 of the Standard Specifications to read:

"783.04 Cleaning. The roadway surface shall be cleaned of debris or any other deleterious material by the use of compressed air or water blast."

Revise the first paragraph of Article 783.06 of the Standard Specifications to read:

"**783.06 Basis of Payment.** This work will be paid for at the contract unit price per each for RAISED REFLECTIVE PAVEMENT MARKER REMOVAL, or at the contract unit price per square foot (square meter) for PAVEMENT MARKING REMOVAL – GRINDING and/or PAVEMENT MARKING REMOVAL – WATER BLASTING."

Delete Article 1101.13 from the Standard Specifications.

PAYMENTS TO SUBCONTRACTORS (BDE)

Effective: November 2, 2017

Add the following to the end of the fourth paragraph of Article 109.11 of the Standard Specifications:

"If reasonable cause is asserted, written notice shall be provided to the applicable subcontractor and/or material supplier and the Engineer within five days of the Contractor receiving payment. The written notice shall identify the contract number, the subcontract or material purchase agreement, a detailed reason for refusal, the value of payment being withheld, and the specific remedial actions required of the subcontractor and/or material supplier so that payment can be made."

PORTABLE CHANGEABLE MESSAGE SIGNS (BDE)

Effective: November 1, 2016 Revised: April 1, 2017

Revise the second paragraph of Article 701.20(h) of the Standard Specifications to read:

"For all other portable changeable message signs, this work will be paid for at the contract unit price per calendar day for each sign as CHANGEABLE MESSAGE SIGN."

Revise this second sentence of the first paragraph of Article 1106.02(i) of the Standard Specifications to read:

"The message panel shall be a minimum of 7 ft (2.1 m) above the edge of pavement in urban areas and a minimum of 5 ft (1.5 m) above the edge of pavement in rural areas, present a level appearance, and be capable of displaying up to eight characters in each of three lines at a time."

PORTLAND CEMENT CONCRETE (BDE)

Effective: November 1, 2017

Revise the Air Content % of Class PP Concrete in Table 1 Classes of Concrete and Mix Design Criteria in Article 1020.04 of the Standard Specifications to read:

"TABLE 1. CLASSES OF CONCRETE AND MIX DESIGN CRITERIA		
Class of Conc.	Use	Air Content %
PP	Pavement Patching Bridge Deck Patching (10)	
	PP-1	
	PP-2 PP-3	4.0 - 8.0"
	PP-4	4.0 0.0
	PP-5	

Revise Note (4) at the end of Table 1 Classes of Concrete and Mix Design Criteria in Article 1020.04 of the Standard Specifications to read:

"(4) For all classes of concrete, the maximum slump may be increased to 7 in (175 mm) when a high range water-reducing admixture is used. For Class SC, the maximum slump may be increased to 8 in. (200 mm). For Class PS, the maximum slump may be increased to 8 1/2 in. (215 mm) if the high range water-reducing admixture is the polycarboxylate type."

PORTLAND CEMENT CONCRETE SIDEWALK (BDE)

Effective: August 1, 2017

Revise the first paragraph of Article 424.12 of the Standard Specifications to read:

"**424.12 Method of Measurement.** This work will be measured for payment in place and the area computed in square feet (square meters). Curb ramps, including side curbs and side flares, will be measured for payment as sidewalk. No deduction will be made for detectable warnings located within the ramp."

PROGRESS PAYMENTS (BDE)

Effective: November 2, 2013

Revise Article 109.07(a) of the Standard Specifications to read:

"(a) Progress Payments. At least once each month, the Engineer will make a written estimate of the quantity of work performed in accordance with the contract, and the value thereof at the contract unit prices. The amount of the estimate approved as due for payment will be vouchered by the Department and presented to the State Comptroller for payment. No amount less than \$1000.00 will be approved for payment other than the final payment.

Progress payments may be reduced by liens filed pursuant to Section 23(c) of the Mechanics' Lien Act, 770 ILCS 60/23(c).

If a Contractor or subcontractor has defaulted on a loan issued under the Department's Disadvantaged Business Revolving Loan Program (20 ILCS 2705/2705-610), progress payments may be reduced pursuant to the terms of that loan agreement. In such cases, the amount of the estimate related to the work performed by the Contractor or subcontractor, in default of the loan agreement, will be offset, in whole or in part, and vouchered by the Department to the Working Capital Revolving Fund or designated escrow account. Payment for the work shall be considered as issued and received by the Contractor or subcontractor on the date of the offset voucher. Further, the amount of the offset voucher shall be a credit against the Department's obligation to pay the Contractor, the Contractor's obligation to pay the subcontractor, and the Contractor's or subcontractor's total loan indebtedness to the Department. The offset shall continue until such time as the entire loan indebtedness is satisfied. The Department will notify the Contractor and Fund Control Agent in a timely manner of such offset. The Contractor or subcontractor shall not be entitled to additional payment in consideration of the offset.

The failure to perform any requirement, obligation, or term of the contract by the Contractor shall be reason for withholding any progress payments until the Department determines that compliance has been achieved."

RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE)

Effective: November 1, 2012 Revise: January 1, 2018

Revise Section 1031 of the Standard Specifications to read:

"SECTION 1031. RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES

1031.01 Description. Reclaimed asphalt pavement and reclaimed asphalt shingles shall be according to the following.

- (a) Reclaimed Asphalt Pavement (RAP). RAP is the material produced by cold milling or crushing an existing hot-mix asphalt (HMA) pavement. The Contractor shall supply written documentation that the RAP originated from routes or airfields under federal, state, or local agency jurisdiction.
- (b) Reclaimed Asphalt Shingles (RAS). Reclaimed asphalt shingles (RAS). RAS is from the processing and grinding of preconsumer or post-consumer shingles. RAS shall be a clean and uniform material with a maximum of 0.5 percent unacceptable material, as defined in Central Bureau of Materials Policy Memorandum, "Reclaimed Asphalt Shingle (RAS) Sources", by weight of RAS. All RAS used shall come from a Central Bureau of Materials approved processing facility where it shall be ground and processed to 100 percent passing the 3/8 in. (9.5 mm) sieve and 93 percent passing the #4 (4.75 mm) sieve based on a dry shake gradation. RAS shall be uniform in gradation and asphalt binder content and shall meet the testing requirements specified herein. In addition, RAS shall meet the following Type 1 or Type 2 requirements.
 - (1) Type 1. Type 1 RAS shall be processed, preconsumer asphalt shingles salvaged from the manufacture of residential asphalt roofing shingles.
 - (2) Type 2. Type 2 RAS shall be processed post-consumer shingles only, salvaged from residential, or four unit or less dwellings not subject to the National Emission Standards for Hazardous Air Pollutants (NESHAP).

1031.02 Stockpiles. RAP and RAS stockpiles shall be according to the following.

(a) RAP Stockpiles. The Contractor shall construct individual, sealed RAP stockpiles meeting one of the following definitions. No additional RAP shall be added to the pile after the pile has been sealed. Stockpiles shall be sufficiently separated to prevent intermingling at the base. Stockpiles shall be identified by signs indicating the type as listed below (i.e. "Homogeneous Surface").

Prior to milling, the Contractor shall request the District provide documentation on the quality of the RAP to clarify the appropriate stockpile.

(1) Fractionated RAP (FRAP). FRAP shall consist of RAP from Class I, HMA (High and Low ESAL) mixtures. The coarse aggregate in FRAP shall be crushed aggregate and may represent more than one aggregate type and/or quality, but shall be at least C quality. All FRAP shall be fractionated prior to testing by screening into a minimum of two size fractions with the separation occurring on or between the #4 (4.75 mm) and 1/2 in. (12.5 mm) sieves. Agglomerations shall be minimized such that 100 percent of the RAP shall pass the sieve size specified below for the mix into which the FRAP will be incorporated.

Mixture FRAP will be used in:	Sieve Size that 100 % of FRAP Shall Pass
IL-19.0	1 1/2 in. (40 mm)
IL-9.5	3/4 in. (20 mm)
IL-4.75	1/2 in. (13 mm)

- (2) Homogeneous. Homogeneous RAP stockpiles shall consist of RAP from Class I, HMA (High and Low ESAL) mixtures and represent: 1) the same aggregate quality, but shall be at least C quality; 2) the same type of crushed aggregate (either crushed natural aggregate, ACBF slag, or steel slag); 3) similar gradation; and 4) similar asphalt binder content. If approved by the Engineer, combined single pass surface/binder millings may be considered "homogeneous" with a quality rating dictated by the lowest coarse aggregate quality present in the mixture.
- (3) Conglomerate. Conglomerate RAP stockpiles shall consist of RAP from Class I, HMA (High and Low ESAL) mixtures. The coarse aggregate in this RAP shall be crushed aggregate and may represent more than one aggregate type and/or quality, but shall be at least C quality. This RAP may have an inconsistent gradation and/or asphalt binder content prior to processing. All conglomerate RAP shall be processed prior to testing by crushing to where all RAP shall pass the 5/8 in. (16 mm) or smaller screen. Conglomerate RAP stockpiles shall not contain steel slag.
- (4) Non-Quality. RAP stockpiles that do not meet the requirements of the stockpile categories listed above shall be classified as "Non-Quality".

RAP/FRAP containing contaminants, such as earth, brick, sand, concrete, sheet asphalt, bituminous surface treatment (i.e. chip seal), pavement fabric, joint sealants, etc., will be unacceptable unless the contaminants are removed to the satisfaction of the Engineer. Sheet asphalt shall be stockpiled separately.

(b) RAS Stockpiles. Type 1 and Type 2 RAS shall be stockpiled separately and shall not be intermingled. Each stockpile shall be signed indicating what type of RAS is present.

Unless otherwise specified by the Engineer, mechanically blending manufactured sand (FM 20 or FM 22) up to an equal weight of RAS with the processed RAS will be permitted to improve workability. The sand shall be "B Quality" or better from an

approved Aggregate Gradation Control System source. The sand shall be accounted for in the mix design and during HMA production.

Records identifying the shingle processing facility supplying the RAS, RAS type, and lot number shall be maintained by project contract number and kept for a minimum of three years.

1031.03 Testing. RAP/FRAP and RAS testing shall be according to the following.

- (a) RAP/FRAP Testing. When used in HMA, the RAP/FRAP shall be sampled and tested either during or after stockpiling.
 - (1) During Stockpiling. For testing during stockpiling, washed extraction samples shall be run at the minimum frequency of one sample per 500 tons (450 metric tons) for the first 2000 tons (1800 metric tons) and one sample per 2000 tons (1800 metric tons) thereafter. A minimum of five tests shall be required for stockpiles less than 4000 tons (3600 metric tons).
 - (2) After Stockpiling. For testing after stockpiling, the Contractor shall submit a plan for approval to the District proposing a satisfactory method of sampling and testing the RAP/FRAP pile either in-situ or by restockpiling. The sampling plan shall meet the minimum frequency required above and detail the procedure used to obtain representative samples throughout the pile for testing.

Each sample shall be split to obtain two equal samples of test sample size. One of the two test samples from the final split shall be labeled and stored for Department use. The Contractor shall extract the other test sample according to Department procedure. The Engineer reserves the right to test any sample (split or Department-taken) to verify Contractor test results.

(b) RAS Testing. RAS or RAS blended with manufactured sand shall be sampled and tested during stockpiling according to Central Bureau of Materials Policy Memorandum, "Reclaimed Asphalt Shingle (RAS) Source".

Samples shall be collected during stockpiling at the minimum frequency of one sample per 200 tons (180 metric tons) for the first 1000 tons (900 metric tons) and one sample per 250 tons (225 metric tons) thereafter. A minimum of five samples are required for stockpiles less than 1000 tons (900 metric tons). Once a \leq 1000 ton (900 metric ton), five-sample/test stockpile has been established it shall be sealed. Additional incoming RAS or RAS blended with manufactured sand shall be stockpiled in a separate working pile as designated in the Quality Control plan and only added to the sealed stockpile when the test results of the working pile are complete and are found to meet the tolerances specified herein for the original sealed RAS stockpile.

Before testing, each sample shall be split to obtain two test samples. One of the two test samples from the final split shall be labeled and stored for Department use. The

Contractor shall perform a washed extraction and test for unacceptable materials on the other test sample according to Department procedures. The Engineer reserves the right to test any sample (split or Department-taken) to verify Contractor test results.

If the sampling and testing was performed at the shingle processing facility in accordance with the QC Plan, the Contractor shall obtain and make available all of the test results from start of the initial stockpile.

1031.04 Evaluation of Tests. Evaluation of test results shall be according to the following.

(a) Evaluation of RAP/FRAP Test Results. All of the extraction results shall be compiled and averaged for asphalt binder content and gradation, and when applicable G_{mm}. Individual extraction test results, when compared to the averages, will be accepted if within the tolerances listed below.

Parameter	FRAP/Homogeneous/ Conglomerate
1 in. (25 mm)	
1/2 in. (12.5 mm)	±8%
No. 4 (4.75 mm)	± 6 %
No. 8 (2.36 mm)	± 5 %
No. 16 (1.18 mm)	
No. 30 (600 µm)	± 5 %
No. 200 (75 µm)	± 2.0 %
Asphalt Binder	\pm 0.4 % $^{1/}$
G _{mm}	± 0.03

1/ The tolerance for FRAP shall be \pm 0.3 %.

If more than 20 percent of the individual sieves and/or asphalt binder content tests are out of the above tolerances, the RAP/FRAP shall not be used in HMA unless the RAP/FRAP representing the failing tests is removed from the stockpile. All test data and acceptance ranges shall be sent to the District for evaluation.

With the approval of the Engineer, the ignition oven may be substituted for extractions according to the ITP, "Calibration of the Ignition Oven for the Purpose of Characterizing Reclaimed Asphalt Pavement (RAP)".

(b) Evaluation of RAS and RAS Blended with Manufactured Sand Test Results. All of the test results, with the exception of percent unacceptable materials, shall be compiled and averaged for asphalt binder content and gradation. Individual test results, when compared to the averages, will be accepted if within the tolerances listed below.

Parameter	RAS
No. 8 (2.36 mm)	± 5 %

No. 16 (1.18 mm)	± 5 %
No. 30 (600 µm)	±4%
No. 200 (75 μm)	± 2.0 %
Asphalt Binder Content	± 1.5 %

If more than 20 percent of the individual sieves and/or asphalt binder content tests are out of the above tolerances, or if the percent unacceptable material exceeds 0.5 percent by weight of material retained on the # 4 (4.75 mm) sieve, the RAS or RAS blend shall not be used in Department projects. All test data and acceptance ranges shall be sent to the District for evaluation.

1031.05 Quality Designation of Aggregate in RAP/FRAP.

- (a) RAP. The aggregate quality of the RAP for homogeneous and conglomerate stockpiles shall be set by the lowest quality of coarse aggregate in the RAP stockpile and are designated as follows.
 - (1) RAP from Class I, Superpave/HMA (High ESAL), or (Low ESAL) IL-9.5L surface mixtures are designated as containing Class B quality coarse aggregate.
 - (2) RAP from Class I binder, Superpave/HMA (High ESAL) binder, or (Low ESAL) IL-19.0L binder mixtures are designated as containing Class C quality coarse aggregate.
- (b) FRAP. If the Engineer has documentation of the quality of the FRAP aggregate, the Contractor shall use the assigned quality provided by the Engineer.

If the quality is not known, the quality shall be determined as follows. Coarse and fine FRAP stockpiles containing plus #4 (4.75 mm) sieve coarse aggregate shall have a maximum tonnage of 5000 tons (4500 metric tons). The Contractor shall obtain a representative sample witnessed by the Engineer. The sample shall be a minimum of 50 lb (25 kg). The sample shall be extracted according to Illinois Modified AASHTO T 164 by a consultant laboratory prequalified by the Department for the specified testing. The consultant laboratory shall submit the test results along with the recovered aggregate to the District Office. The cost for this testing shall be paid by the Contractor. The District will forward the sample to the Central Bureau of Materials Aggregate Lab for MicroDeval Testing, according to ITP 327. A maximum loss of 15.0 percent will be applied for all HMA applications.

1031.06 Use of RAP/FRAP and/or RAS in HMA. The use of RAP/FRAP and/or RAS shall be the Contractor's option when constructing HMA in all contracts.

- (a) RAP/FRAP. The use of RAP/FRAP in HMA shall be as follows.
 - (1) Coarse Aggregate Size. The coarse aggregate in all RAP shall be equal to or less than the nominal maximum size requirement for the HMA mixture to be produced.

- (2) Steel Slag Stockpiles. Homogeneous RAP stockpiles containing steel slag will be approved for use in all HMA (High ESAL and Low ESAL) Surface and Binder Mixture applications.
- (3) Use in HMA Surface Mixtures (High and Low ESAL). RAP/FRAP stockpiles for use in HMA surface mixtures (High and Low ESAL) shall be FRAP or homogeneous in which the coarse aggregate is Class B quality or better. FRAP from Conglomerate stockpiles shall be considered equivalent to limestone for frictional considerations. Known frictional contributions from plus #4 (4.75 mm) homogeneous FRAP stockpiles will be accounted for in meeting frictional requirements in the specified mixture.
- (4) Use in HMA Binder Mixtures (High and Low ESAL), HMA Base Course, and HMA Base Course Widening. RAP/FRAP stockpiles for use in HMA binder mixtures (High and Low ESAL), HMA base course, and HMA base course widening shall be FRAP, homogeneous, or conglomerate, in which the coarse aggregate is Class C quality or better.
- (5) Use in Shoulders and Subbase. RAP/FRAP stockpiles for use in HMA shoulders and stabilized subbase (HMA) shall be FRAP, homogeneous, or conglomerate.
- (6) When the Contractor chooses the RAP option, the percentage of RAP shall not exceed the amounts indicated in Article 1031.06(c)(1) below for a given Ndesign.
- (b) RAS. RAS meeting Type 1 or Type 2 requirements will be permitted in all HMA applications as specified herein.
- (c) RAP/FRAP and/or RAS Usage Limits. Type 1 or Type 2 RAS may be used alone or in conjunction with RAP or FRAP in HMA mixtures up to a maximum of 5.0 percent by weight of the total mix.
 - (1) RAP/RAS. When RAP is used alone or RAP is used in conjunction with RAS, the percentage of virgin asphalt binder replacement shall not exceed the amounts listed in the Max RAP/RAS ABR table listed below for the given Ndesign.

HMA Mixtures	RAP/RAS Maximum ABR %		
Ndesign	Binder/Leveling Binder	Surface	Polymer Modified
30	30	30	10
50	25	15	10
70	15	10	10
90	10	10	10

RAP/RAS Maximum Asphalt Binder Replacement (ABR) Percentage

- 1/ For Low ESAL HMA shoulder and stabilized subbase, the RAP/RAS ABR shall not exceed 50 percent of the mixture.
- 2/ When RAP/RAS ABR exceeds 20 percent, the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 percent ABR would require a virgin asphalt binder grade of PG 64-22 to be reduced to a PG 58-28). If warm mix asphalt (WMA) technology is utilized and production temperatures do not exceed 275 °F (135 °C), the high and low virgin asphalt binder grades shall each be reduced by one grade when RAP/RAS ABR exceeds 25 percent (i.e. 26 percent RAP/RAS ABR would require a virgin asphalt binder grade of PG 64-22 to be reduced to a PG 58-28).
- (2) FRAP/RAS. When FRAP is used alone or FRAP is used in conjunction with RAS, the percentage of virgin asphalt binder replacement shall not exceed the amounts listed in the FRAP/RAS table listed below for the given Ndesign.

HMA Mixtures	FRAP/RAS Maximum ABR %		
Ndesign	Binder/Leveling Binder	Surface	Polymer Modified ^{3/, 4/}
30	50	40	10
50	40	35	10
70	40	30	10
90	40	30	10

FRAP/RAS Maximum Asphalt Binder Replacement (ABR) Percentage

- 1/ For Low ESAL HMA shoulder and stabilized subbase, the FRAP/RAS ABR shall not exceed 50 percent of the mixture.
- 2/ When FRAP/RAS ABR exceeds 20 percent for all mixes, the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 percent ABR would require a virgin asphalt binder grade of PG 64-22 to be reduced to a PG 58-28). If warm mix asphalt (WMA) technology is utilized and production temperatures do not exceed 275 °F (135 °C), the high and low virgin asphalt binder grades shall each be reduced by one grade when FRAP/RAS ABR exceeds 25 percent (i.e. 26 percent ABR would require a virgin asphalt binder grade of PG 64-22 to be reduced to a PG 58-28).
- 3/ For SMA the FRAP/RAS ABR shall not exceed 20 percent.
- 4/ For IL-4.75 mix the FRAP/RAS ABR shall not exceed 30 percent.

1031.07 HMA Mix Designs. At the Contractor's option, HMA mixtures may be constructed utilizing RAP/FRAP and/or RAS material meeting the detailed requirements specified herein.

- (a) RAP/FRAP and/or RAS. RAP/FRAP and/or RAS mix designs shall be submitted for verification. If additional RAP/FRAP and/or RAS stockpiles are tested and found that no more than 20 percent of the results, as defined under "Testing" herein, are outside of the control tolerances set for the original RAP/FRAP and/or RAS stockpile and HMA mix design, and meets all of the requirements herein, the additional RAP/FRAP and/or RAS stockpiles may be used in the original mix design at the percent previously verified.
- (b) RAS. Type 1 and Type 2 RAS are not interchangeable in a mix design.

The RAP, FRAP, and RAS stone bulk specific gravities (G_{sb}) shall be according to the "Determination of Aggregate Bulk (Dry) Specific Gravity (G_{sb}) of Reclaimed Asphalt Pavement (RAP) and Reclaimed Asphalt Shingles (RAS)" procedure in the Department's Manual of Test Procedures for Materials.

1031.08 HMA Production. HMA production utilizing RAP/FRAP and/or RAS shall be as follows.

(a) RAP/FRAP. The coarse aggregate in all RAP/FRAP used shall be equal to or less than the nominal maximum size requirement for the HMA mixture being produced.

To remove or reduce agglomerated material, a scalping screen, gator, crushing unit, or comparable sizing device approved by the Engineer shall be used in the RAP feed system to remove or reduce oversized material.

If the RAP/FRAP control tolerances or QC/QA test results require corrective action, the Contractor shall cease production of the mixture containing RAP/FRAP and either switch to the virgin aggregate design or submit a new RAP/FRAP design.

- (b) RAS. RAS shall be incorporated into the HMA mixture either by a separate weight depletion system or by using the RAP weigh belt. Either feed system shall be interlocked with the aggregate feed or weigh system to maintain correct proportions for all rates of production and batch sizes. The portion of RAS shall be controlled accurately to within ± 0.5 percent of the amount of RAS utilized. When using the weight depletion system, flow indicators or sensing devices shall be provided and interlocked with the plant controls such that the mixture production is halted when RAS flow is interrupted.
- (c) RAP/FRAP and/or RAS. HMA plants utilizing RAP/FRAP and/or RAS shall be capable of automatically recording and printing the following information.
 - (1) Dryer Drum Plants.
 - a. Date, month, year, and time to the nearest minute for each print.
 - b. HMA mix number assigned by the Department.

- c. Accumulated weight of dry aggregate (combined or individual) in tons (metric tons) to the nearest 0.1 ton (0.1 metric ton).
- d. Accumulated dry weight of RAP/FRAP/RAS in tons (metric tons) to the nearest 0.1 ton (0.1 metric ton).
- e. Accumulated mineral filler in revolutions, tons (metric tons), etc. to the nearest 0.1 unit.
- f. Accumulated asphalt binder in gallons (liters), tons (metric tons), etc. to the nearest 0.1 unit.
- g. Residual asphalt binder in the RAP/FRAP material as a percent of the total mix to the nearest 0.1 percent.
- Aggregate and RAP/FRAP moisture compensators in percent as set on the control panel. (Required when accumulated or individual aggregate and RAP/FRAP are printed in wet condition.)
- (2) Batch Plants.
 - a. Date, month, year, and time to the nearest minute for each print.
 - b. HMA mix number assigned by the Department.
 - c. Individual virgin aggregate hot bin batch weights to the nearest pound (kilogram).
 - d. Mineral filler weight to the nearest pound (kilogram).
 - e. RAP/FRAP/RAS weight to the nearest pound (kilogram).
 - f. Virgin asphalt binder weight to the nearest pound (kilogram).
 - g. Residual asphalt binder in the RAP/FRAP/RAS material as a percent of the total mix to the nearest 0.1 percent.

The printouts shall be maintained in a file at the plant for a minimum of one year or as directed by the Engineer and shall be made available upon request. The printing system will be inspected by the Engineer prior to production and verified at the beginning of each construction season thereafter.

1031.09 RAP in Aggregate Surface Course and Aggregate Wedge Shoulders, Type B. The use of RAP in aggregate surface course (temporary access entrances only) and aggregate wedge shoulders, Type B shall be as follows.

- (a) Stockpiles and Testing. RAP stockpiles may be any of those listed in Article 1031.02, except "Non-Quality" and "FRAP". The testing requirements of Article 1031.03 shall not apply. RAP used shall be according to the current Central Bureau of Materials Policy Memorandum, "Reclaimed Asphalt Pavement (RAP) for Aggregate Applications".
- (b) Gradation. One hundred percent of the RAP material shall pass the 1 1/2 in. (37.5 mm) sieve. The RAP material shall be reasonably well graded from coarse to fine. RAP material that is gap-graded or single sized will not be accepted."

SUBCONTRACTOR MOBILILATION PAYMENTS (BDE)

Effective: November 2, 2017

Replace the second paragraph of Article 109.12 of the Standard Specifications with the following:

"This mobilization payment shall be made at least 14 days prior to the subcontractor starting work. The amount paid shall be at the following percentage of the amount of the subcontract reported on form BC 260A submitted for the approval of the subcontractor's work.

Value of Subcontract Reported on Form BC 260A	Mobilization Percentage	
Less than \$10,000	25%	
\$10,000 to less than \$20,000	20%	
\$20,000 to less than \$40,000	18%	
\$40,000 to less than \$60,000	16%	
\$60,000 to less than \$80,000	14%	
\$80,000 to less than \$100,000	12%	
\$100,000 to less than \$250,000	10%	
\$250,000 to less than \$500,000	9%	
\$500,000 to \$750,000	8%	
Over \$750,000	7%"	

TEMPORARY PAVEMENT MARKING (BDE)

Effective: April 1, 2012 Revised: April 1, 2017

Revise Article 703.02 of the Standard Specifications to read:

"703.02 Materials. Materials shall be according to the following.

(a) Pavement Marking Tape, Type I and Type III	1095.06
(b) Paint Pavement Markings	1095.02
(c) Pavement Marking Tape, Type IV	1095.11"

Revise the second paragraph of Article 703.05 of the Standard Specifications to read:

"Type I marking tape or paint shall be used at the option of the Contractor, except paint shall not be applied to the final wearing surface unless authorized by the Engineer for late season applications where tape adhesion would be a problem. Type III or Type IV marking tape shall be used on the final wearing surface when the temporary pavement marking will conflict with the permanent pavement marking such as on tapers, crossovers and lane shifts."

Revise Article 703.07 of the Standard Specifications to read:

"703.07 Basis of Payment. This work will be paid for as follows.

- a) Short Term Pavement Marking. Short term pavement marking will be paid for at the contract unit price per foot (meter) for SHORT TERM PAVEMENT MARKING. Removal of short term pavement markings will be paid for at the contract unit price per square foot (square meter) for SHORT TERM PAVEMENT MARKING REMOVAL.
- b) Temporary Pavement Marking. Where the Contractor has the option of material type, temporary pavement marking will be paid for at the contract unit price per foot (meter) for TEMPORARY PAVEMENT MARKING of the line width specified, and at the contract unit price per square foot (square meter) for TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS.

Where the Department specifies the use of pavement marking tape, the Type III or Type IV temporary pavement marking will be paid for at the contract unit price per foot (meter) for PAVEMENT MARKING TAPE, TYPE III or PAVEMENT MARKING TAPE, TYPE IV of the line width specified and at the contract unit price per square feet (square meter) for PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS or PAVEMENT MARKING TAPE, TYPE IV – LETTERS AND SYMBOLS.

Removal of temporary pavement markings will be paid for at the contract unit price per square foot (square meter) for TEMPORARY PAVEMENT MARKING REMOVAL.

When temporary pavement marking is shown on the Standard, the cost of the temporary pavement marking and its removal will be included in the cost of the Standard."

Add the following to Section 1095 of the Standard Specifications:

"1095.11 Pavement Marking Tape, Type IV. The temporary, preformed, patterned markings shall consist of a white or yellow tape with wet retroreflective media incorporated to provide immediate and continuing retroreflection during both wet and dry conditions. The tape shall be manufactured without the use of heavy metals including lead chromate pigments or other similar, lead-containing chemicals.

The white and yellow Type IV marking tape shall meet the Type III requirements of Article 1095.06 and the following.

- (a) Composition. The retroreflective pliant polymer pavement markings shall consist of a mixture of high-quality polymeric materials, pigments and glass beads distributed throughout its base cross-sectional area, with a layer of wet retroreflective media bonded to a durable polyurethane topcoat surface. The patterned surface shall have approximately 40% ± 10% of the surface area raised and presenting a near vertical face to traffic from any direction. The channels between the raised areas shall be substantially free of exposed beads or particles.
- (b) Retroreflectance. The white and yellow markings shall meet the following for initial dry and wet retroreflectance.
 - (1) Dry Retroreflectance. Dry retroreflectance shall be measured under dry conditions according to ASTM D 4061 and meet the values described in Article 1095.06 for Type III tape.
 - (2) Wet Retroreflectance. Wet retroreflectance shall be measured under wet conditions according to ASTM E 2177 and meet the values shown in the following table.

wet Retroreflectance, initial R_L		
Color	R _L 1.05/88.76	
White	300	
Yellow	200	

Wet Retroreflectance, Initial R_L

(c) Color. The material shall meet the following requirements for daylight reflectance and color, when tested, using a color spectrophotometer with 45 degrees circumferential/zero degree geometry, illuminant D65, and a two degree observer angle. The color instrument shall measure the visible spectrum from 380 to 720 nm with a wavelength measurement interval and spectral bandpass of 10 nm.

Color	Daylight Reflectance %Y	
White	65 minimum	
*Yellow	36-59	

*Shall match Federal 595 Color No. 33538 and the chromaticity limits as follows.

x	0.490	0.475	0.485	0.530
у	0.470	0.438	0.425	0.456

- (d) Skid Resistance. The surface of the markings shall provide an average minimum skid resistance of 50 BPN when tested according to ASTM E 303.
- (e) Sampling, Testing, Acceptance, and Certification. Prior to approval and use of the wet reflective, temporary, removable pavement marking tape, the manufacturer shall submit a notarized certification from an independent laboratory, together with the results of all tests, stating that the material meets the requirements as set forth herein. The certification test report shall state the lot tested, manufacturer's name, and date of manufacture.

After approval by the Department, samples and certification by the manufacturer shall be submitted for each batch used. The manufacturer shall submit a certification stating that the material meets the requirements as set forth herein and is essentially identical to the material sent for qualification. The certification shall state the lot tested, manufacturer's name, and date of manufacture.

All costs of testing (other than tests conducted by the Department) shall be borne by the manufacturer."

TRAINING SPECIAL PROVISIONS (BDE) This Training Special Provision supersedes Section 7b of the Special Provision entitled "Specific Equal Employment Opportunity Responsibilities," and is in implementation of 23 U.S.C. 140(a).

As part of the contractor's equal employment opportunity affirmative action program, training shall be provided as follows:

The contractor shall provide on-the-job training aimed at developing full journeyman in the type of trade or job classification involved. The number of trainees to be trained under this contract will be 1. In the event the contractor subcontracts a portion of the contract work, he shall determine how many, if any, of the trainees are to be trained by the subcontractor, provided however, that the contractor shall retain the primary responsibility for meeting the training requirements imposed by this special provision. The contractor shall also insure that this Training Special Provision is made applicable to such subcontract. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training.

The number of trainees shall be distributed among the work classifications on the basis of the contractor's needs and the availability of journeymen in the various classifications within the reasonable area of recruitment. Prior to commencing construction, the contractor shall submit to the Illinois Department of Transportation for approval the number of trainees to be trained in each selected classification and training program to be used. Furthermore, the contractor shall specify the starting time for training in each of the classifications. The contractor will be credited for each trainee employed by him on the contract work who is currently enrolled or becomes enrolled in an approved program and will be reimbursed for such trainees as provided hereinafter.

Training and upgrading of minorities and women toward journeyman status is a primary objective of this Training Special Provision. Accordingly, the contractor shall make every effort to enroll minority trainees and women (e.g. by conducting systematic and direct recruitment through public and private sources likely to yield minority and women trainees) to the extent such persons are available within a reasonable area of recruitment. The contractor will be responsible for demonstrating the steps that he has taken in pursuance thereof, prior to a determination as to whether the contractor is in compliance with this Training Special Provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a minority group or not.

No employee shall be employed as a trainee in any classification in which he has successfully completed a training course leading to journeyman status or in which he has been employed as a journeyman. The contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used the contractor's records should document the findings in each case.

The minimum length and type of training for each classification will be as established in the training program selected by the contractor and approved by the Illinois Department of Transportation and the Federal Highway Administration. The Illinois Department of Transportation and the Federal Highway Administration shall approve a program, if it is reasonably calculated to meet the equal employment opportunity obligations of the contractor and to gualify the average trainee for journeyman status in the classification concerned by the end of the training period. Furthermore, apprenticeship programs registered with the U.S. Department of Labor, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau and training programs approved by not necessarily sponsored by the U.S. Department of Labor, Manpower Administration, Bureau of Apprenticeship and Training shall also be considered acceptable provided it is being administered in a manner consistent with the equal employment obligations of Federal-aid highway construction contracts. Approval or acceptance of a training program shall be obtained from the State prior to commencing work on the classification covered by the program. It is the intention of these provisions that training is to be provided in the construction crafts rather then clerk-typists or secretarial-type positions. Training is permissible in lower level management positions such as office engineers, estimators, timekeepers, etc., where the training is oriented toward construction applications. Training in the laborer classification may be permitted provided that significant and meaningful training is provided and approved by the Illinois Department of Transportation and the Federal Highway Administration. Some offsite training is permissible as long as the training is an integral part of an approved training program and does not comprise a significant part of the overall training.

Except as otherwise noted below, the contractor will be reimbursed 80 cents per hour of training given an employee on this contract in accordance with an approved training program. As approved by the Engineer, reimbursement will be made for training of persons in excess of the number specified herein. This reimbursement will be made even though the contractor receives additional training program funds from other sources, provided such other source does not specifically prohibit the contractor from receiving other reimbursement. Reimbursement for offsite training indicated above may only be made to the contractor where he does one or more of the following and the trainees are concurrently employed on a Federal-aid project; contributes to the cost of the training, provides the instruction to the trainee or pays the trainee's wages during the offsite training period.

No payment shall be made to the contractor if either the failure to provide the required training, or the failure to hire the trainee as a journeyman, is caused by the contractor and evidences a lack of good faith on the part of the contractor in meeting the requirement of this Training Special Provision. It is normally expected that a trainee will begin his training on the project as soon as feasible after start of work utilizing the skill involved and remain on the project as long as training opportunities exist in his work classification or until he has completed his training program.

It is not required that all trainees be on board for the entire length of the contract. A contractor will have fulfilled his responsibilities under this Training Special Provision if he has provided acceptable training to the number of trainees specified. The number trained shall be determined on the basis of the total number enrolled on the contract for a significant period.

Trainees will be paid at least 60 percent of the appropriate minimum journeyman's rate specified in the contract for the first half of the training period, 75 percent for the third quarter of the training period, and 90 percent for the last quarter of the training period, unless apprentices or trainees in an approved existing program are enrolled as trainees on this project. In that case, the appropriate rates approved by the Departments of Labor or Transportation in connection with the existing program shall apply to all trainees being trained for the same classification who are covered by this Training Special Provision.

The contractor shall furnish the trainee a copy of the program he will follow in providing the training. The contractor shall provide each trainee with a certification showing the type and length of training satisfactorily complete.

The contractor will provide for the maintenance of records and furnish periodic reports documenting his performance under this Training Special Provision.

<u>METHOD OF MEASUREMENT</u> The unit of measurement is in hours.

<u>BASIS OF PAYMENT</u> This work will be paid for at the contract unit price of 80 cents per hour for TRAINEES. The estimated total number of hours, unit price and total price have been included in the schedule of prices.

WEEKLY DBE TRUCKING REPORTS (BDE)

Effective: June 2, 2012 Revised: April 2, 2015

 The Contractor shall submit a weekly report of Disadvantaged Business Enterprise (DBE) trucks hired by the Contractor or subcontractors (i.e. not owned by the Contractor or subcontractors)
 that are used for DBE goal credit.

The report shall be submitted to the Engineer on Department form "SBE 723" within ten business days following the reporting period. The reporting period shall be Monday through Sunday for each week reportable trucking activities occur.

Any costs associated with providing weekly DBE trucking reports shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed.

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within 50 working days.

REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- I. General
- II. Nondiscrimination
- III. Nonsegregated Facilities
- IV. Davis-Bacon and Related Act Provisions
- V. Contract Work Hours and Safety Standards Act Provisions
- VI. Subletting or Assigning the Contract
- VII. Safety: Accident Prevention
- VIII. False Statements Concerning Highway Projects
- IX. Implementation of Clean Air Act and Federal Water Pollution Control Act
- X. Compliance with Governmentwide Suspension and Debarment Requirements
- XI. Certification Regarding Use of Contract Funds for Lobbying

ATTACHMENTS

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only)

I. GENERAL

1. Form FHWA-1273 must be physically incorporated in each construction contract funded under Title 23 (excluding emergency contracts solely intended for debris removal). The contractor (or subcontractor) must insert this form in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services).

The applicable requirements of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Form FHWA-1273 must be included in all Federal-aid design-build contracts, in all subcontracts and in lower tier subcontracts (excluding subcontracts for design services, purchase orders, rental agreements and other agreements for supplies or services). The design-builder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in bid proposal or request for proposal documents, however, the Form FHWA-1273 must be physically incorporated (not referenced) in all contracts, subcontracts and lower-tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services related to a construction contract).

2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.

4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor

performed by convicts who are on parole, supervised release, or probation. The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors.

II. NONDISCRIMINATION

The provisions of this section related to 23 CFR Part 230 are applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more. The provisions of 23 CFR Part 230 are not applicable to material supply, engineering, or architectural service contracts.

In addition, the contractor and all subcontractors must comply with the following policies: Executive Order 11246, 41 CFR 60, 29 CFR 1625-1627, Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The contractor and all subcontractors must comply with: the requirements of the Equal Opportunity Clause in 41 CFR 60-1.4(b) and, for all construction contracts exceeding \$10,000, the Standard Federal Equal Employment Opportunity Construction Contract Specifications in 41 CFR 60-4.3.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with Executive Order 11246 and the policies of the Secretary of Labor including 41 CFR 60, and 29 CFR 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), and Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The following provision is adopted from 23 CFR 230, Appendix A, with appropriate revisions to conform to the U.S. Department of Labor (US DOL) and FHWA requirements.

1. Equal Employment Opportunity: Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, 29 CFR 1625-1627, 41 CFR 60 and 49 CFR 27) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:

a. The contractor will work with the contracting agency and the Federal Government to ensure that it has made every good faith effort to provide equal opportunity with respect to all of its terms and conditions of employment and in their review of activities under the contract.

 b. The contractor will accept as its operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or on-the-job training."

2. EEO Officer: The contractor will designate and make known to the contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active EEO program and who must be assigned adequate authority and responsibility to do so.

3. Dissemination of Policy: All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:

a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.

b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.

c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minorities and women.

d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.

e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

4. Recruitment: When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minorities and women in the area from which the project work force would normally be derived.

a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minorities and women. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority and women applicants may be referred to the contractor for employment consideration.

b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, the contractor is expected to observe the provisions of that agreement to the extent that the system meets the contractor's compliance with EEO contract provisions. Where implementation of such an agreement has the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Federal nondiscrimination provisions.

c. The contractor will encourage its present employees to refer minorities and women as applicants for employment. Information and procedures with regard to referring such applicants will be discussed with employees.

5. Personnel Actions: Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:

a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.

b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.

c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.

d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with its obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of their avenues of appeal.

6. Training and Promotion:

a. The contractor will assist in locating, qualifying, and increasing the skills of minorities and women who are applicants for employment or current employees. Such efforts should be aimed at developing full journey level status employees in the type of trade or job classification involved.

b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision. The contracting agency may reserve training positions for persons who receive welfare assistance in accordance with 23 U.S.C. 140(a).

c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.

d. The contractor will periodically review the training and promotion potential of employees who are minorities and women and will encourage eligible employees to apply for such training and promotion.

7. Unions: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use good faith efforts to obtain the cooperation of such unions to increase opportunities for minorities and women. Actions by the contractor, either directly or through a contractor's association acting as agent, will include the procedures set forth below:

a. The contractor will use good faith efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minorities and women for membership in the unions and increasing the skills of minorities and women so that they may qualify for higher paying employment.

b. The contractor will use good faith efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.

c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the contracting agency and shall set forth what efforts have been made to obtain such information. d. In the event the union is unable to provide the contractor with a reasonable flow of referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minorities and women. The failure of a union to provide sufficient referrals (even though it is obligated to provide exclusive referrals under the terms of a collective bargaining agreement) does not relieve the contractor from the requirements of this paragraph. In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the contracting agency.

8. Reasonable Accommodation for Applicants / Employees with Disabilities: The contractor must be familiar with the requirements for and comply with the Americans with Disabilities Act and all rules and regulations established there under. Employers must provide reasonable accommodation in all employment activities unless to do so would cause an undue hardship.

9. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment. The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of this contract.

a. The contractor shall notify all potential subcontractors and suppliers and lessors of their EEO obligations under this contract.

b. The contractor will use good faith efforts to ensure subcontractor compliance with their EEO obligations.

10. Assurance Required by 49 CFR 26.13(b):

a. The requirements of 49 CFR Part 26 and the State DOT's U.S. DOT-approved DBE program are incorporated by reference.

b. The contractor or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the contracting agency deems appropriate.

11. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following the date of the final payment to the contractor for all contract work and shall be available at reasonable times and places for inspection by authorized representatives of the contracting agency and the FHWA.

a. The records kept by the contractor shall document the following:

 The number and work hours of minority and nonminority group members and women employed in each work classification on the project;

(2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women; and

(3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minorities and women;

b. The contractors and subcontractors will submit an annual report to the contracting agency each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391.

The staffing data should represent the project work force on board in all or any part of the last payroll period preceding the end of July. If on-thejob training is being required by special provision, the contractor will be required to collect and report training data. The employment data should reflect the work force on board during all or any part of the last payroll period preceding the end of July.

III. NONSEGREGATED FACILITIES

This provision is applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more.

The contractor must ensure that facilities provided for employees are provided in such a manner that segregation on the basis of race, color, religion, sex, or national origin cannot result. The contractor may neither require such segregated use by written or oral policies nor tolerate such use by employee custom. The contractor's obligation extends further to ensure that its employees are not assigned to perform their services at any location, under the contractor's control, where the facilities are segregated. The term "facilities" includes waiting rooms, work areas, restaurants and other eating areas, time clocks, restrooms, washrooms, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing provided for employees. The contractor shall provide separate or single-user restrooms and necessary dressing or sleeping areas to assure privacy between sexes.

IV. DAVIS-BACON AND RELATED ACT PROVISIONS

This section is applicable to all Federal-aid construction projects exceeding \$2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size). The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. Contracting agencies may elect to apply these requirements to other projects.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 "Contract provisions and related matters" with minor revisions to conform to the FHWA-1273 format and FHWA program requirements.

1. Minimum wages

a. All laborers and mechanics employed or working upon the site of the work, will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics.

Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph 1.d. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in 29 CFR 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under paragraph 1.b. of this section) and the Davis-Bacon poster (WH–1321) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

b. (1) The contracting officer shall require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefore only when the following criteria have been met:

(i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and

(ii) The classification is utilized in the area by the construction industry; and

(iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(2) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

(3) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. The Wage and Hour Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

(4) The wage rate (including fringe benefits where appropriate) determined pursuant to paragraphs 1.b.(2) or 1.b.(3) of this section, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

c. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.

d. If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, Provided, That the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

2. Withholding

The contracting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor under this contract, or any other Federal contract with the same prime contractor, or any other federallyassisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the contracting agency may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

3. Payrolls and basic records

a. Payrolls and basic records relating thereto shall be maintained by the contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-Bacon Act, the contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

b. (1) The contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the contracting agency. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR 5.5(a)(3)(i), except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall only need to include an individually identifying number for each employee (e.g., the last four digits of the employee's social security number). The required weekly payroll information may be submitted in any form desired. Optional Form WH-347 is available for this purpose from the Wage and Hour Division Web site at http://www.dol.gov/esa/whd/forms/wh347instr.htm or its successor site. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker, and shall provide them upon request to the contracting agency for transmission to the State DOT, the FHWA or the Wage and Hour Division of the Department of Labor for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of this section for a prime contractor to require a subcontractor to provide addresses and social security numbers to the prime contractor for its own records, without weekly submission to the contracting agency..

(2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:

(i) That the payroll for the payroll period contains the information required to be provided under §5.5 (a)(3)(ii) of Regulations, 29 CFR part 5, the appropriate information is being maintained under §5.5 (a)(3)(i) of Regulations, 29 CFR part 5, and that such information is correct and complete;

(ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in Regulations, 29 CFR part 3;

(iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

(3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH–347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(2) of this section.

(4) The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under section 1001 of title 18 and section 231 of title 31 of the United States Code.

c. The contractor or subcontractor shall make the records required under paragraph 3.a. of this section available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the FHWA may, after written notice to the contractor, the contracting agency or the State DOT, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

4. Apprentices and trainees

a. Apprentices (programs of the USDOL).

Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer and Labor Services, or with a State Apprenticeship Agency recognized by the Office, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Office of Apprenticeship Training, Employer and Labor Services or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice.

The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice

performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeymen hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringe shall be paid in accordance with that determination.

In the event the Office of Apprenticeship Training, Employer and Labor Services, or a State Apprenticeship Agency recognized by the Office, withdraws approval of an apprenticeship program, the contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

b. Trainees (programs of the USDOL).

Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration.

The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration.

Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

In the event the Employment and Training Administration withdraws approval of a training program, the contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Equal employment opportunity. The utilization of apprentices, trainees and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR part 30.

d. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

5. Compliance with Copeland Act requirements. The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract.

6. Subcontracts. The contractor or subcontractor shall insert Form FHWA-1273 in any subcontracts and also require the subcontractors to include Form FHWA-1273 in any lower tier subcontracts. The prime contractor shall be responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR 5.5.

7. Contract termination: debarment. A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.

8. Compliance with Davis-Bacon and Related Act requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract.

9. Disputes concerning labor standards. Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

10. Certification of eligibility.

a. By entering into this contract, the contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

c. The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

V. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

The following clauses apply to any Federal-aid construction contract in an amount in excess of \$100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchmen and guards.

1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one

and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek.

2. Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph (1.) of this section, the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph (1.) of this section, in the sum of \$10 for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph (1.) of this section.

3. Withholding for unpaid wages and liquidated damages. The FHWA or the contacting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph (2.) of this section.

4. Subcontracts. The contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraph (1.) through (4.) of this section and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs (1.) through (4.) of this section.

VI. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System.

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).

a. The term "perform work with its own organization" refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions:

(1) the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;
(2) the prime contractor remains responsible for the quality of the work of the leased employees;

(3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and (4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.

b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract.

2. The contract amount upon which the requirements set forth in paragraph (1) of Section VI is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.

3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.

4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

5. The 30% self-performance requirement of paragraph (1) is not applicable to design-build contracts; however, contracting agencies may establish their own self-performance requirements.

VII. SAFETY: ACCIDENT PREVENTION

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.

2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).

3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C.3704).

VIII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined under this title or imprisoned not more than 5 years or both."

IX. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

By submission of this bid/proposal or the execution of this contract, or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any person who is or will be utilized in the performance of this contract is not prohibited from receiving an award due to a violation of Section 508 of the Clean Water Act or Section 306 of the Clean Air Act. 2. That the contractor agrees to include or cause to be included the requirements of paragraph (1) of this Section X in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements.

X. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost \$25,000 or more – as defined in 2 CFR Parts 180 and 1200.

1. Instructions for Certification – First Tier Participants:

a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.

b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.

c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default.

d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.

e. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180 and 1200. "First Tier Covered Transactions" refers to any covered transaction between a grantee or subgrantee of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a grantee or subgrantee of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.

g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.

h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (https://www.epls.gov/), which is compiled by the General Services Administration.

i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

* * * * *

2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:

(1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency;

(2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;

(3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (a)(2) of this certification; and

(4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.

b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

2. Instructions for Certification - Lower Tier Participants:

(Applicable to all subcontracts, purchase orders and other lower tier transactions requiring prior FHWA approval or estimated to cost \$25,000 or more - 2 CFR Parts 180 and 1200)

a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.

b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.

d. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180 and 1200. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations. "First Tier Covered Transactions" refers to any covered transaction between a grantee or subgrantee of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a grantee or subgrantee of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.

f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.

g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (https://www.epls.gov/), which is compiled by the General Services Administration.

h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

* * * * *

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency.

2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

* * * * *

XI. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 (49 CFR 20).

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

ATTACHMENT A - EMPLOYMENT AND MATERIALS PREFERENCE FOR APPALACHIAN DEVELOPMENT HIGHWAY SYSTEM OR APPALACHIAN LOCAL ACCESS ROAD CONTRACTS

This provision is applicable to all Federal-aid projects funded under the Appalachian Regional Development Act of 1965.

1. During the performance of this contract, the contractor undertaking to do work which is, or reasonably may be, done as on-site work, shall give preference to qualified persons who regularly reside in the labor area as designated by the DOL wherein the contract work is situated, or the subregion, or the Appalachian counties of the State wherein the contract work is situated, except:

a. To the extent that qualified persons regularly residing in the area are not available.

b. For the reasonable needs of the contractor to employ supervisory or specially experienced personnel necessary to assure an efficient execution of the contract work.

c. For the obligation of the contractor to offer employment to present or former employees as the result of a lawful collective bargaining contract, provided that the number of nonresident persons employed under this subparagraph (1c) shall not exceed 20 percent of the total number of employees employed by the contractor on the contract work, except as provided in subparagraph (4) below.

2. The contractor shall place a job order with the State Employment Service indicating (a) the classifications of the laborers, mechanics and other employees required to perform the contract work, (b) the number of employees required in each classification, (c) the date on which the participant estimates such employees will be required, and (d) any other pertinent information required by the State Employment Service to complete the job order form. The job order may be placed with the State Employment Service in writing or by telephone. If during the course of the contract work, the information submitted by the contractor in the original job order is substantially modified, the participant shall promptly notify the State Employment Service.

3. The contractor shall give full consideration to all qualified job applicants referred to him by the State Employment Service. The contractor is not required to grant employment to any job applicants who, in his opinion, are not qualified to perform the classification of work required.

4. If, within one week following the placing of a job order by the contractor with the State Employment Service, the State Employment Service is unable to refer any qualified job applicants to the contractor, or less than the number requested, the State Employment Service will forward a certificate to the contractor indicating the unavailability of applicants. Such certificate shall be made a part of the contractor's permanent project records. Upon receipt of this certificate, the contractor may employ persons who do not normally reside in the labor area to fill positions covered by the certificate, notwithstanding the provisions of subparagraph (1c) above.

5. The provisions of 23 CFR 633.207(e) allow the contracting agency to provide a contractual preference for the use of mineral resource materials native to the Appalachian region.

6. The contractor shall include the provisions of Sections 1 through 4 of this Attachment A in every subcontract for work which is, or reasonably may be, done as on-site work.

Contract Provision - Cargo Preference Requirements

In accordance with Title 46 CFR § 381.7 (b), the contractor agrees-

"(1) To utilize privately owned United States-flag commercial vessels to ship at least 50 percent of the gross tonnage (computed separately for dry bulk carriers, dry cargo liners, and tankers) involved, whenever shipping any equipment, material, or commodities pursuant to this contract, to the extent such vessels are available at fair and reasonable rates for United States-flag commercial vessels.

(2) To furnish within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (b) (1) of this section to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Division of National Cargo, Office of Market Development, Maritime Administration, Washington, DC 20590.

(3) To insert the substance of the provisions of this clause in all subcontracts issued pursuant to this contract."

Provisions (1) and (2) apply to materials or equipment that are acquired solely for the project. The two provisions do not apply to goods or materials that come into inventories independent of the project, such as shipments of Portland cement, asphalt cement, or aggregates, when industry suppliers and contractors use these materials to replenish existing inventories.

MINIMUM WAGES FOR FEDERAL AND FEDERALLY ASSISTED CONSTRUCTION CONTRACTS

This project is funded, in part, with Federal-aid funds and, as such, is subject to the provisions of the Davis-Bacon Act of March 3, 1931, as amended (46 Sta. 1494, as amended, 40 U.S.C. 276a) and of other Federal statutes referred to in a 29 CFR Part 1, Appendix A, as well as such additional statutes as may from time to time be enacted containing provisions for the payment of wages determined to be prevailing by the Secretary of Labor in accordance with the Davis-Bacon Act and pursuant to the provisions of 29 CFR Part 1. The prevailing rates and fringe benefits shown in the General Wage Determination Decisions issued by the U.S. Department of Labor shall, in accordance with the provisions of the foregoing statutes, constitute the minimum wages payable on Federal and federally assisted construction projects to laborers and mechanics of the specified classes engaged on contract work of the character and in the localities described therein.

General Wage Determination Decisions, modifications and supersedes decisions thereto are to be used in accordance with the provisions of 29 CFR Parts 1 and 5. Accordingly, the applicable decision, together with any modifications issued, must be made a part of every contract for performance of the described work within the geographic area indicated as required by an applicable DBRA Federal prevailing wage law and 29 CFR Part 5. The wage rates and fringe benefits contained in the General Wage Determination Decision shall be the minimum paid by contractors and subcontractors to laborers and mechanics.