

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	91 Y-T	COOK	12	2
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS HIGHWAY PROJECT		

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS, GENERAL NOTES & SUMMARY OF QUANTITIES
3	SUMMARY OF QUANTITIES
4	EXISTING TYPICAL SECTION
5	EXISTING BOX CULVERT (FOR INFORMATION ONLY)
6	EXISTING CONDITIONS
7	PROPOSED IMPROVEMENT
8	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT
9	METHOD OF FLAGGING
10	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS
11	TRAFFIC CONTROL AND PROTECTION OF TURN BAYS (TO REMAIN OPEN TO TRAFFIC)
12	TEMPORARY INFORMATION SIGNING DETAIL

STATE STANDARDS

STANDARD NO.	DESCRIPTION
000001-01	TYPICAL SYMBOLS, ABBREVIATIONS AND PATTERNS
602001	CATCH BASIN, TYPE A
602401	MANHOLE, TYPE A
604001-02	FRAME AND LIDS, TYPE 1
606001-02	CONCRETE CURB AND COMBINATION CONCRETE CURB AND GUTTER
701101-01	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 2' FROM PAVEMENT EDGE
701421-01	URBAN LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS 45 TO 55 MPH
701701-04	URBAN LANE CLOSURE, MULTILANE INTERSECTION
702001-05	TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGES OF HILLSIDE AND WESTCHESTER.

THE CONTRACTOR WILL NOT BE ABLE TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT THE WRITTEN PERMISSION OF THE DEPARTMENT.

THE CONTRACTOR SHALL REPLACE ANY AND ALL PAVEMENT MARKINGS AND SIGNING DISTURBED OR DAMAGED BY WORK ACTIVITIES AT CONTRACTOR'S EXPENSE. REPLACEMENT FOR PAVEMENT MARKINGS SHALL BE POLYUREA. AND WHEN THIS HAPPENS THE RESIDENT ENGINEER SHALL CONTACT MR. SCOTT KUZNICKI, AREA TRAFFIC FIELD ENGINEER AT (847) 715-8423 A MINIMUM OF 72 HOURS PRIOR TO PLACEMENT OF PAVEMENT MARKING.

3 METERS (10 FEET) TRANSITION SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER TO EXISTING CURB AND GUTTER IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITION SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEMS OF WORK SPECIFIED.

ALL PARKING LOT PAVEMENT, SIDEWALK, AND CURB & GUTTER REMOVED SHALL BE REPLACED "IN KIND".

MIXTURE TABLE

MIXTURE TYPE	AC/PG	RAP MAX	AIR VOIDS
BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE C, N50, 1 3/4"	PG 64-22	4% @ 50 GYR	15%
CLASS D PATCHES, 8" IL-19	PG 64-22	4% @ 70 GYR	15%

THE UNIT WEIGHT USED TO CALCULATE ALL BITUMINOUS MIXTURES IS 112 LB/SQ YD/IN

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
SCALE:	VERT. HORIZ.	DRAWN BY
DATE		CHECKED BY

PLOT DATE = 12/13/2005  
 FILE NAME = c:\p\c\p\107706\design\_002.dgn  
 PLOT SCALE = 50:0000 / IN  
 USER NAME = chngj

12/13/2005  
 c:\p\c\p\107706\design\_002.dgn  
 chngj