

SCHEDULE OF LANDSCAPE ITEMS										
ITEM	UNIT	TOTAL	SHEET NUMBER							
			5	6	7	8	9	10	11	
SHADE TREES										
Carpinus caroliniana (American Hornbeam), 2" Caliper, Balled & Burlapped	EACH	3		3						
Celtis occidentalis (Hackberry), Container Grown, 3-Gallon	EACH	70								70
Juglans nigra (Black Walnut), Container Grown, 3-Gallon	EACH	70								70
Ostrya virginiana (American Hophornbeam), Container Grown, 3-Gallon	EACH	140						60		80
Quercus alba (White Oak), Container Grown, 3-Gallon	EACH	270				50	50			170
Quercus ellipsoidalis (Hill's Oak), 1-3/4" Caliper, Balled & Burlapped	EACH	14							14	
Quercus ellipsoidalis (Hill's Oak), Container Grown, 3-Gallon	EACH	40								40
Quercus imbricaria (Shingle Oak), Container Grown, 3-Gallon	EACH	120						60		60
Quercus macrocarpa (Bur Oak), 1-1/2" Caliper, Balled & Burlapped	EACH	14							14	
Quercus macrocarpa (Bur Oak), Container Grown, 3-Gallon	EACH	360						50		310
Quercus rubra (Red Oak), 1-3/4" Caliper, Balled & Burlapped	EACH	14							14	
Quercus rubra (Red Oak), Container Grown, 3-Gallon	EACH	190				50	50			90
Tilia americana (American Linden), Container Grown, 3-Gallon	EACH	140				50				90
INTERMEDIATE TREES										
Amelanchier canadensis (Shadblow Serviceberry), 4' Height, Shrub Form, B & B	EACH	50						50		
Cercis canadensis (Eastern Redbud), 5' Height, Clump Form, Balled & Burlapped	EACH	8	8							
SHRUBS										
Aronia melanocarpa (Black Chokeberry), 2' Height, Balled & Burlapped	EACH	50							50	
Cephalanthus occidentalis (Buttonbush), 2' Height, Balled & Burlapped	EACH	10		10						
Corylus americana (American Filbert), 2' Height, Balled & Burlapped	EACH	490	200			200			90	
Hamamelis virginiana (Common Witchhazel), 2' Height, Balled & Burlapped	EACH	50						50		
Rhus typhina (Staghorn Sumac), 2' Height, Container	EACH	20		20						
Salix humilis (Prairie Willow), 18" Height, Container	EACH	150							150	
Sambucas canadensis (American Elder), 2' Height, Container	EACH	75							75	
EVERGREENS										
Juniperus virginiana (Eastern Red Cedar), 5' Height, Balled & Burlapped	EACH	48							48	
Thuja occidentalis Techny (Techny Arborvitae), 4' Height, Balled & Burlapped	EACH	67							67	
OTHER										

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).

VILLAGE WATER, SEWER MAINS AND OTHER UTILITIES MAY BE LOCATED IN THE LANDSCAPE AREA. THE ACTUAL LOCATION OF PROPOSED LANDSCAPING WILL BE ADJUSTED IN THE FIELD TO AVOID UTILITIES. THE VILLAGE OF WILLOW SPRINGS AND THE FOREST PRESERVE DISTRICT OF COOK COUNTY ARE NOT PART OF "J.U.L.I.E." THE CONTRACTOR SHALL CONTACT THE RESPECTIVE VILLAGES TO LOCATE THEIR UTILITIES.

THE CONTRACTOR WILL NOT BE ALLOWED TO PROCEED WITH ANY PLANTING WORK UNTIL ALL UTILITY OWNERS FIELD LOCATE THEIR FACILITIES WHICH MAY INTERFERE WITH LANDSCAPING OPERATIONS.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY OR FOREST PRESERVE HOLDINGS WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT OR THE FOREST PRESERVE DISTRICT OF COOK COUNTY.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4155 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

UNDERBRUSH OR DEBRIS AT PLANTING LOCATIONS SHALL BE REMOVED AND DISPOSED OF IN ACCORDANCE WITH SECTION 201 OF THE STANDARD SPECIFICATIONS. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT THE COSTS SHALL BE CONSIDERED AS INCLUDED IN THE CONTRACT UNIT PRICES FOR THE CONSTRUCTION ITEMS INVOLVED, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

THE CONTRACTOR SHALL PROTECT ALL EXISTING PLANT MATERIAL FROM DAMAGE FOR WHICH THE CONTRACT DOES NOT PROVIDE REMOVAL. THE PROTECTION OF EXISTING PLANT MATERIAL AND THE REPAIR OR REPLACEMENT OF EXISTING PLANT MATERIAL DAMAGED BY THE CONTRACTOR SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 201 OF THE STANDARD SPECIFICATIONS UNLESS OTHERWISE NOTED.

THE CONTRACTOR SHALL ORDER ALL CONTAINER TREES IMMEDIATELY FOLLOWING EXECUTION OF THE CONTRACT TO ASSURE AVAILABILITY OF THE PLANT MATERIAL FOR SPRING PLANTING.

THE RESIDENT ENGINEER IN COORDINATION WITH THE DISTRICT LANDSCAPE ARCHITECT WILL STAKE ALL TREE PLANTINGS AT THE TREE MITIGATION SITE. UNLESS OTHERWISE NOTIFIED, THE CONTRACTOR SHALL PROVIDE AN ADEQUATE NUMBER OF LATHES SEVERAL WEEKS PRIOR TO THE SCHEDULED TREE PLANTING.

WHERE MULCH BEDS ARE SPECIFIED, ALL EXISTING GRASS, WEEDS, AND DEBRIS ARE TO BE REMOVED AND THE BEDS TILLED TO A DEPTH OF 6 INCHES PRIOR TO PLACING PROPOSED PLANTS. FOLLOWING PLANTING, BEDS SHALL BE MULCHED TO A DEPTH OF 4 INCHES. THIS WORK WILL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE FOR THE PLANTING ITEMS.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF LANDSCAPE ITEMS

GENERAL NOTES

SCALE: VERT. _____
 HORIZ. _____

DATE _____ DRAWN BY _____
 CHECKED BY _____