

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	16R-2	WHITESIDE	57	22
STA.	TO STA.			
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				

PAY CODE		50104400	50105220	60500040	60500060	XX146400				
STORM SEWER REMOVAL SCHEDULE										
LOCATION		CONCRETE HEADWALL REMOVAL	PIPE CULVERT REMOVAL	REMOVING MANHOLES	REMOVING INLETS	STORM SEWER REMOVAL				
						12" FOOT	15" FOOT	24" FOOT	30" FOOT	
US RTE 30 - URBAN										
STA. 1123+89.12	31.48 FT	LT	TO	STA. 1123+94.52	19.69 FT	LT				12.97
STA. 1123+94.52	19.69 FT	LT	TO	STA. 1123+97.24	19.31 FT	RT			1	39.09
STA. 1123+96.83	30.00 FT	RT	TO	STA. 1123+97.24	19.31 FT	RT				10.70
STA. 1124+00.91	30.95 FT	LT	TO	STA. 1125+04.01	15.89 FT	LT		104.14		
STA. 1125+04.01	15.89 FT	LT							1	
STA. 1126+94.15	46.75 FT	LT	TO	STA. 1127+18.19	47.41 FT	LT				34.02
STA. 1127+18.19	47.41 FT	LT	TO	STA. 1127+22.23	41.75 FT	LT				
STA. 1127+22.23	41.75 FT	LT						7.01		
STA. 1127+22.23	41.75 FT	LT	TO	STA. 1127+56.37	41.69 FT	LT				
STA. 1127+56.37	41.69 FT	LT							1	
STA. 1127+56.37	41.69 FT	LT	TO	STA. 1127+83.84	22.74 FT	LT				
STA. 1127+83.84	22.74 FT	LT								
STA. 1130+84.56	33.57 FT	LT							1	
STA. 1130+84.56	33.57 FT	LT	TO	STA. 1131+23.66	33.23 FT	LT				
STA. 1131+23.66	33.23 FT	LT							1	
STA. 1131+23.66	33.23 FT	LT	TO	STA. 1131+56.00	15.47 FT	LT				36.90
STA. 1131+55.99	39.00 FT	RT								
STA. 1131+55.99	39.00 FT	RT	TO	STA. 1131+56.00	15.47 FT	LT				54.47
STA. 1131+56.00	15.47 FT	LT							1	
SAWYER ROAD										
STA. 8+26.99	23.02 FT	RT	TO	STA. 8+79.73	23.03 FT	RT				53
SUBTOTAL - URBAN		2		53	5	5	113.45	104.14	125.39	62.76
TOTAL - URBAN		2		53	5	5	114	105	126	63
TOTAL		2		53	5	5		408		

PAY CODE		70400100	70400200	Z0030260	Z0030330	
TEMPORARY CONCRETE BARRIER SCHEDULE						
LOCATION		STAGE	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3
ROUTE 30 - RURAL						
STA. 1157+16.10	TO	STA. 1159+00.25	RT	5		2
STA. 1157+22.00	TO	STA. 1159+06.25		4	186.41	186.41
SUBTOTAL - RURAL				381	187	2
TOTAL				390	190	2

PAY CODE		66400560		
FENCE SCHEDULE				
LOCATION		CHAIN LINK FENCE, 6' (SPECIAL)		
LOCATION		FOOT		
US RTE 30 - URBAN				
STA. 1127+90.75	TO	STA. 1130+71.01	LT	283.37
STA. 1131+71.68	TO	STA. 1133+44.95	LT	173.34
SUBTOTAL - URBAN		457		
TOTAL		457		

PAY CODE		20101100	
TREE TRUNK PROTECTION SCHEDULE			
LOCATION		TREE TRUNK PROTECTION	
STATION	OFFSET	L/R	
US RTE 30 - URBAN			
STA. 1118+62.20	42.13	LT	1
STA. 1122+26.68	51.04	RT	1
STA. 1122+56.35	52.83	RT	1
STA. 1126+51.65	59.16	RT	1
STA. 1129+86.94	63.91	LT	1
STA. 1130+05.97	63.93	LT	1
STA. 1138+12.25	79.44	LT	1
STA. 1139+67.43	86.89	LT	1
SCENIC STREET			
STA. 15+60.14	23.71	LT	1
SAWYER ROAD			
STA. 8+82.72	53.16	RT	1
SUBTOTAL - URBAN		10	
US RTE 30 - RURAL			
STA. 1159+32.00	65.00	RT	1
STA. 1159+83.00	65.00	RT	1
STA. 1166+48.83	50.45	RT	1
SUBTOTAL - RURAL		3	
TOTAL		13	

PAY CODE		78300100	78300200	
PAVEMENT MARKING REMOVAL SCHEDULE				
LOCATION		PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION		SQ FT	EACH	
US RTE 30 - URBAN				
STA. 1108+81.68	TO	STA. 1110+37.04	RT	721.02
STA. 1108+81.68	TO	STA. 1114+01.68	RT	116.55
STA. 1122+50.00	TO	STA. 1126+00.00	RT	183.15
STA. 1126+00.00	TO	STA. 1132+00.00	RT	199.80
STA. 1132+00.00	TO	STA. 1138+00.00	RT	199.80
STA. 1138+00.00	TO	STA. 1144+00.00	RT	199.80
STA. 1144+00.00	TO	STA. 1150+00.00	RT	199.80
STA. 1150+00.00	TO	STA. 1156+00.00	RT	199.80
STA. 1156+00.00	TO	STA. 1157+00.00	RT	33.30
SUBTOTAL - URBAN		1,854	14	
US RTE 30 - RURAL				
STA. 1157+00.00	TO	STA. 1162+00.00	RT	166.50
STA. 1162+00.00	TO	STA. 1168+00.00	RT	199.80
STA. 1168+00.00	TO	STA. 1174+30.00	RT	199.80
STA. 1174+30.00	TO	STA. 1178+30.00	RT	133.20
STA. 1174+30.00	TO	STA. 1178+30.00	LT	133.20
STA. 1174+30.00	TO	STA. 1178+30.00		33.30
SUBTOTAL - RURAL		866	0	
TOTAL		2,720	14	

PAY CODE		44004300	
PAVEMENT BREAKING SCHEDULE			
LOCATION		PAVEMENT BREAKING	
LOCATION		SQ YD	
US RTE 30 - URBAN			
STA. 1156+00.00	TO	STA. 1157+00.00	427.08
SUBTOTAL - URBAN		428	
US RTE 30 - RURAL			
STA. 1157+00.00	TO	STA. 1157+87.00	246.78
STA. 1158+43.00	TO	STA. 1162+00.00	1,017.24
STA. 1162+00.00	TO	STA. 1168+00.00	1,683.16
SUBTOTAL - RURAL		2,948	
TOTAL		3,376	

PAY CODE		XZ127900		
RETAINING WALL REMOVAL SCHEDULE				
LOCATION		RETAINING WALL REMOVAL		
LOCATION		FOOT		
US RTE 30 - URBAN				
STA. 1117+70.89	TO	STA. 1117+71.54	LT	8.38
STA. 1117+86.04	TO	STA. 1117+90.38	LT	9.74
SUBTOTAL - URBAN		19		
TOTAL		19		

PAY CODE		63000000	63100045	
GUARDRAIL SCHEDULE				
LOCATION		STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 2	
LOCATION		FOOT	EACH	
US RTE 30 - URBAN				
STA. 1128+23.15	LT TO	STA. 1128+37.43	LT	1
STA. 1128+37.43	LT TO	STA. 1128+44.88	LT	7.44
STA. 1128+44.88	LT TO	STA. 1128+59.17	LT	1
SUBTOTAL - URBAN		12.5	2	
TOTAL		12.5	2	

PAY CODE		*Z0048800
RELOCATE EXISTING SURVEY MARKERS SCHEDULE		
LOCATION		RELOCATE EXISTING SURVEY MARKERS
LOCATION		EACH
US ROUTE 30 - RURAL		
LOCATION 1		1
SUBTOTAL - RURAL		1
TOTAL		1

PAY CODE		44000300		
CURB REMOVAL SCHEDULE				
LOCATION		CURB REMOVAL		
LOCATION		FOOT		
US RTE 30 - URBAN				
STA. 1132+75.49	RT TO	STA. 1132+77.45	RT	24.0
SUBTOTAL - URBAN		24		
TOTAL		24		

PAY CODE		Z0013300		
CONCRETE REMOVAL (SPECIAL) - 1.25" WIDE SCHEDULE				
LOCATION		CONCRETE REMOVAL (SPECIAL)		
LOCATION		SQ YD		
US RTE 30 - URBAN				
STA. 1117+12.34	TO	STA. 1118+56.05	RT	19.97
SUBTOTAL - URBAN		20		
TOTAL		20		

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES FAP ROUTE 309 (US 30) SECTION 16R-2, EAST CONTRACT FROM 0.2 MILE EAST OF JACKSON ST. TO FRENCH CREEK WHITESIDE COUNTY

SCALE: N.T.S. DRAWN BY: CAM  
 DATE: 09/01/05 CHECKED BY: RDY