

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	16R-2	WHITESIDE	547	23
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS	FED. AID PROJECT	

PAY CODE		25000310	25000910	25001830	25000400	25000500	25000600	25100115	25200100	25200200	21101615
PERMANENT SEEDING SCHEDULE											
LOCATION		SEEDING, CLASS 4	SEEDING, CLASS 1 (MODIFIED)	SEEDING, CLASS 6 (MODIFIED)	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 2	SODDING	SUPPLEMENTAL WATERING	TOPSOIL FURNISH AND PLACE, 4"
ACRE		ACRE	ACRE	POUND	POUND	POUND	ACRE	SQ YD	UNIT	SQ YD	
US RTE 30 - URBAN											
STA. 1115+15.00	TO	STA. 1120+00.00	LT						294.26	2.65	294.26
STA. 1114+50.00	TO	STA. 1120+00.00	RT						351.89	3.17	351.89
STA. 1120+00.00	TO	STA. 1126+00.00	LT						1,476.93	13.29	1,476.93
STA. 1120+00.00	TO	STA. 1126+00.00	RT						914.38	8.23	914.38
STA. 1126+00.00	TO	STA. 1132+00.00	LT						2,102.38	18.92	2,102.38
STA. 1126+00.00	TO	STA. 1132+00.00	RT						1,344.85	12.10	1,344.85
STA. 1132+00.00	TO	STA. 1138+00.00	LT	0.66	0.12	70.20	70.20	0.78	552.60	4.97	4,327.80
STA. 1132+00.00	TO	STA. 1138+00.00	RT	0.02	0.15	15.30	15.30	0.17	590.53	5.31	1,413.33
STA. 1138+00.00	TO	STA. 1144+00.00	LT	0.24	0.09	29.70	29.70	0.33	1,773.78	15.96	3,370.96
STA. 1138+00.00	TO	STA. 1144+00.00	RT	0.07	0.20	24.30	24.30	0.27			1,306.80
STA. 1144+00.00	TO	STA. 1150+00.00	LT	0.09	0.16	32.40	32.40	0.36			1,742.40
STA. 1144+00.00	TO	STA. 1150+00.00	RT	0.13	0.34	42.30	42.30	0.47			2,274.80
STA. 1150+00.00	TO	STA. 1156+00.00	LT	0.15	0.02	0.11	25.20	0.28			1,355.20
STA. 1150+00.00	TO	STA. 1156+00.00	RT	0.11	0.18	26.10	26.10	0.29			1,403.60
STA. 1156+00.00	TO	STA. 1157+00.00	LT	0.004	0.03	3.06	3.06	0.03			164.56
STA. 1156+00.00	TO	STA. 1157+00.00	RT	0.008	0.05	5.22	5.22	0.06			280.72
SCENIC STREET											
STA. 15+50.00	TO	STA. 16+00.00	LT						36.40	0.33	36.40
STA. 15+50.00	TO	STA. 16+30.00	RT						135.00	1.22	135.00
SAWYER ROAD											
STA. 7+00.00	TO	STA. 8+97.50	LT						413.80	3.72	413.80
STA. 7+00.00	TO	STA. 8+97.50	RT						760.85	6.85	760.85
SYCAMORE STREET											
STA. 5+50.00	TO	STA. 6+00.00	LT						69.26	0.62	69.26
STA. 5+50.00	TO	STA. 6+00.00	RT						43.73	0.39	43.73
BISHOP ROAD											
STA. 210+94.15	TO	STA. 212+31.00	LT	0.01	0.03	3.60	3.60	0.04			193.60
STA. 210+94.15	TO	STA. 213+82.25	RT	0.03	0.10	11.70	11.70	0.13			629.20
SUBTOTAL - URBAN		1.75	0.25	1.75	290	290	290	3.25	10,861	97.8	26,407
US RTE 30 - RURAL											
STA. 1157+00.00	TO	STA. 1162+00.00	LT	0.12	0.45	51.30	51.30	0.57			2,758.80
STA. 1157+00.00	TO	STA. 1162+00.00	RT	0.09	0.36	40.50	40.50	0.45			2,178.00
STA. 1162+00.00	TO	STA. 1168+00.00	LT	0.10	0.35	40.50	40.50	0.45			2,178.00
STA. 1162+00.00	TO	STA. 1168+00.00	RT	0.05	0.32	33.30	33.30	0.37			1,790.80
STA. 1168+00.00	TO	STA. 1174+30.00	LT	0.18	0.38	50.40	50.40	0.56			2,710.40
STA. 1168+00.00	TO	STA. 1174+30.00	RT	0.02	0.29	40.50	40.50	0.45			2,178.00
STA. 1174+30.00	TO	STA. 1178+30.00	LT		0.10	9.00	9.00	0.10			484.00
STA. 1174+30.00	TO	STA. 1178+30.00	RT		0.14	12.60	12.60	0.14			677.60
SUBTOTAL - RURAL		0.75	0.50	2.25	279	279	279	3.25	0.0	0.0	14,956
TOTAL		2.50	0.75	4.00	569	569	569	6.50	10,861	97.8	41,363

NITROGEN, PHOSPHORUS, AND POTASSIUM USE 90 lb/acre

THE CONTRACTOR SHALL SEED OR SOD ALL DISTURBED AREAS WITHIN THE PROJECT LIMITS. SEEDING CLASS 4 OR 6 (MODIFIED) SHALL BE USED, EXCEPT IN FRONT OF PROPERTIES WHERE THE GRASS WILL BE MOWED, THEN USE SEEDING CLASS 1 (MODIFIED). CLASS 6 (MODIFIED) SHALL BE USED ON FRONT SLOPES AND DITCH BOTTOMS. CLASS 4 SHALL BE USED BEHIND M-4.24, ON ALL BACKSLOPES AND AREAS BEHIND THE BACKSLOPE, AND BEYOND THE TOE OF FRONT SLOPE ON FILL SECTIONS WITHOUT DITCHES. THE CONTRACTOR SHALL SOD ANY DISTURBED AREAS FROM STA. 1114+50.00 TO STA. 1133+60.57 LT. & RT., INCLUDING SIDE ROADS. IN ADDITION SOD WILL PLACED THROUGH AGREEMENTS MADE IN THE COMMITMENTS.

PAY CODE		70300210	70300220				70300250	70300260	70300280	70301000
M.O.T.		TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4"				TEMPORARY PAVEMENT MARKING - LINE 8"	TEMPORARY PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 24"	WORK ZONE PAVEMENT REMOVAL
LOCATION		SQ. FT.	SOLID WHITE	SOLID DBL. YELLOW	SOLID YELLOW	SKIP-DASH YELLOW	WHITE	YELLOW	WHITE	SQ. FT.
FOOT		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
US RTE 30 - URBAN										
STAGE 1										
STA. 1111+96.50	TO	STA. 1114+00.00	203.50							67.16
STA. 1114+00.00	TO	STA. 1120+00.00	1,201.50	600.00						276.87
STA. 1120+00.00	TO	STA. 1126+00.00	1,200.00	600.00						198.00
STA. 1126+00.00	TO	STA. 1132+00.00	956.50	490.80						171.27
STA. 1132+00.00	TO	STA. 1138+00.00	1,200.00	600.00						638.00
STA. 1138+00.00	TO	STA. 1144+00.00	1,200.00	600.00						633.00
STA. 1144+00.00	TO	STA. 1150+00.00	1,200.00	600.00						
STA. 1150+00.00	TO	STA. 1156+00.00	1,200.00	600.00						
STA. 1156+00.00	TO	STA. 1157+00.00	105.00	61.50						
WINTER SHUTDOWN										
STA. 1111+61.68	TO	STA. 1114+00.00	31.2		477.00	119.30				228.15
STA. 1111+76.36	TO	STA. 1114+00.00		224.50						73.92
STA. 1114+00.00	TO	STA. 1120+00.00	78.0	1,200.00	1,200.00	300.00				969.00
STA. 1120+00.00	TO	STA. 1126+00.00	78.0	1,200.00	5.00	1,190.00	290.00			965.75
STA. 1126+00.00	TO	STA. 1132+00.00	124.8	1,235.50	669.60	110.30	27.60	393.70	48.20	1,524.85
STA. 1132+00.00	TO	STA. 1138+00.00		1,202.20	967.70	133.80		13.60	200.50	1,298.85
STA. 1138+00.00	TO	STA. 1138+00.00								101.60
STA. 1138+00.00	TO	STA. 1144+00.00	200.00	600.00						133.00
STA. 1138+00.00	TO	STA. 1144+00.00							220.40	180.20
STA. 1144+00.00	TO	STA. 1150+00.00		600.00						
STA. 1144+00.00	TO	STA. 1150+00.00							181.30	181.30
STA. 1150+00.00	TO	STA. 1156+00.00		600.00						
STA. 1150+00.00	TO	STA. 1156+00.00							194.00	194.00
STA. 1156+00.00	TO	STA. 1157+00.00		21.50						
STA. 1156+00.00	TO	STA. 1157+00.00							67.80	67.80
STAGE 6										
STA. 1130+63.30	TO	STA. 1132+00.00	31.2	90.80	136.70			116.90		199.88
STA. 1132+00.00	TO	STA. 1138+00.00		1,200.00	963.10	137.00		13.60	200.40	1,298.00
STA. 1138+00.00	TO	STA. 1144+00.00		1,200.00	600.00					798.00
STA. 1144+00.00	TO	STA. 1150+00.00		1,200.00	700.00	100.00			28.20	926.20
STA. 1150+00.00	TO	STA. 1156+00.00	62.4	1,200.00	650.00	100.00		238.00	117.00	1,203.36
STA. 1156+00.00	TO	STA. 1157+00.00		245.70	259.50	69.50		2.00	31.00	342.23
SUBTOTAL - URBAN		406	18,865	10,925	3,518	737	778	625	846	125
TOTAL - URBAN		406	18,865	10,925	3,518	737	778	625	846	125
US RTE 30 - RURAL										
STAGE 1										
STA. 1157+00.00	TO	STA. 1162+00.00		1,008.50	500.00					
STA. 1162+00.00	TO	STA. 1168+00.00		1,200.00	600.00					
STA. 1168+00.00	TO	STA. 1174+00.00		1,200.00	600.00					
STA. 1174+00.00	TO	STA. 1178+30.00		860.00	430.00					
WINTER SHUTDOWN										
STA. 1157+00.00	TO	STA. 1158+00.00			100.00					
STA. 1157+00.00	TO	STA. 1162+00.00							243.30	243.30
STA. 1162+00.00	TO	STA. 1168+00.00							323.50	323.50
STA. 1168+00.00	TO	STA. 1177+95.50							324.60	324.60
STAGE 6										
STA. 1157+00.00	TO	STA. 1162+00.00	62.4	1,000.00	994.20				251.50	1,484.75
STA. 1162+00.00	TO	STA. 1168+00.00		1,200.00	639.00	270.00	50.00		91.00	1,020.73
STA. 1168+00.00	TO	STA. 1174+00.00		1,200.00		300.00	150.00			544.50
STA. 1174+00.00	TO	STA. 1178+30.00		860.00			107.50			355.83
SUBTOTAL - RURAL		62	8,529	3,863	570	308	0	343	891	0
TOTAL - RURAL		62	8,529	3,863	570	308	0	343	891	0
TOTAL		468	27,394	14,790	7,036	1,045	778	968	1,737	125

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
 FAP ROUTE 309 (US 30)
 SECTION 16R-2, EAST CONTRACT
 FROM 0.2 MILE EAST OF JACKSON ST.
 TO FRENCH CREEK
 WHITES