

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	16R-2	WHITESIDE	547	24
STA.		TO STA.		
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				

PAY CODE	35101400	40200800	40300200	40800040	42001300	42300300
DRIVEWAY SCHEDULE	AGGREGATE BASE COURSE, TYPE B	AGGREGATE SURFACE COURSE, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	INCIDENTAL BITUMINOUS SURFACING	PROTECTIVE COAT	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH
LOCATION	TON	TON	TON	TON	SQ YD	SQ YD
US RTE 30 - URBAN						
STA. 1114+03.33	RT				17.38	8.69
STA. 1114+47.21	LT				10.34	5.17
STA. 1114+94.70	LT				20.00	10.00
STA. 1115+31.25	LT	2.17			48.92	24.46
STA. 1116+42.90	RT				105.42	52.71
STA. 1118+75.00	RT				54.50	27.25
STA. 1118+76.35	LT	3.01			94.18	47.09
STA. 1117+00.00	RT				78.16	39.08
STA. 1117+51.43	LT	2.32			48.50	24.25
STA. 1117+59.00	RT				83.56	41.78
STA. 1117+79.68	LT	10.15			48.50	24.25
STA. 1118+41.20	LT				91.06	45.53
STA. 1118+97.37	LT	19.00	0.06	4.75	100.00	50.00
STA. 1119+70.95	LT	5.94	0.02	1.49	99.44	49.72
STA. 1119+77.30	RT	37.32	0.12	9.34	139.34	69.67
STA. 1120+21.44	LT		40.55		99.44	49.72
STA. 1121+84.90	RT	77.88	0.24	19.49	110.84	55.42
STA. 1123+22.65	RT				141.86	70.93
STA. 1123+32.35	LT				94.76	47.38
STA. 1124+12.40	LT		9.81		67.44	33.72
STA. 1124+41.05	RT				159.64	79.82
STA. 1124+86.00	LT		13.74		119.68	59.84
STA. 1125+86.55	RT				162.34	81.17
STA. 1126+94.87	RT				349.64	174.82
STA. 1127+90.83	RT				95.52	47.76
STA. 1135+75.10	LT	12.05	0.04	3.02		
STA. 1136+00.84	RT	8.13	0.02	1.35	349.78	174.89
STA. 1137+09.83	RT	116.51	0.27	21.19		
STA. 1138+33.50	RT	161.95	44.23	29.90		
STA. 1140+01.83	LT	129.69	0.24	18.92		
STA. 1144+75.00	LT	39.22				
STA. 1149+01.68	LT	21.47	23.31	0.03	88.24	44.12
STA. 1150+12.65	RT	8.13	0.02	1.35	524.44	262.22
SCENIC STREET						
STA. 16+09.05	RT	105.13	0.33	26.31	52.52	26.26
SAWYER ROAD						
STA. 8+29.10	LT	9.48	0.03	2.37	128.58	64.29
STA. 8+52.60	RT				277.00	138.50
SYCAMORE STREET						
STA. 5+77.17	RT				52.60	26.30
BISHOP ROAD						
STA. 211+22.58	LT	57.75	9.22	0.14	11.19	
SUBTOTAL - URBAN						
		810	159	2.0	153	3,914
US RTE 30 - RURAL						
STA. 1166+50.00	RT	12.05	0.04	3.01		
STA. 1166+82.65	LT	115.42	0.28	21.98		
STA. 1170+75.00	RT	109.79				
STA. 1172+74.37	RT	99.28	0.22	17.93		
STA. 1172+75.00	LT	69.31				
SUBTOTAL - RURAL						
		406	0	0.6	43	0
TOTAL						
		1,216	159	2.6	196	3,914

CONVERSION RATES: ASPHALT: 112 LB/SQ YD IN AGGREGATE = 2.05 TON/CU YD
 APPLICATION RATES - BITUMINOUS MATERIALS (PRIME COAT): INCIDENTAL BITUMINOUS SURFACING ON GRANULAR BASE: 0.00143 TONS / SQ YD

PAY CODE	X0322923		
SEGMENTAL WALL SCHEDULE	SEGEMENTAL CONCRETE BLOCK WALL		
LOCATION	SQ FT		
US RTE 30 - URBAN			
STA. 1125+25.00	TO STA. 1126+90.00	LT	828.00
SCENIC STREET - URBAN			
STA. 15+86.88	TO STA. 15+87.34	RT	212.88
STA. 15+87.34	TO STA. 15+72.31	RT	77.70
SUBTOTAL - URBAN			1119
TOTAL			1,119

PAY CODE	42400200		
SIDEWALK SCHEDULE	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH		
LOCATION	SQ FT		
US RTE 30 - URBAN			
STA. 1126+82.64	TO STA. 1126+90.16	RT	12.03
SCENIC SREET			
STA. 15+67.00	TO STA. 15+72.31	RT	208.68
SUBTOTAL - URBAN			221.0
TOTAL			221

PAY CODE	TREE REPLACEMENT SCHEDULE - URBAN	UNIT	QUANTITY
*A2001714	TREE, ACER SACCHARUM (SUGAR MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	9
*A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	9
*A2007814	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	9
*B2002716	TREE, MALUS ADIRONDACK (ADIRONDACK CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	9
*B2004814	TREE, MALUS SARGENTII (SARGENT CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10
*B2005214	TREE, MALUS SUTYZAM (SUGAR TYME CRAB APPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10
TOTAL - URBAN			56
TOTAL			56

LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT
 MULCH SHALL BE HARD WOOD CHIPS, 5 FOOT WIDTH, 4 INCHES THICK WITH WEED BARRIER FABRIC
 ALTERNATE PLANTING SITE, I-88/ IL78 INTERCHANGE

PAY CODE	50800105	54002020	54201525	54248510
TEMPORARY CULVERT EXTENSION SCHEDULE	REINFORCEMENT BARS	EXPANSION BOLTS 3/4 INCH	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 60"	CONCRETE COLLAR
LOCATION	POUND	EACH	FOOT	CU YD
US RTE 30 - RURAL				
STA. 1158+14.82	RT	75.49	20	80.00
SUBTOTAL - RURAL				
		76	20	80
TOTAL				
		76	20	80

PAY CODE	35101400	40300200	40800040
INCIDENTAL BITUMINOUS SURFACING SUMMARY	AGGREGATE BASE COURSE, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	INCIDENTAL BITUMINOUS SURFACING
LOCATION	TON	TON	TON
ROUTE 30 - URBAN			
STA. 1116+83.00	TO STA. 1116+88.00	RT	0.75
STA. 1117+12.00	TO STA. 1117+47.00	RT	8.27
STA. 1117+71.00	TO STA. 1119+59.80	RT	46.93
STA. 1119+14.87	TO STA. 1119+53.46	LT	21.61
STA. 1127+79.34	TO STA. 1129+36.06	RT	115.03
STA. 1132+75.60	TO STA. 1136+23.05	RT	1,086.52
SUBTOTAL - URBAN			
		1,280	4.1
TOTAL			
		1,280	4.1

APPLICATION RATES - BITUMINOUS MATERIALS (PRIME COAT): INCIDENTAL BITUMINOUS SURFACING ON GRANULAR BASE: 0.00143 TONS / SQ YD

PAYCODE	X4066740		
LEVELING BINDER SCHEDULE	LEVELING BINDER (HAND METHOD), SUPERPAVE N70		
LOCATION	TON		
US RTE 30 - URBAN			
STA. 1115+15.00	TO STA. 1174+30.00	LT	10.00
SUBTOTAL - URBAN			10.0
TOTAL			10.0

PAY CODE	40200800	
TEMPORARY DRIVEWAY SCHEDULE	AGGREGATE SURFACE COURSE, TYPE B	
LOCATION	TON	
US RTE 30 - URBAN		
STA. 1115+31.25	LT	6.05
STA. 1116+42.90	RT	6.67
STA. 1116+76.35	LT	6.68
STA. 1117+51.43	LT	6.67
STA. 1117+79.68	LT	10.72
STA. 1118+41.20	LT	6.67
STA. 1118+97.37	LT	8.57
STA. 1119+70.95	LT	6.66
STA. 1119+77.30	RT	9.33
STA. 1120+21.44	LT	11.16
STA. 1121+84.90	RT	14.26
STA. 1123+22.65	RT	6.55
STA. 1123+32.35	LT	7.47
STA. 1124+12.40	LT	13.03
STA. 1124+31.00	RT	6.43
STA. 1124+86.00	LT	14.59
STA. 1125+86.55	RT	6.54
STA. 1126+84.91	RT	23.30
STA. 1137+09.83	RT	10.97
STA. 1138+41.00	RT	26.78
STA. 1140+01.83	LT	27.07
STA. 1144+75.00	LT	7.06
STA. 1149+01.68	LT	19.04
STA. 1150+12.65	RT	13.12
SYCAMORE STREET		
STA. 5+77.17	RT	4.08
BISHOP ROAD		
STA. 211+22.58	LT	7.65
SUBTOTAL - URBAN		288
US RTE 30 - RURAL		
STA. 1166+82.65	LT	12.54
STA. 1170+75.00	RT	24.70
STA. 1172+74.37	RT	15.36
STA. 1172+75.00	LT	14.58
SUBTOTAL - RURAL		68
TOTAL		356

CONVERSION RATES: AGGREGATE = 2.05 TON/CU YD

REVISIONS	NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP ROUTE 309 (US 30)
 SECTION 16R-2, EAST CONTRACT
 FROM 0.2 MILE EAST OF JACKSON ST.
 TO FRENCH CREEK
 WHITESIDE COUNTY
 SCALE: N.T.S. DRAWN BY CAM
 DATE 09/01/05 CHECKED BY RDY