CONTRACT NO. 64969

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	16R-2	WHITESIDE	547	28
STA.		TO STA.		
FED. ROAD DIST. NO. 2	ILLINOIS	FED. AID PROJECT		

MAINTENANCE OF TRAFFIC STORM SEWER SCHEDULE

PAY CODE							542D0217	542D0223	550A0050
							PIPE CULVERTS, CLASS D, TYPE 1		STORM SEWERS, CLASS A, TYPE 1 12"
							12"	18"	
LOCATION						STAGE	FT	FT	FT
ROUTE 30 -URBAN									
STA. 1114+22.00	25.51 FT	LT				2			2.00
STA. 1114+38.75	23.30 FT	RT				1			2.00
STA. 1115+74.94	26.10 FT	RT				1			1.50
STA. 1116+25.00	33.00 FT	RT	TO	STA. 1117+25.00	35.00 FT	RT 1	100.02		
STA. 1119+00.00	34.00 FT	RT	TO	STA. 1120+00.00	33.00 FT	RT 1	100.00		
STA. 1120+60.00	28.00 FT	RT				1			1.00
STA. 1121+50.00	37.00 FT	RT	TO	STA. 1122+25.00	33.00 FT	RT 1	75.11		
STA. 1122+35.00	28.00 FT					1			1.00
STA. 1122+75.00	34.00 FT	RT	TO	STA. 1123+50.00	34.00 FT	RT 1	75.00		
STA. 1123+75.09	28.00 FT					1			1.00
STA. 1123+96.83	30.00 FT	RT				1			1.00
STA. 1124+80.00	28.00 FT					1			1.00
SUBTOTAL -URBAN							351	0	11
ROUTE 30 -RURAL									
STA. 1168+83.48	45.81 FT	RT	TO	STA. 1169+36.00	50.00 FT	RT 4		52.68	
STA. 1170+25.00	64.00 FT	RT	TO	STA. 1171+00.00	41.72 FT	RT 1		78.24	
STA. 1172+50.00	40.10 FT	RT	TO	STA. 1173+00.00	38.60 FT	RT 1		50.00	
SUBTOTAL -RURAL							0	181	0
TOTAL							351	181	11

DRAIN FOR AGGREGATE BASE SCHEDULE

PAY CODE			60107600	31100910
			PIPE UNDERDRAINS 4"	SUB-BASE GRANULAR MATERIAL, TYPE A 12"
LOCATION			FOOT	SQ YD
US RTE 30 - URBAN				
STA. 1115+75.00			53	
STA. 1120+56.00			56	
STA. 1122+33.00			56	
STA. 1124+60.00			28	
STA. 1124+82.00			28	
STA. 1126+10.00			56	
STA. 1128+60.00			64	
STA. 1130+20.00			50	
STA. 1131+55.00			28	
STA. 1135+50.00	LT	RT		6
STA. 1138+00.00	LT	RT		6
STA. 1140+50.00	LT	RT		6
STA. 1143+00.00	LT	RT		6
STA. 1145+50.00	LT	RT		6
STA. 1148+00.00	RT			3
STA. 1148+40.00	LT			3
STA. 1152+50.00	LT	RT		6
STA. 1155+00.00	LT	RT		6
SUBTOTAL - URBAN			419	48
US RTE 30 - RURAL				
STA. 1157+50.00	LT	RT		6
STA. 1159+00.00	LT	RT		6
STA. 1160+50.00	LT	RT		6
STA. 1162+00.00	LT	RT		6
STA. 1163+50.00	LT	RT		6
STA. 1165+00.00	LT	RT		6
STA. 1166+50.00	LT	RT		6
STA. 1168+00.00	LT	RT		6
STA. 1169+40.00	LT			3
STA. 1169+50.00	RT			3
STA. 1171+00.00	LT	RT		6
STA. 1172+32.00	LT	RT		6
STA. 1174+00.00	LT	RT		6
SUBTOTAL - RURAL			0	72
TOTAL			419	120

PIPE CULVERT SCHEDULE

PAY CODE							28100107	28200300	54215550	54215559	542D0220	542D0229
							STONE RIPRAP, CLASS A4	FILTER FABRIC	METAL END SECTIONS		PIPE CULVERTS, CLASS D, TYPE 1	
									15"	24"	15"	24"
LOCATION							SQ YD	SQ YD	EA	EA	FT	FT
US RTE 30 - URBAN												
STA. 1139+75.00	30.00 FT	LT								1		
STA. 1139+75.00	30.00 FT	LT	TO	STA. 1140+25.00	34.40 FT	LT						50
STA. 1140+25.00	34.40 FT	LT								1		
STA. 1144+50.00	35.32 FT	LT								1		
STA. 1144+50.00	35.32 FT	LT	TO	STA. 1145+00.00	35.99 FT	LT						50
STA. 1145+00.00	35.99 FT	LT								1		
STA. 1147+69.21	35.52 FT	LT	TO	STA. 1147+78.61	32.11 FT	LT	6	14				
STA. 1153+11.63	34.73 FT	LT	TO	STA. 1153+23.92	43.34 FT	LT	9	19				
STA. 1156+00.00	55.00 FT	LT								1		
STA. 1156+00.00	55.00 FT	LT	TO	STA. 1157+00.00	70.00 FT	LT						102
STA. 1156+81.59	56.51 FT	RT	TO	STA. 1157+89.77	75.50 FT	RT	245	305				
STA. 1157+00.00	70.00 FT	LT								1		
SAWYER ROAD												
STA. 7+29.92	22.28 FT	LT	TO	STA. 7+44.88	22.31 FT	LT	13	25				
STA. 7+46.75	22.28 FT	RT	TO	STA. 7+66.74	22.28 FT	RT	22	37				
SUBTOTAL - URBAN							295	400	0	6	0	202
US RTE 30 - RURAL												
STA. 1157+03.70	70.50 FT	LT	TO	STA. 1157+90.50	75.00 FT	LT	194	243				
STA. 1158+09.60	60.00 FT	RT	TO	STA. 1158+20.60	60.00 FT	RT	19	32				
STA. 1158+39.00	73.50 FT	LT	TO	STA. 1158+78.90	72.35 FT	LT	89	118				
STA. 1158+41.31	67.90 FT	RT	TO	STA. 1158+77.10	57.50 FT	RT	86	114				
STA. 1166+50.00	42.49 FT	LT							1			
STA. 1166+50.00	42.49 FT	LT	TO	STA. 1167+10.00	44.51 FT	LT					60	
STA. 1167+10.00	44.51 FT	LT							1			
STA. 1170+16.43	66.29 FT	RT	TO	STA. 1170+21.38	64.97 FT	RT	12	25				
STA. 1170+25.00	64.00 FT	RT							1			
STA. 1170+25.00	64.00 FT	RT	TO	STA. 1171+25.00	37.28 FT	RT					104	
STA. 1171+25.00	37.28 FT	RT							1			
STA. 1172+50.00	37.85 FT	RT							1			
STA. 1172+50.00	37.85 FT	RT	TO	STA. 1173+00.00	35.76 FT	RT					50	
STA. 1173+00.00	35.76 FT	RT							1			
STA. 1172+50.00	40.87 FT	LT							1			
STA. 1172+50.00	40.87 FT	LT	TO	STA. 1173+00.00	40.14 FT	LT					50	
STA. 1173+00.00	40.14 FT	LT							1			
SUBTOTAL - RURAL							400	532	8	0	264	0
TOTAL							695	932	8	6	264	202

FIELD TILE SCHEDULE

PAY CODE	61133100	61140000	61140100	61140200
	FIELD TILE JUNCTION VAULTS, 2' DIA.	STORM SEWERS, SPECIAL		
		8"	10"	12"
LOCATION	EACH	FOOT	FOOT	FOOT
US RTE 30 - RURAL				
LOCATION 1	1	50.0	50.0	50.0
LOCATION 2	1	50.0	50.0	50.0
LOCATION 3	1	50.0	50.0	50.0
LOCATION 4	1	50.0	50.0	50.0
SUBTOTAL - RURAL	4	200	200	200
TOTAL	4	200	200	200

DRAINAGE STRUCTURE REPAIR/RECONSTRUCTION SCHEDULE

PAY CODE			Z0018200	Z0018300
			DRAINAGE STRUCTURE RECONSTRUCTION (SPECIAL)	DRAINAGE STRUCTURE REPAIR
LOCATION			EACH	EACH
STATION	OFFEST	L/R		
US RTE 30 - URBAN				
STA. 1114+22.00	25.51	LT	1	1
STA. 1114+38.75	23.30	RT	1	1
STA. 1115+74.94	26.10	RT		1
STA. 1120+60.00	28.00	RT		1
STA. 1122+35.00	28.00	RT		1
STA. 1123+75.09	28.00	RT		1
STA. 1123+96.83	30.00	RT		1
STA. 1124+80.00	28.00	RT		1
SUBTOTAL - URBAN			2	8
TOTAL			2	8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
FAP ROUTE 309 (US 30)
SECTION 16R-2, EAST CONTRACT
FROM 0.2 MILE EAST OF JACKSON ST.
TO FRENCH CREEK
WHITESIDE COUNTY

SCALE: N.T.S. DRAWN BY CAM

DATE 09/01/05 CHECKED BY RDY