CONTRACT NO. 64969

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	16R-2	WHITESIDE	547	29
STA.		TO STA.		
FED. ROAD DIST. NO. 2	ILLINOIS	FED. AID PROJECT		

PAY CODE							20800150	XX001135	54213657	54213660	54213663	54213675	54247150	60218400	60218500	60221700	60223800	60236200	60242801	60242802	550A0140	550A0340	550A0360	550A0380	550A0400	550A0410
STORM SEWER SCHEDULE							TRENCH BACKFILL	PAVEMENT PATCHING SPECIAL	PRECAST REINFORCED CONCRETE FLARED END SECTIONS				GRATING FOR CONCRETE FLARED END SECTION 30"	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	INLETS, TYPE A, TYPE 8 GRATE	INLETS, SPECIAL, NO. 5	INLETS, SPECIAL, NO. 6	STORM SEWERS, CLASS A, TYPE 1	STORM SEWERS, CLASS A, TYPE 2				
									12"	15"	18"	30"									30"	12"	15"	18"	21"	24"
LOCATION							CU YD	SQ YD	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	FT	FT	FT	FT	FT	FT
US RTE 30 - URBAN																										
STA. 1115+75.21	26.50 FT	LT																	1							
STA. 1115+74.94	26.10 FT	RT																	1							
STA. 1115+75.21	26.50 FT	LT	TO	STA. 1115+74.94	26.10 FT	RT	16.3	18																		
STA. 1115+74.94	26.10 FT	RT	TO	STA. 1114+38.75	23.30 FT	RT	31.2															132				
STA. 1120+60.00	28.00 FT	RT																	1							
STA. 1120+60.00	28.00 FT	LT																	1							
STA. 1122+35.00	28.00 FT	LT																	1							
STA. 1122+35.00	28.00 FT	RT																	1							
STA. 1123+92.27	29.84 FT	LT															1									
STA. 1123+91.21	40.43 FT	LT										1	1													
STA. 1123+96.83	30.00 FT	RT															1									
STA. 1123+75.09	28.00 FT	RT																		1						
STA. 1124+80.00	28.00 FT	RT																	1							
STA. 1124+58.00	28.00 FT	LT																	1							
STA. 1126+96.33	36.55 FT	LT												1												
STA. 1120+60.00	28.00 FT	RT	TO	STA. 1120+60.00	28.00 FT	LT	15.8	19																		
STA. 1120+60.00	28.00 FT	LT	TO	STA. 1122+35.00	28.00 FT	LT	45.1																	169		
STA. 1122+35.00	28.00 FT	RT	TO	STA. 1122+35.00	28.00 FT	LT	16.0	19																		
STA. 1122+35.00	28.00 FT	LT	TO	STA. 1123+92.27	29.84 FT	LT	46.2																	152		
STA. 1123+92.27	29.84 FT	LT	TO	STA. 1123+91.21	40.43 FT	LT	0.7														2					
STA. 1123+92.27	29.84 FT	LT	TO	STA. 1123+96.83	30.00 FT	RT	56.3	19																		
STA. 1123+75.09	28.00 FT	RT	TO	STA. 1123+96.83	30.00 FT	RT	6.2																			
STA. 1124+80.00	28.00 FT	RT	TO	STA. 1123+96.83	30.00 FT	RT	27.8																			
STA. 1124+58.00	28.00 FT	LT	TO	STA. 1123+92.27	29.84 FT	LT	41.4																			61
STA. 1126+10.03	28.00 FT	LT	TO	STA. 1124+58.00	28.00 FT	LT	55.0																			146
STA. 1126+10.06	28.00 FT	RT																	1							
STA. 1126+10.03	28.00 FT	LT																	1							
STA. 1126+88.85	28.00 FT	LT																	1							
STA. 1127+86.13	38.08 FT	LT																1								
STA. 1127+86.13	38.08 FT	LT	TO	STA. 1127+90.75	28.00 FT	LT																10				
STA. 1127+90.75	28.00 FT	LT																	1							
STA. 1126+10.06	28.00 FT	RT	TO	STA. 1126+10.06	28.00 FT	LT	16.4	19																		
STA. 1126+88.85	28.00 FT	LT	TO	STA. 1126+10.03	28.00 FT	LT	21.7																		78	
STA. 15+60.00	18.00 FT	LT	TO	STA. 1126+96.33	36.55 FT	LT	12.7															35				
STA. 1126+96.33	36.55 FT	LT	TO	STA. 1126+88.85	28.00 FT	LT	7.2																		10	
STA. 1127+74.60	26.00 FT	LT	TO	STA. 1126+88.85	28.00 FT	LT	11.0																			
STA. 1127+90.75	28.00 FT	LT	TO	STA. 1128+60.18	28.00 FT	LT	11.8																64			
STA. 1128+60.18	28.00 FT	LT																	1							
STA. 1128+60.09	35.00 FT	RT																	1							
STA. 1128+75.00	48.15 FT	RT													1											
STA. 1129+18.50	48.25 FT	RT												1												
STA. 1130+20.14	49.60 FT	RT																	1							
STA. 1126+96.33	36.55 FT	LT	TO	STA. 1127+90.75	28.00 FT	LT	62.2	42																	95	
STA. 1128+75.00	48.15 FT	RT	TO	STA. 1129+18.50	48.25 FT	RT	54.1																44			
STA. 1129+18.50	48.25 FT	RT	TO	STA. 8+76.00	24.00 FT	LT	128.3																98			
STA. 9+00.00	35.90 FT	RT	TO	STA. 1130+45.35	42.05 FT	RT	67.7																	50		
STA. 1130+20.14	49.60 FT	RT	TO	STA. 1130+45.35	42.05 FT	RT	16.7															26				
STA. 1130+45.35	42.05 FT	RT	TO	STA. 1131+55.78	39.80 FT	RT	180.0	43															111			
STA. 1131+55.78	39.80 FT	RT	TO	STA. 1132+49.90	42.75 FT	RT	118.5																95			
STA. 1130+53.65	28.00 FT	LT	TO	STA. 1131+55.41	28.00 FT	LT	30.8															102				
STA. 1131+67.05	38.08 FT	LT	TO	STA. 1131+55.41	28.00 FT	LT																15				
STA. 1130+53.65	28.00 FT	LT	TO	STA. 5+45.00	22.00 FT	LT	4.0																			
STA. 1130+75.61	52.81 FT	LT	TO	STA. 5+45.00	22.00 FT	LT																9				
STA.1130+53.65	28.00 FT	LT	TO	STA. 1131+39.00	26.00 FT	LT	12.7																			
STA. 1130+75.61	52.81 FT	LT																1								
STA. 1130+45.35	42.05 FT	RT												1												
STA. 1131+55.78	39.80 FT	RT												1												
STA. 1131+55.41	28.00 FT	LT																	1							
STA. 1131+67.05	38.08 FT	LT																1								
STA. 1132+49.90	42.75 FT	RT	TO	STA. 1132+49.90	51.65 FT	RT	6.8															9				
STA. 1132+49.90	42.75 FT	RT	TO	STA. 1134+76.60	47.00 FT	RT	142.8															226				
STA. 1130+45.35	42.05 FT	RT	TO	STA. 1130+53.65	28.00 FT	LT	59.5	25															72			
STA. 1128+60.09	35.00 FT	RT	TO	STA. 1128+75.00	48.15 FT	RT	4.9															19				
STA. 1133+49.57	38.08 FT	LT	TO	STA. 1133+75.00	38.08 FT	LT																26				
STA.1130+53.65	28.00 FT	LT																	1							
STA. 1132+49.90	42.75 FT	RT												1												
STA. 1132+49.90	51.65 FT	RT																1								

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
FAP ROUTE 309 (US 30)
SECTION 16R-2, EAST CONTRACT
FROM 0.2 MILE EAST OF JACKSON ST.
TO FRENCH CREEK
WHITESIDE COUNTY

SCALE: N.T.S. DRAWN BY CAM

DATE 09/01/05 CHECKED BY RDY