

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	24BR-1	JO DAVIESS	50	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X080-2A 80% FED/ 20% STATE	SFTY - 3N 80% FED/ 20% STATE
20200100	EARTH EXCAVATION	CU YD	299	299	
20400800	FURNISHED EXCAVATION	CU YD	121	121	
28100105	STONE RIPRAP, CLASS A3	SQ YD	741	741	
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	331	331	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	193	193	
40600990	TEMPORARY RAMP	SQ YD	56	56	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	380	380	
44000400	GUTTER REMOVAL	FOOT	148	148	
44002000	CONCRETE CURB REMOVAL	FOOT	137	137	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	68	68	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURE	EACH	1	1	
50102400	CONCRETE REMOVAL	CU YD	2.8	2.8	
50300225	CONCRETE STRUCTURES	CU YD	2.8	2.8	
50300260	BRIDGE DECK GROOVING	SQ YD	560	560	
50300300	PROTECTIVE COAT	SQ YD	565	565	
5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	574	574	
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	19	19	
50301250	FORMED CONCRETE REPAIR (DEPTH GREATER THAN 5 INCHES)	SQ FT	160	160	
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	4956	4956	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7550	7550	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	301	301	
51500100	NAME PLATES	EACH	1	1	
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	937.5	937.5	
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	1285	1285	
63500105	DELINEATORS	EACH	4	4	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6	

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X080-2A 80% FED/ 20% STATE	SFTY - 3N 80% FED/ 20% STATE
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4712	4712	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1571	1571	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	564	564	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	612	612	
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4956	4956	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	19	19	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	712	712	
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	150	150	
X0321781	MECHANICAL SPLICE	EACH	54	54	
X0323557	BRIDGE JOINT SYSTEM (EXPANSION), 1"	FOOT	70	70	
X0712400	TEMPORARY PAVEMENT	SQ YD	483	483	
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	113	113	
XX005495	PRECAST PRESTRESSED CONCRETE DECK BEAM (21" DEPTH) SPECIAL	SQ FT	146	146	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	44	44	
Z0002600	BAR SPLICERS	EACH	171	171	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON - REDIRECTIVE), TEST LEVEL 3	EACH	4		4

* SPECIALTY ITEMS

PLT DATE = Mon Dec 12 09:11:04 2005
 PLT SCALE = 50:0000
 USER NAME = mgj11j

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT.	DRAWN BY	CHECKED BY
DATE		

SUMMARY OF QUANTITIES