

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	24BR-1	JO DAVIESS	50	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SCHEDULE OF QUANTITIES

**20200100 EARTH EXCAVATION**

CU YD	LOCATION				
	US 20				
120	LT&RT	2019+31	- 2022+60	(FROM CROSS SECTIONS)	
179	LT&RT	2024+00	- 2029+40	(FROM CROSS SECTIONS)	
299	TOTAL				

**20400000 FURNISHED EXCAVATION**

CU YD	LOCATION				
	US 20				
120	LT&RT	2022+25	- 2022+60	(FROM CROSS SECTIONS)	
1	LT&RT	2024+00	- 2028+75	(FROM CROSS SECTIONS)	
121	TOTAL				

**28100105 STONE RIPRAP, CLASS A3**

SQ YD	LOCATION				
	US 20				
202	LT	2020+75	- 2022+60	(FROM CROSS SECTIONS)	
55	RT	2021+75	- 2022+60	(FROM CROSS SECTIONS)	
484	LT	2024+00	- 2028+75	(FROM CROSS SECTIONS)	
741	TOTAL				

**31100100 SUB-BASE GRANULAR MATERIAL, TYPE A**

TON	LOCATION				
	US 20				
89	RT	2019+31	- 2022+48	(FROM CROSS SECTIONS)	
49	LT	2020+00	- 2022+60	(FROM CROSS SECTIONS)	
65	RT	2024+00	- 2026+59	(FROM CROSS SECTIONS)	
128	LT	2024+12	- 2029+40	(FROM CROSS SECTIONS)	
331	TOTAL				

**40600980 BITUMINOUS SURFACE REMOVAL - BUTT JOINT**

SQ YD	LOCATION				
	US 20				
97	LT&RT	2022+30	- 2022+62		
96	LT&RT	2023+97	- 2024+29		
193	TOTAL				

**40600990 TEMPORARY RAMP**

SQ YD	LOCATION				
	US 20				
28	LT&RT	2022+49	- 2022+56		
28	LT&RT	2024+03	- 2024+10		
56	TOTAL				

**44000030 BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)**

SQ YD	LOCATION				
	US 20				
98	RT	2019+31	- 2021+76	(FROM CROSS SECTIONS)	
66	LT	2020+08	- 2021+74	(FROM CROSS SECTIONS)	
5	LT	2022+21	- 2022+30	(FROM CROSS SECTIONS)	
4	RT	2022+23	- 2022+30	(FROM CROSS SECTIONS)	
4	RT	2024+29	- 2024+36	(FROM CROSS SECTIONS)	
4	LT	2024+29	- 2024+37	(FROM CROSS SECTIONS)	
78	RT	2024+71	- 2026+43	(FROM CROSS SECTIONS)	
96	LT	2024+78	- 2027+57	(FROM CROSS SECTIONS)	
25	LT	2028+09	- 2029+40	(FROM CROSS SECTIONS)	
380	TOTAL				

**44000400 GUTTER REMOVAL**

EQ FT	LOCATION				
	US 20				
32	RT	2022+16	- 2022+48		
42	LT	2022+18	- 2022+60		
42	RT	2024+00	- 2024+42		
32	LT	2024+12	- 2024+44		
148	TOTAL				

**44002000 CONCRETE CURB REMOVAL**

EQ FT	LOCATION				
	US 20				
32	RT	2022+15	- 2022+47		
42	LT	2022+17	- 2022+59		
31	RT	2024+00	- 2024+31		
32	LT	2024+12	- 2024+44		
137	TOTAL				

**48101200 AGGREGATE SHOULDERS, TYPE B**

TONS	LOCATION				
	US 20				
21	RT	2019+31	- 2021+75	(FROM CROSS SECTIONS)	
13	LT	2020+00	- 2022+75	(FROM CROSS SECTIONS)	
24	RT	2024+00	- 2026+60	(FROM CROSS SECTIONS)	
10	LT	2028+75	- 2029+40	(FROM CROSS SECTIONS)	
68	TOTAL				

**63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A**

EQ FT	LOCATION				
	US 20				
200	RT	2020+14	- 2022+14		
162.5	LT	2020+63	- 2022+26		
162.5	RT	2024+33	- 2025+96		
412.5	LT	2024+45	- 2028+58		
937.5	TOTAL				

**63100007 TRAFFIC BARRIER TERMINAL, TYPE 6A**

EACH	LOCATION				
	US 20				
1	RT	2022+14	- 2022+48		
1	LT	2022+26	- 2022+60		
1	RT	2024+00	- 2024+33		
1	LT	2024+12	- 2024+45		
4	TOTAL				

**63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)**

EACH	LOCATION				
	US 20				
1	RT	2019+64	- 2020+14		
1	LT	2020+13	- 2020+63		
1	RT	2025+96	- 2026+46		
1	LT	2028+58	- 2029+08		
4	TOTAL				

**63200310 GUARDRAIL REMOVAL**

EQ FT	LOCATION				
	US 20				
291	RT	2019+58	- 2022+48		
253	LT	2020+07	- 2022+60		
252	RT	2024+00	- 2026+51		
489	LT	2024+12	- 2029+00		
1285	TOTAL				

**63500105 DELINEATORS**

EACH	LOCATION				
	US 20				
1	RT	2019+64			
1	LT	2020+13			
1	RT	2026+46			
1	LT	2029+08			
4	TOTAL				

**70300220 TEMPORARY PAVEMENT MARKING - LINE 4"**

EQ FT	LOCATION				
	US 20				
596	RT	2020+30	- 2026+26	(STAGE 1A)	
2058	LT&RT	2018+06	- 2028+35	(STAGE 1)	
2058	LT&RT	2018+06	- 2028+35	(STAGE 2)	
4712	TOTAL				

**70301000 WORK ZONE PAVEMENT MARKING REMOVAL**

SQ FT	LOCATION				
	US 20				
199	RT	2020+30	- 2026+26	(STAGE 1A)	
686	LT&RT	2018+06	- 2028+35	(STAGE 1)	
686	LT&RT	2018+06	- 2028+35	(STAGE 2)	
1571	TOTAL				

**70400100 TEMPORARY CONCRETE BARRIER**

EQ FT	LOCATION				
	US 20				
396	RT	2021+30	- 2025+26	(STAGE 1A)	
84	LT&RT	2020+46	- 2021+30	(STAGE 1)	
84	LT&RT	2025+26	- 2026+10	(STAGE 1)	
564	TOTAL				

PLOT DATE = Mon, Dec 12 09:33:52 2005  
 FILE NAME = c:\p\o\mets\p\2005\082025\vr.dgn  
 PLOT SCALE = 50.0000 / IN.  
 USER NAME = mg1111

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_