

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	24BR-1	JO DAVIESS	50	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SCHEDULE OF QUANTITIES

**70400200 RELOCATE TEMPORARY CONCRETE BARRIER**

EQOI	LOCATION			
	US 20			
24	RT	2021+30	2021+54	(STAGE 1)
24	RT	2025+02	2025+26	(STAGE 1)
564	LT&RT	0+0	0+0	(STAGE 2)
612	TOTAL			

**78001110 PAINT PAVEMENT MARKING - LINE 4' (TWO COATS)**

EQOI	LOCATION			
	US 20			
1452	STA.	2018+06	2025+32	(NO PASSING LT)
363	STA.	2018+06	2025+32	(SKIP DASH RT)
2256	LT&RT	2020+46	2026+10	(EDGE LINE)
70	STA.	2025+32	2026+72	(SKIP DASH)
652	STA.	2026+72	2028+35	(NO PASSING RT)
163	STA.	2026+72	2028+35	(SKIP DASH LT)
4956	TOTAL			

**78200410 GUARDRAIL MARKERS, TYPE A**

EACH	LOCATION			
	US 20			
4	RT	2020+14	2022+14	
4	LT	2020+63	2022+26	
4	RT	2024+33	2025+96	
7	LT	2024+45	2028+58	
19	TOTAL			

**78201000 TERMINAL MARKER - DIRECT APPLIED**

EACH	LOCATION			
	US 20			
1	RT	2019+64		
1	LT	2020+13		
1	RT	2026+46		
1	LT	2029+08		
4	TOTAL			

**78300500 PAINT PAVEMENT MARKING REMOVAL**

SQ FT	LOCATION			
	US 20			
303	STA.	2018+06	2025+32	(CENTER LINE)
12	STA.	2025+32	2026+72	(CENTER LINE)
69	STA.	2026+72	2028+35	(CENTER LINE)
72	LT	2020+46	2022+60	(EDGE LINE)
188	RT	2020+46	2026+10	(EDGE LINE)
68	LT	2024+07	2026+10	(EDGE LINE)
712	TOTAL			

**X0712400 TEMPORARY PAVEMENT**

SQ YD	LOCATION			
	US 20			
130	RT	2019+31	2022+48	(FROM CROSS SECTIONS)
71	LT	2020+00	2022+60	(FROM CROSS SECTIONS)
95	RT	2024+00	2026+59	(FROM CROSS SECTIONS)
187	LT	2024+12	2029+40	(FROM CROSS SECTIONS)
483	TOTAL			

**X4066424 BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX 'D', N50**

TON	LOCATION			
	US 20			
11	RT	2019+31	2021+76	(FROM CROSS SECTIONS)
8	LT	2020+08	2021+74	(FROM CROSS SECTIONS)
1	LT	2022+21	2022+30	(FROM CROSS SECTIONS)
1	RT	2022+23	2022+30	(FROM CROSS SECTIONS)
11	LT&RT	2022+30	2022+62	(FROM CROSS SECTIONS)
11	LT&RT	2023+97	2024+29	(FROM CROSS SECTIONS)
1	RT	2024+29	2024+36	(FROM CROSS SECTIONS)
1	LT	2024+29	2024+37	(FROM CROSS SECTIONS)
54	RT	2024+71	2026+43	(FROM CROSS SECTIONS)
11	LT	2024+78	2027+57	(FROM CROSS SECTIONS)
3	LT	2028+09	2029+40	(FROM CROSS SECTIONS)
113	TOTAL			

**Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3**

EACH	LOCATION			
	US 20			
1	RT	2021+30		(STAGE 1A)
1	RT	2025+26		(STAGE 1A)
2	TOTAL			

**Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3**

EACH	LOCATION			
	US 20			
1	LT	2020+46		(STAGE 1)
1	LT	2026+10		(STAGE 1)
1	RT	2020+46		(STAGE 2)
1	RT	2026+10		(STAGE 2)
4	TOTAL			

PLOT DATE = Mon, Dec 12 09:33:53 2005  
 FILE NAME = c:\pvc\jstest\p200205\002025v.dgn  
 PLOT SCALE = 50.0000 / IN.  
 USER NAME = megillj

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_