

EARTH WORK SCHEDULE

CONTRACT NO. 64A48				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	24BR-1	JO DAVIESS	50	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

EARTH WORK SCHEDULE				
LOCATION	EARTH EXC (CUT)	EARTH EXC ADJ SHRINK 25%	EMBANK (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
2019+31 - 2022+60	120	90	209	-120
2024+00 - 2029+ 40	179	134	135	-1
TOTAL	299	224	344	-121

PLOT DATE = Mon, Dec 12 09:33:53 2005  
FILE NAME = c:\projects\p200205\c00205.rvt  
PLOT SCALE = 50.0000' / IN.  
USER NAME = mg111

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT. DATE		DRAWN BY CHECKED BY