

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(37-3-DHL-1)	HENRY	10	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

90% FED 10% STATE  
URBAN  
Y030-1E

PAY ITEM	ENGLISH DESCRIPTION	UNIT	TOTALS
<del>X8300180</del>	LIGHT POLE, ALUMINUM, 45' MH, 15' DAVIT ARM, TWIN	EACH	2
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
	<b>ELECTRIC</b>		
80400105	SERVICE INSTALLATION, SPECIAL	EACH	1
81020500	CONDUIT PUSHED, 2" DIA INTERMEDIATE METAL	FOOT	458
81020700	CONDUIT PUSHED, 3" DIA INTERMEDIATE METAL	FOOT	51
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	96
<b>81300835</b>	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18"X18"X10"	EACH	1
81500200	TRENCH & BACKFILL FOR ELECTRICAL WORK	FOOT	2,368
81600315	UNIT DUCT, 2 *6 XLP, 1 *6 XLP GROUND 1" POLYETHYLENE	FOOT	2,935
82102250	LUMINARIES, SODIUM VAPOR, HORIZONTAL MOUNT 250 WATT	EACH	<b>18</b>
82107100	UNDERPASS LUMINAIRE, 70 WATT HPS	EACH	4
82500540	LIGHTING CONTROLLER CB - RCS - 100 - 480	EACH	1
83003600	LIGHT POLE, ALUMINUM, 45' MH, 15' DAVIT ARM	EACH	<b>14</b>
83600355	LIGHT POLE FOUNDATION, METAL, 15" B.C., 8" x 6'	EACH	<b>14</b>
<b>83600357</b>	LIGHT POLE FOUNDATION, METAL, 15" B.C., 8" x 8'	EACH	2
⊙ 83800650	BREAKAWAY DEVICE, COUPLING, STAINLESS STEEL SCREEN	EACH	<del>64</del>
87900200	DRILL EXISTING HANDHOLE	EACH	6
89502380	REMOVE EXISTING HANDHOLE	EACH	2
X0321478	MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE	L SUM	1
X0323437	CONDUIT, FLEXIBLE METALLIC, WEATHERPROOF 2"	EACH	1
X7010800	TRAFFIC CONTROL AND PROTECTION, STANDARD 702001, SPECIAL	L SUM	1
XX220000	REMOVE EXISTING LIGHTING SYSTEM	EACH	1

⊙ SFTY-3C

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY

PLOT DATE = Wed Dec 21 13:45:33 2005  
FILE NAME = P:\Projects\052-985-05\plan sheets 64b23.dgn  
PLOT SCALE = 30.0000 / IN.  
USER NAME = INTX