

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
627	1BR	LASALLE	69	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE:	
				I000-2A ROADWAY	X081-2A BRIDGE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1015	1015	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	519	519	
20101000	TEMPORARY FENCE	FOOT	315	315	
20200100	EARTH EXCAVATION	CU YD	1290	1290	
20400800	FURNISHED EXCAVATION	CU YD	27531	27531	
20700400	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	260		260
* 25000310	SEEDING, CLASS 4	ACRE	1.6	1.6	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	144	144	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	144	144	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	144	144	
* 25100115	MULCH, METHOD 2	ACRE	1.6	1.6	
* 25100630	EROSION CONTROL BLANKET	SQ YD	700	700	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	320	320	
28000300	TEMPORARY DITCH CHECKS	EACH	12	12	
28000400	PERIMETER EROSION BARRIER	FOOT	1070	1070	
28100109	STONE RIPRAP, CLASS A5	SQ YD	2030		2030
28200200	FILTER FABRIC	SQ YD	2030		2030
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	633	633	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	181	181	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	388	388	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	603	603	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	37	37	
44000100	PAVEMENT REMOVAL	SQ YD	204	204	
44000400	GUTTER REMOVAL	FOOT	475	475	
44004000	PAVED DITCH REMOVAL	FOOT	75	75	
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	539	539	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	22	22	
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	50	50	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50104400	CONCRETE HEADWALL REMOVAL	EACH	5	5	
50200100	STRUCTURE EXCAVATION	CU YD	90		90
50200300	COFFERDAM EXCAVATION	CU YD	138		138
50202901	COFFERDAM (LOCATION 1)	EACH	1		1
50202902	COFFERDAM (LOCATION 2)	EACH	1		1
50300100	FLOOR DRAINS	EACH	6		6
50300225	CONCRETE STRUCTURES	CU YD	260.2		260.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	459.9		459.9
50300260	BRIDGE DECK GROOVING	SQ YD	1182.2		1182.2
50300265	SEAL COAT CONCRETE	CU YD	104		104

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DATE _____ DRAWN BY _____
CHECKED BY _____

PLOT DATE = 11/2/2005
 PLOT SCALE = AS SHOWN
 USER NAME = JLSB88