

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
627	1BR	LASALLE	69	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES				80% FED F	20% STATE	80% FED BR	20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE:			
				I000-2A ROADWAY	X081-2A BRIDGE		
50300300	PROTECTIVE COAT	SQ YD	1692			1692	
50400745	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 72"	FOOT	2118			2118	
50800105	REINFORCEMENT BARS	POUND	53490			53490	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	155,030			155,030	
51201700	FURNISHING STEEL PILES HP12X74	FOOT	774			774	
51202700	DRIVING STEEL PILES	FOOT	774			774	
51203700	TEST PILE STEEL HP12X74	EACH	2			2	
51500100	NAME PLATES	EACH	1			1	
55100500	STORM SEWER REMOVAL 12"	FOOT	386	386			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	99.5			99.5	
60500050	REMOVING CATCH BASINS	EACH	5	5			
60609580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	156			156	
60616110	PAVED DITCH, TYPE A-30	FOOT	75	75			
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	675	675			
* 63000130	STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)	FOOT	35.3	35.3			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1	1			
63200310	GUARDRAIL REMOVAL	FOOT	408	408			
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1			
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8			
67100100	MOBILIZATION	L SUM	1	0.2		0.8	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3980	3980			
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	900	900			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	14	14			
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	5	5			
78200405	GUARDRAIL MARKERS	EACH	16	16			
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10			
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	6			6	
X3550700	BITUMINOUS BASE COURSE SUPERPAVE 10"	SO YD	584	584			
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	217	217			
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	130	130			
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	30	30			
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1			
Z0002600	BAR SPLICERS	EACH	400			400	
* Z0008254	DRILLED SHAFT IN SOIL 54"	FOOT	282.9			282.9	
* Z0008348	DRILLED SHAFT IN ROCK 48"	FOOT	180			180	
Z0065100	SETTLEMENT PLATFORMS	EACH	2	2			

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY