

SUMMARY OF QUANTITIES

URBAN
80% FEDERAL
20% STATE
0% CITY

ROADWAY X020-2A EAST FORK
NETTLE CR.
PR. 032-0108
EX. 032-0081

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5952	C-BR-1	GRUNDY	50	6
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

CODE NO	ITEM	UNIT	TOTAL QUANTITY	X020-2A	X020-2A
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	6887	6887	
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	39	39	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	130	130	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	130	130	
* 70500690	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 11	EACH	4	4	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3378	3378	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	447	447	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	569	569	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	364	364	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	189	189	
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	16	16	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	814	814	
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	83	83	
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	222	222	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	35	35	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10	10	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	982	982	
81012200	CONDUIT IN TRENCH, 3/4" DIA., PVC	FOOT	21	21	
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	183	183	
81400400	CONCRETE HANDHOLE	EACH	1	1	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	198	198	
84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	1	1	
84200700	LIGHTING FOUNDATION REMOVAL	EACH	1	1	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	2	
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	195	195	
87900200	DRILL EXISTING HANDHOLE	EACH	3	3	
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	116	116	
* 89502200	MODIFY EXISTING CONTROLLER	EACH	2	2	
X0325200	RELOCATE INTERCONNECT CABLE	FOOT	606	606	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	13	13	
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	18	18	
550A0420	STORM SEWERS, CLASS A, TYPE 2 27"	FOOT	195	195	
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	214	214	

* SPECIALTY ITEMS
REVISED
 2-27-06
 ADDENDUM 1

BOWMAN, BARRETT & ASSOCIATES INC.
 CONSULTING ENGINEERS
 130 E. RANDOLPH STREET
 CHICAGO, ILLINOIS 60601
 JOB NO. 541



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 6
 SUMMARY OF QUANTITIES

SCALE: VERT. NTS
 HORIZ. NTS
 DATE 10/25/05

DRAWN BY RGR
 CHECKED BY DDM

m:\541\road\civil\66563 East Fork\541cage01.fg.dgn 1/27/2005 3:38:05 PM