

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5952	G-BR-1	GRUNDY	50	4
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

URBAN
80% FEDERAL
20% STATE
0% CITY

ROADWAY

EAST FORK
NETTLE CR.
PR. 032-0108
EX. 032-0081

CODE NO	ITEM	UNIT	TOTAL QUANTITY	X020-2A	X020-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	21	21	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	36	36	
20200100	EARTH EXCAVATION	CU YD	382	382	
20300100	CHANNEL EXCAVATION	CU YD	154	154	
20400800	FURNISHED EXCAVATION	CU YD	62	62	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	952	952	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	705	705	
25000210	SEEDING, CLASS 2A	ACRE	0.2	0.2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18	1830
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18	
25100115	MULCH, METHOD 2	ACRE	0.35	0.35	
25100630	EROSION CONTROL BLANKET	SQ YD	705	705	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	35	35	
28000400	PERIMETER EROSION BARRIER	FOOT	1178	1178	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
28100107	STONE RIPRAP, CLASS A4	SQ YD	760		760
28200200	FILTER FABRIC	SQ YD	760		760
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	560	560	
40600300	AGGREGATE (PRIME COAT)	TON	4.3	4.3	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	550	550	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	51	51	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	477	477	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1494	1494	
42400420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SQ FT	494	494	
44000009	BITUMINOUS SURFACE REMOVAL 3"	SQ YD	1591	1591	
44000100	PAVEMENT REMOVAL	SQ YD	347	347	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	360	360	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	972	972	
44000600	SIDEWALK REMOVAL	SQ FT	1901	1901	
44000700	APPROACH SLAB REMOVAL	SQ YD	125	125	
44004000	PAVED DITCH REMOVAL	FOOT	19	19	
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	401	401	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	38	38	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		U.S. ROUTE 6 SUMMARY OF QUANTITIES
SCALE: VERT. NTS	DRAWN BY RGR	CHECKED BY DDM
HORIZ. NTS	DATE 10/25/05	

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
130 E. RANDOLPH STREET
CHICAGO, ILLINOIS 60601
JOB NO. 541

