

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	105 BR-1	LIVINGSTON	45	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

20200500 EARTH EXCAVATION (WIDENING)

CU YD	LOCATION
21	584 + 60, RT. - 586 + 16.50, RT.
28	587 + 07.50, RT. - 589 + 00, RT.
49	TOTAL

63304805 TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 6

EACH	LOCATION
1	586 + 16.50, RT.
1	586 + 16.50, LT.
1	587 + 07.50, RT.
1	587 + 07.50, LT.
4	TOTAL

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
810	582 + 70 - 590 + 80 - LT. EDGELINE - WHITE
810	582 + 70 - 590 + 80 - RT. EDGELINE - WHITE
1620	TOTAL

35600400 BITUMINOUS CONCRETE BASE COURSE WIDENING 10 INCHES

SQ YD	LOCATION
122	584 + 60, RT. - 586 + 16.50, RT.
150	587 + 07.50, RT. - 589 + 00, RT.
272	TOTAL

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION
50	584 + 50 - 589 + 00, LT. WHITE
50	584 + 50 - 589 + 00, CENTERLINE YELLOW
50	584 + 50 - 589 + 00, RT. WHITE
150	TOTAL

78001130 PAINT PAVEMENT MARKING - LINE 6"

FOOT	LOCATION
210	582 + 70 - 590 + 80 - CENTERLINE
210	TOTAL

40600100 BITUMINOUS MATERIALS (PRIME COAT)

GALLON	LOCATION
25	585 + 66.50 - 586 + 16.50
25	587 + 07.50 - 587 + 57.50
50	TOTAL

70300220 TEMPORARY PAVEMENT MARKING - LINE 4" (TP)

FOOT	LOCATION
1620	582 + 70 - 590 + 80 - EDGE - YELLOW - STAGE 1 LT. & RT.
1620	582 + 70 - 590 + 80 - EDGE - YELLOW - STAGE 1 LT. & RT.
1620	582 + 70 - 590 + 80 - EDGE - WHITE
4860	TOTAL

78100100 RAISED REFLECTIVE PAVEMENT MARKERS

EACH	LOCATION
4	582 + 70 - 586 + 16.50
3	587 + 07.50 - 590 + 80
7	TOTAL

40600300 AGGREGATE (PRIME COAT)

TON	LOCATION
0.1	585 + 66.50 - 586 + 16.50
0.1	587 + 07.50 - 587 + 57.50
0.2	TOTAL

70400240 TEMPORARY PAVEMENT MARKING - LINE 6"

FOOT	LOCATION
210	582 + 70 - 590 + 00 - CENTERLINE
210	TOTAL

78100105 RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE)

EACH	LOCATION
1	586 + 16.50 - 587 + 07.50
1	TOTAL

40600990 TEMPORARY RAMP

SQ YD	LOCATION
37	585 + 66.50 SURFACE REMOVAL
30	585 + 66.50 BRIDGE APPROACH - STAGE 1
47	587 + 57.50 BRIDGE APPROACH - STAGE 2
37	587 + 57.50 SURFACE REMOVAL
151	TOTAL

70300280 TEMPORARY PAVEMENT MARKING - LINE 24" (TP)

FOOT	LOCATION
13	582 + 70 - STAGE 1 - RT.
13	590 + 80 - STAGE 1 - LT.
13	582 + 70 - STAGE 2 - RT.
13	590 + 80 - STAGE 2 - LT.
52	TOTAL

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION
2	586 + 16.50, RT. - TERMINAL, TYPE 6A
2	586 + 16.50, LT. - TERMINAL, TYPE 6A
2	587 + 07.50, RT. - TERMINAL, TYPE 6A
2	587 + 07.50, LT. - TERMINAL, TYPE 6A
8	TOTAL

44000030 BITUMINOUS SURFACE REMOVAL - (VARIABLE DEPTH)

SQ YD	LOCATION
245	585 + 66.50 - 586 + 16.50
245	587 + 07.50 - 587 + 57.50
490	TOTAL

70301000 WORKZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
283	582 + 70 - 590 + 80 - STAGE 1 - RT.
283	582 + 70 - 590 + 80 - STAGE 1 - LT.
283	582 + 70 - 590 + 80 - STAGE 2 - RT.
283	582 + 70 - 590 + 80 - STAGE 2 - LT.
1132	TOTAL

78300100 PAVEMENT MARKING REMOVAL

EACH	LOCATION
70	582 + 70 - 590 + 80, CENTERLINE
540	582 + 70 - 590 + 80, RT. & LT.
610	TOTAL

48101200 AGGREGATE SHOULDERS, TYPE B

TON	LOCATION
12	584 + 60.00 - 586 + 16.50
14	587 + 07.50 - 589 + 00.00
26	TOTAL

70400100 TEMPORARY CONCRETE BARRIER

TON	LOCATION
450	584 + 50 - 589 + 00 - STAGE 1
450	TOTAL

78300200 RAISED REFLECTIVE PAVEMENT MARKERS (REMOVAL)

EACH	LOCATION
8	582 + 70 - 590 + 80
8	TOTAL

63100087 TRAFFIC BARRIER TERMINAL, TYPE 6A

EACH	LOCATION
1	586 + 16.50, RT.
1	586 + 16.50, LT.
1	587 + 07.50, RT.
1	587 + 07.50, LT.
4	TOTAL

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

TON	LOCATION
450	584 + 50 - 589 + 00 - STAGE 2
450	TOTAL

X4066414 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50

TON	LOCATION
21	585 + 66.50 - 586 + 16.50 - MAINLINE
21	587 + 07.50 - 587 + 57.50 - MAINLINE
42	TOTAL

X4066765 LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N70

TON	LOCATION
11	585 + 66.50 - 586 + 16.50 - MAINLINE
11	587 + 07.50 - 587 + 57.50 - MAINLINE
22	TOTAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 68 (IL RTE. 23)
SECTION 105 BR-1
LIVINGSTON COUNTY

SCALE: VERT. _____
HORIZ. _____

DATE: _____

DRAWN BY: BISHOP
CHECKED BY: BOTT

GREENE & BRADFORD, INC.
OF SPRINGFIELD

REGISTERED PROFESSIONAL ENGINEER
NO. 001234567
ILLINOIS LICENSE NO. 001234567
PROFESSIONAL DESIGN FIRM NO. 001234567
PROFESSIONAL & STRUCTURAL ENGINEERING CORPORATION
301 755 8844, 301 755 8077, P.O. BOX 1111, SPRINGFIELD, ILLINOIS 62763-1111

COMPUTER FILE NO.
03236_W01L.SQ

PROJECT 03236 W01L
12/19/05 - MML

PLT DATE = 12/21/2005
FILE NAME = J:\03236\W01L\DRAWINGS\03236_W01L.SQ.dgn
SCALE = 1/8" = 1'-0"
PLOT SCALE = 1/8" = 1'-0"
OPERATOR = mschell