

F.A.U. RTE.	SECTION	COUNTIES	TOTAL SHEETS	SHEET NO.
6088	17N	*	18	4
STA.		TO STA.		
FED. ROAD DIST. NO. _ ILLINOIS		FED. AID PROJECT		

* LASALLE & BUREAU

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION CODE TYPE:		I000-1A 90% FED 10% STATE ROADWAY	Y031-1F 90% FED 10% STATE SIGNALS
		UNIT	TOTAL QUANTITY		
78300400	THERMOPLASTIC PAVEMENT MARKING REMOVAL	SQ FT	2756	2756	
* 81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	563		563
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	200		200
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	25		25
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	32		32
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	32		32
* 81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	113		113
* 81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	107		107
81306500	REMOVE EXISTING JUNCTION BOX	EACH	2		2
* 81400400	CONCRETE HANDHOLE	EACH	4		4
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	525		525
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	963		963
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1286		1286
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1318		1318
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3737		3737
87501200	TRAFFIC SIGNAL POST, 16 FT.	EACH	1		1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3		3
87900200	DRILL EXISTING HANDHOLE	EACH	24		24
* 88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	12		12
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	11		11
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1500		1500
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	5623		5623
89502380	REMOVE EXISTING HANDHOLE	EACH	2		2
X3560146	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 10 3/4 INCH	SQ YD	172	172	
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	197	197	
X4066740	LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON	1	1	
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1
* X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	5		5
* X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3		3
* X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	3		3
X0962500	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1		1
86200300	UNINTERRUPTIBLE POWER SUPPLY (UPS EXTENDED)	EACH	1		1

* SPECIALTY ITEMS