

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	136 BR-1	IROQUOIS	45	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

20200500 EARTH EXCAVATION (WIDENING)

CU_YD	LOCATION
10.9	STA. 615+50, RT. TO STA. 616+38, RT.
8.5	STA. 617+31, RT. TO STA. 618+00, RT.
8.1	STA. 615+50, LT. TO STA. 616+38, LT.
6.4	STA. 617+31, LT. TO STA. 618+00, LT.
33.9	TOTAL

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

EACH	LOCATION
1	STA. 615+56.75, LT. TO STA. 616+06.75, LT.
1	STA. 617+80, LT. TO STA. 618+30, LT.
1	STA. 619+77, RT. TO STA. 620+27, RT.
3	TOTAL

78001130 PAINT PAVEMENT MARKING - LINE 6"

FOOT	LOCATION
180	STATION 613+34.5 TO STATION 620+40.5, CENTERLINE - YELLOW
180	TOTAL

38100107 STONE RIPRAP, CLASS A4

SQ_YD	LOCATION
226	STA. 615+50, 21' RT. - 37' RT. TO STA. 616+57, 21' RT. - 37' RT.
226	TOTAL

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION
130	STA. 615+06.75, RT. TO STA. 616+37, RT.
80	STA. 615+56.75, LT. TO STA. 616+37, LT.
31	STA. 617+31, RT. TO STA. 617+62.25, RT.
99	STA. 617+31, LT. TO STA. 618+30, LT.
50	STA. 619+77, RT. TO STA. 620+27, RT.
390	TOTAL

78100100 RAISED REFLECTIVE PAVEMENT MARKERS

EACH	LOCATION
4	STATION 615+12.5 TO STATION 618+00
4	TOTAL

28200100 FILTER FABRIC FOR USE WITH RIPRAP

SQ_YD	LOCATION
226	STA. 615+50, 21' RT. - 37' RT. TO STA. 616+57, 21' RT. - 37' RT.
226	TOTAL

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION
70	STA. 613+34.5 TO STA. 620+40.5, RT. WHITE
70	STA. 613+34.5 TO STA. 620+40.5, CENTERLINE YELLOW
70	STA. 613+34.5 TO STA. 620+40.5, LT. WHITE
210	TOTAL

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION
4	STA. 615+05, RT. TO STA. 617+63, RT.
3	STA. 615+80, LT. TO STA. 617+63, LT.
7	TOTAL

35600400 BITUMINOUS CONCRETE BASE COURSE WIDENING 10 INCHES

SQ_YD	LOCATION
38.7	STA. 615+50, RT. TO STA. 616+38, RT.
30.6	STA. 617+31, RT. TO STA. 618+00, RT.
29.3	STA. 615+50, LT. TO STA. 616+38, LT.
23.0	STA. 617+31, LT. TO STA. 618+00, LT.
121.6	TOTAL

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
1412	STA. 613+34.5 TO STA. 620+40.5, EDGELINE-WHITE STAGE 1 - RT. & LT.
1412	STA. 613+34.5 TO STA. 620+40.5, EDGELINE-WHITE STAGE 2 - RT. & LT.
1412	STA. 613+34.5 TO STA. 620+40.5, RT. & LT. WHITE
4236	TOTAL

78300100 PAVEMENT MARKING REMOVAL

SQ_FT	LOCATION
236	STA. 613+34.5 TO STA. 620+40.5, RT. EDGELINE- WHITE
236	STA. 613+34.5 TO STA. 620+40.5, LT. EDGELINE- WHITE
60	STA. 613+34.5 TO STA. 620+40.5, CENTERLINE. YELLOW
532	TOTAL

40600100 BITUMINOUS MATERIALS (PRIME COAT)

GALLON	LOCATION
30	STA. 615+77.02 TO STA. 616+58.10
30	STA. 617+09.90 TO STA. 617+91.90
60	TOTAL

70300240 TEMPORARY PAVEMENT MARKING - LINE 6"

SQ_YD	LOCATION
180	STA. 613+34.5 TO STA. 620+40.5, CENTERLINE - YELLOW
180	TOTAL

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION
4	STATION 615+12.5 TO STATION 618+00
4	TOTAL

40600990 TEMPORARY RAMP

SQ_YD	LOCATION
28.3	STA. 615+77.02 TO STA. 615+97.02
29	STA. 617+71.90 TO STA. 617+91.90
24	STAGE 1
34	STAGE 2
113	TOTAL

70300280 TEMPORARY PAVEMENT MARKING-LINE 24"

FOOT	LOCATION
12	STA. 613+34.5 - WHITE STAGE 1 - RT.
12	STA. 620+40.5 - WHITE STAGE 1 - LT.
12	STA. 613+34.5 - WHITE STAGE 2 - RT.
12	STA. 620+40.5 - WHITE STAGE 2 - LT.
48	TOTAL

X4066414 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50

TON	LOCATION
25	STA. 615+77.02 TO STA. 616+58.10
25	STA. 617+09.90 TO STA. 617+91.90
50	TOTAL

44000030 BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)

SQ_YD	LOCATION
297	STA. 615+77.02 TO STA. 616+58.10
301	STA. 617+09.90 TO STA. 617+91.90
598	TOTAL

70301000 WORKZONE PAVEMENT MARKING REMOVAL

SQ_FT	LOCATION
471	STA. 613+34.5 TO STA. 620+40.5, EDGELINE-WHITE STAGE 1 - RT.
471	STA. 613+34.5 TO STA. 620+40.5, EDGELINE-WHITE STAGE 1 - LT.
471	STA. 613+34.5 TO STA. 620+40.5, EDGELINE-WHITE STAGE 2 - RT.
60	STA. 613+34.5 TO STA. 620+40.5, EDGELINE-WHITE STAGE 2 - LT.
1473	TOTAL

X4066765 LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50

TON	LOCATION
13	STA. 615+77.02 TO STA. 616+58.10
13	STA. 617+09.90 TO STA. 617+91.90
26	TOTAL

48101200 AGGREGATE SHOULDERS, TYPE B

TON	LOCATION
7	STA. 615+05, RT. TO STA. 615+50, RT.
7	TOTAL

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
350	STATION 615+12.5 TO STATION 618+62.5
350	TOTAL

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

TON	LOCATION
1	STA. 614+94.5 TO STA. 615+12.5 - STAGE 1
1	STA. 618+00 TO STA. 618+18 - STAGE 1
2	TOTAL

63000000 STEEL PLATE BEAM GUARD RAIL, TYPE A

FOOT	LOCATION
100	STA. 615+06.75, RT. TO STA. 616+06.75, RT.
18	STA. 617+62.25, LT. TO STA. 617+80, LT.
118	TOTAL

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
350	STATION 615+12.5 TO STATION 618+62.5
350	TOTAL

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

TON	LOCATION
1	STA. 614+94.5 TO STA. 615+12.5 - STAGE 1
1	STA. 618+00 TO STA. 618+18 - STAGE 1
2	TOTAL

63100087 TRAFFIC BARRIER TERMINAL, TYPE 6A

EACH	LOCATION
1	STA. 616+06.75, RT. TO STA. 616+38, RT.
1	STA. 616+06.75, LT. TO STA. 616+38, LT.
1	STA. 617+31, RT. TO STA. 617+62.25, RT.
1	STA. 617+31, LT. TO STA. 617+62.25, LT.
4	TOTAL

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
706	STA. 613+34.5 TO STA. 620+40.5, RT. EDGELINE - WHITE
706	STA. 613+34.5 TO STA. 620+40.5, LT. EDGELINE - WHITE
1412	TOTAL

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

TON	LOCATION
1	STA. 614+94.5 TO STA. 615+12.5 - STAGE 1
1	STA. 618+00 TO STA. 618+18 - STAGE 1
2	TOTAL

PLOT DATE = 12/22/2005
 FILE NAME = J:\0326\4012\IRAMINUS\SCH002.dgn
 PLOT DATE = 12/22/2005
 PLOT TIME = 10:00:00 AM
 OPERATOR = michelle

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAS 840 (IL RTE 49)
 OVER SHAVETAIL CREEK
 SEC. 136 BR-1
 IROQUOIS COUNTY

SCALE: VERT. _____
 HORIZ. _____

DATE: 10/21/05

DRAWN BY: SUT
 CHECKED BY: B

GREENE & BRADFORD, INC.
 OF SPRINGFIELD
 CONSULTING ENGINEERS
 100 WESTLARK DRIVE
 SPRINGFIELD, ILLINOIS 62761-1803
 PROFESSIONAL ENGINEERS REG. NO. 001-000000
 PHONE: 217-223-8844 FAX: 217-223-8844
 WWW: WWW.GREENE-AND-BRADFORD.COM

COMPUTER
 SC
 PROJ