

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	.	VERMILION	9	7

• D-5 CONTRACT MAINT 2006-2
CONTRACT NO. 70535

SCHEDULE OF QUANTITIES

CLASS B PATCHES

STATION	TO STATION	DIRECTION	LANE	LENGTH (FOOT)	WIDTH (FOOT)	DEPTH (INCH)	TYPE IV (SQ. YD)	SAW CUTS (FOOT)	TIE BARS (EACH)	DOWEL BARS (EACH)	PAVEMENT FABRIC (SQ. YD.)
1158+92	1161+60	WB	DL	268.00	12.00	10	358	572	119	70	358
** 1158+61	1158+87	WB	PL	26.00	12.00	VAR.	35	64	12	10	35
1158+87	1161+03	WB	PL	216.00	12.00	10	288	456	96	50	288
1239+88	1242+32	WB	DL	244.00	12.00	10	326	500	97	70	326
** 1242+32	1242+48	WB	DL	16.00	12.00	VAR.	22	56	18	0	22
1240+18	1242+20	WB	PL	202.00	12.00	10	270	416	80	60	270
** 1242+20	1242+48	WB	PL	28.00	12.00	VAR.	38	80	23	0	38
** 1318+98	1319+70	WB	DL	72.00	12.00	VAR.	96	156	30	20	96
1319+70	1321+70	WB	DL	200.00	12.00	10	267	400	78	50	267
** 1321+70	1322+08	WB	DL	38.00	12.00	VAR.	51	100	27	10	51
** 1318+98	1319+72	WB	PL	74.00	12.00	VAR.	99	160	31	20	99
1319+72	1321+70	WB	PL	198.00	12.00	10	264	420	89	50	264
TOTAL:							2114	3380	700	410	2114

** PAID FOR AS CLASS B PATCHES, TYPE IV

TOTAL VAR.: 341
TOTAL 10": 1773

PAINT PAVEMENT MARKING - LINE 4"

STATION	TO STATION	DIRECTION	LANE	LENGTH (FEET)	WHITE EDGE (FEET)	WHITE SKIP DASH (FEET)	YELLOW EDGE (FEET)	TOTAL (FEET)
1158+98.00	1161+60.00	WB	DL	268	268	70	0	338
1158+61.00	1161+03.00	WB	PL	242	0	0	242	242
1239+88.00	1242+48.00	WB	DL	260	260	70	0	330
1240+18.00	1242+48.00	WB	PL	230	0	0	230	230
1318+98.00	1322+08.00	WB	DL	310	310	80	0	390
1318+98.00	1321+70.00	WB	PL	272	0	0	272	272

WHITE LINE TOTAL: 1058
YELLOW LINE TOTAL: 744

TOTAL 4" LINE: 1802

RAISED REFLECTIVE PAVEMENT MARKER

STATION	TO STATION	LENGTH (FEET)	ONE WAY CRYSTAL (EACH)	NO. OF MARKER TIMES	TOTAL MARKERS (EACH)
1158+61.00	1161+60.00	299	5	2	10
1239+88.00	1242+48.00	260	5	2	10
1318+98.00	1322+08.00	310	5	2	10

TOTAL: 30