

CABLE GUARD M	OUANTITI		
LOCATION	(EACH)		
LOCATION A			
STA 259+84	τo	STA 288+00	72
STA 292+00	TO	STA 340+30	124
STA 340+39	TO	STA 341+96	4
STA 348+90	TO	STA 366+35	45
STA 367+40	то	STA 381+20	35
LOCATION B			
STA 14+15	TO	STA 0+00	36
STA 167+20	TO	STA 252+09	218
STA 301+50	TO	STA 317+82	42
STA 321+67	TO	STA 363+60	108
STA 364+60	τo	STA 369+27	12
STA 211+42	то	STA 225+50	36
			732

			CC	NTRACT	NO. 72	<b>A10</b>
F.A.I. RTE	SECTION		C	OUNTY	TOTAL SHEETS	SHEET NO,
.55_	<b>:</b>		_SANGAWON_		_20_	_20A
STA TO STA						
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT						

NOTES:

MATERIAL: THE MATERIAL SHALL BE IN ACCORDANCE WITH SECTION 1090 AND 1091 OF THE STANDARD SPECIFICATIONS.

CONSTRUCTION REQUIREMENTS: THE REFLECTIVE SHEETING SHALL BE INSTALLED DIRECTLY ON THE CABLE POSTS. THE REFLECTIVE SHEETING SHALL BE INSTALLED AS SHOWN IN THE PLANS, ON EVERY 6TH POST. THE SURFACE OF THE POST SHALL BE CLEANED OF ALL CONTAMINANTS PRIOR TO THE INSTALLATION OF THE REFLECTIVE SHEETING. THE SURFACE SHALL BE CLEANED USING A 5-8 PERCENT PHOSPHORIC ACID SOLUTION AND RINSED WITH CLEAN WATER OR AS RECOMMENDED BY THE MANUFACTURER OF THE REFLECTIVE SHEETING AND AS APPROVED BY THE ENGINEER.

BASIS OF PAYMENT: THIS WORK WILL BE PAID FOR AT THE Contract unit price each for Cable Guard Warker.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATIO					
NAME	DATE	ILLINGIS DECANIMENT OF TRANSPORTATION					
		CABLE GUARD MARKER DETAIL					
		FAI 55 (1-55)					
		SECTION D-6 CABLE MED BAR ■1 SANGAMON COUNTY					
		SCALES VERT	DRAWN BY				
		HORIZ	UTAWN BT				
		DATE	CHECKED BY				