

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	100% STATE - <i>SFTY-2A</i>
			QUANTITY
50102400	CONCRETE REMOVAL	CU YD	0.5
50300300	PROTECTIVE COAT	SQ YD	26
50301200	CONCRETE WEARING SURFACE	SQ YD	26
50400405	<i>PRECAST, PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)</i>	SQ FT	195
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	590
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	1800
70400100	TEMPORARY CONCRETE BARRIER	FOOT	380
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	2925
78300105	PAVEMENT MARKING REMOVAL	FOOT	2025
X0320047	REMOVAL OF EXISTING PPC DECK BEAMS	SQ FT	198
X0321781	MECHANICAL SPLICE	EACH	76
X0322752	WORK ZONE PAVEMENT MARKING REMOVAL	FOOT	1800
X7200201	WIDTH RESTRICTION SIGN	L SUM	1
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	2
Δ Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2

* SPECIALTY ITEMS
 Δ SFTY-3N

SUMMARY OF QUANTITIES
 FAP 713 (IL 101)
 SECTION (120BR)I-1
 SCHUYLER COUNTY