

FAU. RT.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2955	02-00048-00-PV	COOK	45	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

Contract 83819

SUMMARY OF QUANTITIES					PAVEMENT	SIDEWALKS	MARKINGS	SIGNS	LANDSCAPE	SIGNALS	TRAINING		
S.P.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE								
					1000	SFTY-1B	SFTY-1D	Y002-1C	Y003	Y031	Y080		
△	*	56200200	WATER SERVICE LINE 3/4"	FOOT	1020	1020							
△	*	56201100	WATER SERVICE LINE 3"	FOOT	80	80							
		60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2							
		60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	3	3							
		60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1	1							
		60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	14	14							
		60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	5	5							
		60207905	CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE	EACH	1	1							
		60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	5	5							
		60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3							
		60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1							
		60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1							
		60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5							
		60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	4	4							
		60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3	3							
		60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1							
	*	60224600	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1							
	*	60225400	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3							
	*	60225924	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1							
		60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	2	2							
		60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4	4							
		60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	8	8							
	*	60248700	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2							
	*	60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2							
		60255500	MANHOLES TO BE ADJUSTED	EACH	1	1							
		60265700	VALVE VAULTS TO BE ADJUSTED	EACH	4	4							
		60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1							
	*	60266910	VALVE BOXES TO BE REMOVED	EACH	1	1							
		60500040	REMOVING MANHOLES	EACH	3	3							
		60500050	REMOVING CATCH BASINS	EACH	10	10							
		60500205	FILLING CATCH BASINS	EACH	2	2							
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	458	458							
		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4852	4852							
		60618800	CONCRETE MEDIAN, TYPE SB	SQ FT	1055	1055							
		63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	19	19							
	*	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1							
		72000100	SIGN PANEL - TYPE 1	SQ FT	16.5			16.5					
		72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	12			12					
		72900100	METAL POST - TYPE A	FOOT	38			38					
		73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	1			1					
△		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	40			40					
△		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2626			2626					
△		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	157			157					
△		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	300			300					
△		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	211			211					
△	*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	72					72			
	*	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	3436	3436							
	*	XX000479	WATER MAIN REMOVAL 6 INCH	FOOT	80	80							
△	*	XX000679	CUT AND CAP EXISTING WATER MAIN	EACH	3	3							

* - INDICATES SPECIAL PROVISIONS △ - SPECIALTY ITEM

ROBINSON ENGINEERING, LTD.
CONSULTING REGISTERED PROFESSIONAL ENGINEERS
AND PROFESSIONAL LAND SURVEYORS
17000 SOUTH PARK AVENUE SOUTH HOLLAND, ILLINOIS 60473
(708) 531-6700 FAX (708) 531-3626
© COPYRIGHT 2004
ILLINOIS DESIGN FIRM REGISTRATION NO. 184001128

OAK PARK AVENUE RECONSTRUCTION
115TH STREET TO 111TH STREET
SUMMARY OF QUANTITIES

WORTH, ILLINOIS
Drawn by: EC Date: 3/31/04
Checked by: JMN Scale: NA
Sheet of Project No. 02-162

REVISIONS		
No.	Date	Remarks
1	8-23-04	PS
2	9-7-05	REL