


**SUMMARY OF QUANTITIES**

	IDOT CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	80% FEDERAL 20% BRIDGEVIEW
					CONSTRUCTION TYPE CODE SFTY-1B
1	20200100	EARTH EXCAVATION	CU YD	771	771
2	21101615	TOPSOIL, FURNISH AND PLACE, 4 IN	SQ YD	4207	4207
3	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	52	52
4	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	52	52
5	25000600	POTASIUM FERTILIZER NUTRIENT	POUND	52	52
6	25200110	SODDING, SALT TOLERANT	SQ YD	4207	4207
7	25200200	SUPPLEMENTAL WATERING	UNIT	63	63
8	28000400	PERIMETER EROSION BARRIER	FOOT	60	60
9	31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	10	10
10	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 IN	SQ FT	20297	20297
11	42400800	DETECTABLE WARNINGS	SQ FT	1010	1010
12	44000300	CURB REMOVAL	FOOT	935	935
13	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	308	308
14	44000600	SIDEWALK REMOVAL	SQ FT	3842	3842
15	60250200	CATCH BASINS TO BE ADJUSTED	EACH	4	4
16	60255500	MANHOLES TO BE ADJUSTED	EACH	5	5
17	60265700	VALVE VAULT TO BE ADJUSTED	EACH	1	1
18	60600605	CONCRETE CURB, TYPE B	FOOT	1633	1633
19	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	270	270
20	63200310	GUARDRAIL REMOVAL	FOOT	14	14
21	67100100	MOBILIZATION	L SUM	1	1
22	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
23	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
24	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
25	<del>72400710</del>	RELOCATE SIGN PANEL - TYPE 1	<del>SQ FT</del>	<del>35</del>	<del>35</del>
* 26	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3186	3186
* 27	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	939	939
28	X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	49.6	49.6
29	X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19, N50	TON	99.1	99.1
30	X4066735	LEVELING BINDER (HAND METHOD), SUPERPAVE N50	TON	10	10
31	X8950200	REBUILD EXISTING HANDHOLE	EACH	2	2
32	X8950210	REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	EACH	1	1
33	<del>XX006461</del>	BITUMINOUS CONCRETE PAVEMENT REMOVAL (FULL DEPTH)	SQ YD	1095	1095

\* - DENOTES SPECIALTY ITEM

 <p><b>Globetrotters</b> Engineering Corporation ENGINEERS ARCHITECTS 300 South Wacker Drive Chicago, Illinois 60606</p>	 <p><b>Village of Bridgeview</b> Illinois Steven M. Landek, Mayor</p>	<table border="1"> <tr><th colspan="2">REVISIONS</th></tr> <tr><th>NAME</th><th>DATE</th></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </table>	REVISIONS		NAME	DATE																	<p>ILLINOIS DEPARTMENT OF TRANSPORTATION SIDEWALK IMPROVEMENT SUMMARY OF QUANTITIES</p> <p>SCALE: VERT. N.T.S. HORIZ. N.T.S. DATE: 11 / 17 / 05</p> <p>DRAWN BY: B.C. CHECKED BY: L.S. / D.Z.</p>
		REVISIONS																					
NAME	DATE																						