

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
IL 43	03-00047-00-SW	COOK	20	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 83830				

SCHEDULE OF QUANTITIES

IDOT CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	STA 2+76.95	STA 16+94.08	STA 26+80.00	STA 34+04.73	STA 47+32.12	STA 53+06.50	STA 60+77.22	STA 65+23.17
				TO STA 14+86.01	TO STA 24+89.24	TO STA 33+42.61	TO STA 45+45.39	TO STA 51+51.82	TO STA 56+85.44	TO STA 63+31.00	TO STA 73+55.93
1	20200100 EARTH EXCAVATION	CU YD	771	94	207	97	147	70	33	0	123
2	21101615 TOPSOIL, FURNISH AND PLACE, 4 IN	SQ YD	4207	278	649	645	1238	458	291	0	648
3	25000400 NITROGEN FERTILIZER NUTRIENT	POUND	52	3	8	8	15	6	4	0	8
4	25000500 PHOSPHORUS FERTILIZER NUTRIENT	POUND	52	3	8	8	15	6	4	0	8
5	25000600 POTASIAM FERTILIZER NUTRIENT	POUND	52	3	8	8	15	6	4	0	8
6	25200110 SODDING, SALT TOLERANT	SQ YD	4207	278	649	645	1238	458	291	0	648
7	25200200 SUPPLEMENTAL WATERING	UNIT	63	4	10	10	18	7	4	0	10
8	28000400 PERIMETER EROSION BARRIER	FOOT	60	60	0	0	0	0	0	0	0
9	31101000 SUB-BASE GRANULAR MATERIAL, TYPE B	TON	10	0.5	0	0	0	0.5	0	0	9.0
10	42400200 PORTLAND CEMENT CONCRETE SIDEWALK, 5 IN	SQ FT	20297	4003	3340	2502	4080	1883	1090	75	3324
11	42400800 DETECTABLE WARNINGS	SQ FT	1010	130	140	120	300	60	80	0	180
12	44000300 CURB REMOVAL	FOOT	935	75	210	176	156	80	0	0	238
13	44000500 COMBINATION CURB AND GUTTER REMOVAL	FOOT	308	118	0	0	0	60	110	0	20
14	44000600 SIDEWALK REMOVAL	SQ FT	3842	280	2462	847	78	100	0	75	0
15	60250200 CATCH BASINS TO BE ADJUSTED	EACH	4	0	0	1	2	1	0	0	0
16	60255500 MANHOLES TO BE ADJUSTED	EACH	5	0	1	2	2	0	0	0	0
17	60265700 VALVE VAULT TO BE ADJUSTED	EACH	1	0	0	0	0	0	0	0	1
18	60600605 CONCRETE CURB, TYPE B	FOOT	1633	75	210	220	660	30	0	0	438
19	60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	270	140	0	0	0	0	110	0	20
20	63200310 GUARDRAIL REMOVAL	FOOT	14	0	0	0	0	0	0	0	14
21	67100100 MOBILIZATION	L SUM	1	0	0	0	0	0	0	0	0
22	70102625 TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0	0	0	0	0	0	0	0
23	70102635 TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0	0	0	0	0	0	0	0
24	70102640 TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0	0	0	0	0	0	0	0
25	72400710 RELOCATE SIGN PANEL - TYPE 1	SQ FT	35	0	0	0	0	35	0	0	0
26	78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3186	1020	0	258	462	60	752	170	464
27	78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	939	276	0	52	123	15	206	131	136
28	X4066414 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	49.6	2	0	0	28	0.4	0	0	19.2
29	X4066614 BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19, N50	TON	99.1	2	0	0	58	0.7	0	0	38.4
30	X4066735 LEVELING BINDER (HAND METHOD), SUPERPAVE N50	TON	10	0	0	0	0	0	0	0	10
31	X8950200 REBUILD EXISTING HANDHOLE	EACH	2	0	0	1	0	0	0	0	1
32	X8950210 REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	EACH	1	1	0	0	0	0	0	0	0
33	XXXXXX BITUMINOUS CONCRETE PAVEMENT REMOVAL (FULL DEPTH)	SQ YD	1095	0	0	0	133	0	0	0	962

- DENOTES SPECIALTY ITEM

 <b>Globetrotters®</b> Engineering Corporation ENGINEERS ARCHITECTS 300 South Wacker Drive Chicago, Illinois 60606	 <b>Village of Bridgeview</b> Illinois Steven M. Landek, Mayor	REVISIONS NAME DATE		ILLINOIS DEPARTMENT OF TRANSPORTATION SIDEWALK IMPROVEMENT SCHEDULE OF QUANTITIES  SCALE: VERT. N.T.S. HORIZ. N.T.S. DATE: 11 / 17 / 05
		DRAWN BY: B.C. CHECKED BY: L.S. / D.Z.		