

# SCHEDULES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PA 283	01-00282-00-BR	LEE	51	5
FED. ROAD DIST. NO. 7		ALPMS	FED. AID PROJECT	

FURNISHING AND ERECTING RIGHT-OF-WAY		
STATION	EACH	REMARKS
ROCKYFORD ROAD		
34.38'L -13+62.90	1	
45' L 15+00	1	
45' L 16+00	1	
45' L 17+00	1	
45' L 17+70.95	1	PT
60' L 19+50	1	
60' L 20+75.64	1	
50' L 21+50	1	
45' L 22+00	1	
45' L 23+00	1	
45' L 24+00	1	
40' L 24+41.80	1	
40' L 25+70	1	
79.69' L 25+70.41	1	
40' L 31+19.31	1	PC
40' L 32+00	1	
40' L 33+00	1	
40' L 34+00	1	
40' L 37+57.13	1	PC
40' L 38+00	1	
40' L 39+00	1	
40' L 40+00	1	
32.70' L 40+93.77	1	PT
40' R 24+27.95	1	
40' R 25+00	1	
40' R 25+88	1	PT
40' R 31+19.31	1	PC
40' R 32+20.45	1	
RIVER VIEW ROAD		
33' L 100+00	1	
33' R 100+00	1	
<b>PROJECT TOTAL</b>	<b>30</b>	

66600105

SHORT-TERM PAVEMENT MARKING		
STATION	FOOT	REMARKS
212+83 - 324+20	1,012	4' STRIPE @ 40' GAP
14+20 - 17+56	30	4' STRIPE @ 40' GAP
<b>PROJECT TOTAL</b>	<b>1,042</b>	

70300100

WORK ZONE PAVEMENT MARKING REMOVAL		
STATION	SQ FT	REMARKS
ENTIRE PROJECT	347	
<b>PROJECT TOTAL</b>	<b>347</b>	

70301000

THERMOPLASTIC PAVEMENT MARKING LINE - 4"		
STATION	FOOT	REMARKS
213+00 TO 221+00	800	NPZ EB/NB SOLID 4" YELLOW
237+00 TO 307+00	7,000	NPZ EB/NB SOLID 4" YELLOW
312+00 TO 318+00	600	NPZ EB/NB SOLID 4" YELLOW
327+50 TO 321+00	650	NPZ WB/SB SOLID 4" YELLOW
315+00 TO 248+00	6,700	NPZ WB/SB SOLID 4" YELLOW
229+00 TO 223+00	600	
212+83 TO 248+00	879	4" SKIP DASH 10'/30'
307+00 TO 312+00	125	4" SKIP DASH 10'/30'
315+00 TO 327+00	300	4" SKIP DASH 10'/30'
14+20 TO 17+56	672	2 - 4" YELLOW
212+83 TO 324+20	22,374	4" WHITE EDGE LINE
14+20 TO 17+90	740	4" WHITE EDGE LINE
<b>PROJECT TOTAL</b>	<b>41,440</b>	

78000200

BIDIRECTIONAL GUARDRAIL REFLECTORS		
STATION	EACH	REMARKS
L&R - GUARDRAIL AT BRIDGE STA. 20+00	12	SEE STANDARD 635006-02
<b>PROJECT TOTAL</b>	<b>12</b>	

78200455

TERMINAL - MARKER DIRECT APPLIED		
STATION	EACH	REMARKS
BRIDGE AT STA. 20+00	4	ENDS OF TRA. BAR. TER. T-1, SPL (TAN)
<b>PROJECT TOTAL</b>	<b>4</b>	

78201000

BREAKER-RUN CRUSHED STONE		
STATION	TON	REMARKS
CONTINGENCY ITEM	1,861	AS REQUIRED BY ENGINEER
<b>PROJECT TOTAL</b>	<b>1,861</b>	

Z0005400