CONTRACT NO. 92667

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
III	10(B-1,BR-2)	MONTGOMERY	104	4

STA. _____ TO STA. _____

FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT

LOCATION OF WORK
IL 185, T.R. 318
± 1.4 MILES SOUTWEST OF COFFEEN
MONTGOMERY COUNTY

SUMMARY OF QUANTITIES

PAYCODE	PAY ITEM DESCRIPTION	UNITS	TOTAL QUANTITY	F: RURAL ROADWAY IL 185	F: RURAL ROADWAY TR 318	BRF: RURAL STRUCTURES BAYOU CREEK 068-0027	BRF: RURAL STRUCTURES SHOAL CREEK 068-0505 PR
				CONSTRUCTION TYPE CODE			
				I000-2A		SFTY-2A	X071-2A
				80% FED / 20% STATE		80% FED / 20% STATE	80% FED / 20% STATE
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2745	2633	112	0	0
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ YD	600	600			
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	2.5	0	2.5	0	0
40300500	COVER COAT AGGREGATE	TON	11.6	0	11.6	0	0
40300600	SEAL COAT AGGREGATE	TON	5.8	0	5.8	0	0
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.1	2.2	0.9	0	0
40600300	AGGREGATE (PRIME COAT)	TON	7.0	7.0	0	0	0
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	0	0	0
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	187	187	0	0	0
40600990	TEMPORARY RAMP	SQ YD	508.1	508.1	0	0	0
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	226	226	0	0	0
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	43	43	0	0	0
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1791	1791	0	0	0
44000100	PAVEMENT REMOVAL	SQ YD	559	239	320	0	0
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	1069	1069	0	0	0
44001205	BITUMINOUS CONCRETE SURFACE REMOVAL COMPLETE	SQ YD	191.5	0	0	191.5	0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	26	0	26	0	0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	0	0	0	1
50102400	CONCRETE REMOVAL	CU. YD.	2.1			2.1	
50105220	PIPE CULVERT REMOVAL	FOOT	120	87	33	0	0
50200100	STRUCTURE EXCAVATION	CU YD	166.1	0	0	0	166.1

Rev. 2-28-06

Rev.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 777 (IL RTE. 185)
SECTION 10(B-1, BR-2)
MONTGOMERY COUNTY

SCALE: VERT. HORIZ. DRAWN BY
DATE CHECKED BY

PLOT DATE = 1/12/2006
FILE NAME = c:\projects\ed53694\shtsoq.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = sieglert