

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
777	10(B-1, BR-2)	MONTGOMERY	104	8
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

LOCATION OF WORK
 IL 185, T. R. 318
 ± 1.4 MILES SOUTHWEST OF COFFEE
 MONTGOMERY COUNTY

ROADWAY		RURAL	
IL 185	TR 318	BAYOU CREEK	SHOAL CREEK
		068-0027	068-0505 PR

SUMMARY OF QUANTITIES

PAYCODE	PAY ITEM DESCRIPTION	UNITS	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				I000-2A 80% FED / 20% STATE		SFTY-2A 80% FED / 20% STATE		X071-2A 80% FED / 20% STATE	
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	15	15	0	0	0	0	0
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION LOCATION 1	EACH	1	0	0	0	0	1	0
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION LOCATION 2	EACH	1	0	0	0	0	1	0
X6330103	REMOVE AND RE-ERECT TRAFF BARR TERMINAL, TY 1, SPECIAL (TANGENT)	EACH	4	4	0	0	0	0	0
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	8	8	0	0	0	0	0
X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	0	0	0	0	0
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1	0	0	0	0	0
Z0002600	BAR SPLICERS	EACH	683	0	0	42	0	0	0
Z0003700	BEARING PAD ADJUSTMENT	EACH	22	0	0	22	0	0	0
Δ Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	EACH	4	4	0	0	0	0	0
Δ Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3	EACH	2	2	0	0	0	0	0
Δ Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3	EACH	4	4	0	0	0	0	0
Z0032700	KEYWAY REPAIR	FOOT	116	0	0	116	0	0	0
* Z0065000	SETTING PILES IN ROCK	EACH	12	0	0	0	0	12	0

Δ SFTY-3N
 * SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP 777 (IL RTE. 185)
 SECTION 10(B-1, BR-2)
 MONTGOMERY COUNTY
 SCALE: VERT. _____
 DATE: _____
 DRAWN BY _____
 CHECKED BY _____

PLOT DATE = 1/12/2006
 FILE NAME = c:\projects\92667\shyoa.dgn
 PLOT SCALE = 30.0000 / IN.
 USER NAME = shyoa

Rev.