

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
777	10(B-1, BR-2)	MONTGOMERY	---	21
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS FED. AID PROJECT		

GUARD RAIL										
LOCATION				STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 5A (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 2 (EACH)	RADIUS GURADRAIL (EACH)	TRAF BAR TERMINAL TYPE 1 SPECIAL (TANGENT) (EACH)	TERMINAL MARKER - DIRECT APPLIED (EACH)
STATION	TO	STATION	LT / RT	(FT)						
490+55.00	-	491+05.55	LT						1	1
491+05.55	-	492+13.75	LT	108.2						
492+13.75	-	492+27.00	LT		1					
489+46.85	-	489+96.85	RT						1	1
489+96.85	-	492+13.75	RT	216.9						
492+13.75	-	492+27.00	RT		1					
493+15.00	-	493+28.25	LT		1					
493+28.25	-	493+74.81	LT	46.6						
LOCATION 2 RADIUS			LT				1	1		
493+15.00	-	493+28.25	RT		1					
493+28.25	-	493+81.96	RT	53.7						
LOCATION 1 RADIUS			RT				1	1		
494+42.00	-	494+92.00	LT						1	1
494+92.00	-	495+25.00	LT	33.0						
495+25.00	-	495+75.00	LT							
498+12.94	-	498+62.94	LT						1	1
498+62.94	-	499+36.24	LT	73.3						
499+36.24	-	499+67.50	LT			1				
497+53.76	-	498+03.76	RT						1	1
498+03.76	-	499+32.25	RT	128.5						
499+32.25	-	499+63.50	RT			1				
501+24.50	-	501+55.75	LT			1				
501+55.75	-	501+68.00	LT	12.5						
LOCATION 3 RADIUS			LT				1	1		
501+20.50	-	501+51.75	RT			1				
501+51.75	-	502+15.50	RT	63.75						
502+15.50	-	502+65.50	RT						1	1
502+20.00	-	502+70.00	LT						1	1
502+70.00	-	503+19.50	LT	49.50						
503+19.50	-	503+69.50	LT						1	1
TOTALS:				786	4	4	3	3	9	9

PLOT DATE = 1/24/2006  
 USER NAME = alegret

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FAP 777 (IL RTE. 185)  
 SECTION 10(B-1, BR-2)  
 MONTGOMERY COUNTY  
 SCALE: VERT. DATE      HORIZ. DATE  
 DRAWN BY      CHECKED BY