

teeslegok  
 ..../23/2005  
 c:\projects\94964\d03502.pae.dgn

CONTRACT NO. 94964

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	13B-1&13B-2	MARION	78	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		DUMS CREEK		SKILLET FORK CREEK	
				X071-2A	SFTY-3N	X071-2A	SFTY-3N
51202700	DRIVING STEEL PILES	FOOT	2543	1218		1325	
51203700	TEST PILE STEEL HP12X74	EACH	4	4			
51203710	TEST PILE STEEL HP12X84	EACH	3			3	
51500100	NAME PLATES	EACH	2	1		1	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	164.7	72		92.7	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	295.3	144		151.3	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	700	350		350	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	4		4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	8	4		4	
63200310	GUARDRAIL REMOVAL	FOOT	2046	1005		1041	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	14	7		7	
67100100	MOBILIZATION	L SUM	1	0.5		0.5	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1		1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5		0.5	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5		0.5	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8	4		4	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1		1	
70106700	TEMPORARY RUMBLE STRIP	EACH	12	6		6	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	777	415		362	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9493	5560		3933	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1997	1064		933	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1820	990		830	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1760	930		830	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	9493	5560		3933	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	13	8		5	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	5	2		3	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	6		6	
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	10	4		6	

\* SPECIALTY ITEMS

PLOT DATE = 12/23/2005  
 FILE NAME = c:\projects\94964\d03502.pae.dgn  
 PLOT SCALE = 28.8000 / IN.  
 USER NAME = teeslegok

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 SCALE: VERT. \_\_\_\_\_  
 DATE: \_\_\_\_\_ HORIZ. \_\_\_\_\_  
 DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_