

5000

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	142
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	164
20200100	EARTH EXCAVATION	CU YD	1520
20400800	FURNISHED EXCAVATION	CU YD	315
20800150	TRENCH BACKFILL	CU YD	657
25000100	SEEDING, CLASS 1	ACRE	1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2
25100115	MULCH, METHOD 2	ACRE	1
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	1
28000300	TEMPORARY DITCH CHECKS	EACH	20
28000400	PERIMETER EROSION BARRIER	FOOT	957
28000500	INLET AND PIPE PROTECTION	EACH	5
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	24
28200200	FILTER FABRIC	SQ YD	24
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	8807
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	13
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	111
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	26
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	7000
42001200	PAVEMENT FABRIC	SQ YD	7000
42001300	PROTECTIVE COAT	SQ YD	8283
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	128
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	14840
42400800	DETECTABLE WARNINGS	SQ FT	24
44000100	PAVEMENT REMOVAL	SQ YD	504
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	58
44000600	SIDEWALK REMOVAL	SQ FT	510
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2

5000

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
50105220	PIPE CULVERT REMOVAL	FOOT	296
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1
54248515	CONCRETE COLLAR	EACH	1
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	476
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	93
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	634
60218500	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	3
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	3
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	5
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	2
60240324	INLETS, TYPE B, TYPE 20 FRAME AND GRATE	EACH	1
60500060	REMOVING INLETS	EACH	2
60600605	CONCRETE CURB, TYPE B	FOOT	109
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4493
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	4,700
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	210
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	88
X0322034	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	705
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	75
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	363
X6020074	INLETS, TYPE A, TYPE 3V FRAME & GRATE	EACH	5
X6020075	INLETS, TYPE B, TYPE 3V FRAME & GRATE	EACH	16
XX004949	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE	TON	1
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	52
Z0013798	CONSTRUCTION LAYOUT	L SUM	1

\* SPECIALTY ITEMS

CITY OF O'FALLON, ILLINOIS

**SUMMARY OF QUANTITIES**  
 SHEET 1 OF 1

SCALE: N/A  
 DATE: 7/21/05

DRAWN BY: SSM  
 CHECKED BY: SRD

Plot Date: 07/13/2005  
 Plot Time: 2:05:54 PM  
 File Name: I:\03005\CAD\Construction\Plans\Summary.dgn

