

BL059

X:\Bloomington\0508503\Draw\Sheets\
 FILE: 02_INDEXSUM.dwg
 LAYOUT: 02_INDEX_SUM
 UPDATE BY: jfrank
 SURVEY BOOK #
 DATE: Thu 2/9/06 9:21am
 XREF DWG: Clntinfo.dwg

REVISIONS

NUMBER	BY	DATE

0 1 2

THIS BAR IS EQUAL TO 2"
 AT FULL SCALE (34X22).

Index To Sheets	
Sht. No.	Title
01	COVER SHEET
02	INDEX TO SHEETS & SUMMARY OF QUANTITIES
03	AIRPORT SITE PLAN
04	CONSTRUCTION ACTIVITY PLAN 1
05	CONSTRUCTION ACTIVITY PLAN 2
06	EXISTING CONDITIONS & REMOVALS
07	PROPOSED IMPROVEMENTS
08	TYPICAL SECTIONS
09	TAXIWAY G-1 PLAN & PROFILE STA. 18+00 TO STA. 31+00
10	JOINTING PLAN
11	JOINTING DETAILS
12	PAVING & MISCELLANEOUS DETAILS
13	ELECTRICAL & LIGHTING PLAN
14	WIND CONE LAYOUT PLAN
15	WIND CONE CABLING SHEET 1
16	WIND CONE CABLING SHEET 2
17	WIND CONE CABLING SHEET 3
18	WIND CONE DETAILS
19	SIGN MODIFICATIONS FOR TAXIWAY G-2
20	ELECTRICAL DETAILS SHEET 1
21	ELECTRICAL DETAILS SHEET 2
22	ELECTRICAL DETAILS SHEET 3
23	ELECTRICAL DETAILS SHEET 4
24	ELECTRICAL DETAILS SHEET 5
25	ELECTRICAL DETAILS SHEET 6
26	DRAINAGE PLAN
27	UNDERDRAIN DETAILS
28	MARKING PLAN
29	MARKING DETAILS
30	TURFING PLAN
31	EROSION CONTROL DETAILS
32	TAXIWAY G-1 CROSS SECTIONS STA. 20+37.95 TO STA. 22+50
33	TAXIWAY G-1 CROSS SECTIONS STA. 23+00 TO STA. 25+50

SUMMARY OF QUANTITIES			
ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY
AR107408	L-806 WIND CONE -8' LIGHTED	EA	4
AR108051	POWER CABLE IN UNIT DUCT	LF	2330
AR108108	1/C #8 5 KV UG CABLE	LF	1600
AR108158	1/C #8 5 KV UG CABLE IN UD	LF	1000
AR110504	4-WAY CONCRETE ENCASED DUCT	LF	200
AR800312	2" HDPE, DIRECT BURY	LF	1600
AR125415	MITL - BASE MOUNTED	EA	32
AR125441	TAXI GUIDANCE SIGN 1 CHARACTER	EA	1
AR125442	TAXI GUIDANCE SIGN 2 CHARACTER	EA	1
AR125443	TAXI GUIDANCE SIGN 3 CHARACTER	EA	3
AR125445	TAXI GUIDANCE SIGN 5 CHARACTER	EA	1
AR125446	TAXI GUIDANCE SIGN 6 CHARACTER	EA	1
AR125470	MODIFY EXISTING SIGN PANEL	EA	4
AR125525	HURL, INPAVEMENT	EA	1
AR125565	SPLICE CAN	EA	2
AR125902	REMOVE BASE MOUNTED LIGHT	EA	5
AR125906	REMOVE SPLICE CAN	EA	1
AR150510	ENGINEER'S FIELD OFFICE	LS	1
AR152455	EMBANKMENT IN PLACE	CY	2500
AR156510	SILT FENCE	LF	1000
AR201504	BITUMINOUS BASE COURSE - 4"	SY	13100
AR201630	BITUMINOUS BASE TEST SECTION	EA	1
AR209604	CRUSHED AGG. BASE COURSE - 4"	SY	4400
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	3100
AR501512	12" PCC PAVEMENT	SY	8650
AR501530	PCC TEST BATCH	EA	1
AR602510	BITUMINOUS PRIME COAT	GAL	3440
AR603510	BITUMINOUS TACK COAT	GAL	1375
AR620520	PAVEMENT MARKING WATER BORNE	SF	12000
AR620900	PAVEMENT MARKING REMOVAL	SF	2050
AR705524	4" PERFORATED UNDERDRAIN WITH SOCK	LF	1525
AR705640	UNDERDRAIN CLEANOUT	EA	4
AR705905	REMOVE COLLECTION STRUCTURE	EA	1
AR800317	PAVEMENT SENSOR	EA	1
AR800333	PORTABLE CLOSED RUNWAY MARKER	EA	2
AR800357	ADJUSTABLE LIGHT CANS	EA	2
AR901510	SEEDING	AC	1
AR904510	SODDING	SY	1000
AR908520	EXCELSIOR BLANKET	SY	5000

BLOOMINGTON-NORMAL AIRPORT AUTHORITY
 CENTRAL ILLINOIS REGIONAL AIRPORT
 BLOOMINGTON, ILLINOIS

CONSTRUCT TAXIWAY G-1

INDEX TO SHEETS &
 SUMMARY OF QUANTITIES

© Copyright CMT, Inc.
CMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 94-000613



DESIGN BY: JEF

DRAWN BY: DPA

CHECKED BY: RLV

APPROVED BY: JEF

DATE: 1/13/2006

JOB No: 05085-0300

ILLINOIS PROJECT BMI-3452

A.I.P. PROJECT 3-17-0006-XX

SHEET 02 OF 2 SHEETS