February 24, 2023

SUBJECT: FAU 2419 (Lakeview Parkway)

Section 98-00026-02-WR (Vernon Hills)

Lake County

Contract No. 61J15

Item 122

March 10, 2023 Letting

Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices
- 2. Revised Plan Sheets 9, 10, 19, 66, 68, 71, 72, 73, 118, 119, 143, 144, 155 & 156
- 3. Revised Page 68 of the Special Provsions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.

THE LEG

Bureau Chief, Design and Environment

111+00 to 115+50 LT	Underground Telecommunications	MCI Contractor to relocate facility MCI		15 Days
209+00 LT	Gas Valve	North Shore Contractor to relocate facility	North Shore Gas	30 Days
404+00 to 408+50	Underground Gas	North Shore Contractor to relocate facility		
201+00 to 206+00	Underground Gas	North Shore Contractor to relocate facility	North Shore Gas	60 Davis
208+50 to 215+00	Underground Gas	North Shore Contractor to relocate facility	North Shore Gas	60 Days
111+00	Underground Gas	North Shore Contractor to relocate facility		

Stage 1

STAGE / LOCATION	ТҮРЕ	DESCRIPTION	RESPONSIBLE AGENCY	DURATION OF TIME
109+50 – 111+00 LT	underground lines	AT&T Contractor to expose and protect duct and cable during storm sewer installation	AT&T	15 Days

Pre-Stage: 295 Days Total Installation
Stage 1: Days Total Installation
Stage 2: Days Total Installation

<u>UTILITIES TO BE WATCHED AND PROTECTED</u>

The areas of concern noted below have been identified by following the suggested staging plan included for the contract. The information provided is not a comprehensive list of all remaining utilities, but those which during coordination were identified as ones which might require the Department's contractor to take into consideration when making the determination of the means and methods that would be required to construct the proposed improvement. In some instances, the contractor will be responsible to notify the owner in advance of the work to take place so necessary staffing on the owner's part can be secured.

Stage 1

STAGE / LOCATION	ТҮРЕ	DESCRIPTION	RESPONSIBLE AGENCY
201+86, 46' RT	Buried Cable	UG Cable Crosses near PR Storm Structure	ATT
206+74.7, 47.2' RT	Buried Cable	UG Cable Crosses near PR Storm Structure	ATT