

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				90% FEDERAL, 10% STATE			
				BRIDGE			
				ROADWAY 0003 URBAN	SN 099-8307 URBAN	LIGHTING 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN
20101000	TEMPORARY FENCE	FOOT	310	310			
20101100	TREE TRUNK PROTECTION	EACH	50	50			
20101200	TREE ROOT PRUNING	EACH	50	50			
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	25	25			
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	25	25			
20200100	EARTH EXCAVATION	CU YD	3,278	3,278			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	959	959			
20400800	FURNISHED EXCAVATION	CU YD	32,990	32,990			
20800150	TRENCH BACKFILL	CU YD	254	254			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	425	425			
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,164	1,164			
25000210	SEEDING, CLASS 2A	ACRE	1.50	1.50			
25000300	SEEDING, CLASS 3A	ACRE	1.50	1.50			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	125	125			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	125	125			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	125	125			
25100115	MULCH, METHOD 2	ACRE	0.75	0.75			

2

* SPECIALTY ITEM

MODEL: 20 SHEET 1
FILE NAME: C:\TRANSPORT\SYSTEMS\LOCAL\TRANSPORT\SYSTEMS\PM\01\DM\60808\162R55-SHT-500-01.DGN



USER NAME = HECHTBR	DESIGNED - BH	REVISED -
	DRAWN - CMA	REVISED -
PLOT SCALE = 0.16666667 ' / IN.	CHECKED - DDH	REVISED -
PLOT DATE = 12/15/2022	DATE - 12/15/2022	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


BRIGGS STREET
SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	FAI 80 22 BR	WILL	133	5
CONTRACT NO. 62R55				
ILLINOIS FED. AID PROJECT				

2 REVISED SHEET 2/24/2023

REV-SEP

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				90% FEDERAL, 10% STATE			
				BRIDGE			
				ROADWAY 0003 URBAN	SN 099-8307 URBAN	LIGHTING 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN
60108204	PIPE UNDERDRAINS, TYPE 2, 4"	FOOT	141	141			
60146304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	220		220		
60146305	PIPE UNDERDRAINS FOR STRUCTURES (SPECIAL) 4"	FOOT	233	233			
60201340	CATCH BASINS, TYPEA, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	8	8			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	434	434			
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPEA, 6 FOOT POSTS	FOOT	112.5	112.5			
* 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	225	225			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	3			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4 2	4 2			
63200310	GUARDRAIL REMOVAL	FOOT	1,321	1,321			
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2			
64301090	ATTENUATOR BASE	SQ YD	42	42			
* 64401100	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	490	490			
* 64401300	HIGH TENSION CABLE MEDIAN BARRIER TERMINALS	EACH	4	4			

* SPECIALTY ITEM

MODEL: 00 SHEET 1
FILE NAME: C:\TRANSPORT\LOCAL\TRANSPORT\SYSTEMS\PH-01\DM50808162R55-SHT-500-06.DGN



USER NAME = HECHTBR	DESIGNED - BH	REVISED -
PLOT SCALE = 0.16666667 ' / IN.	DRAWN - CMA	REVISED -
PLOT DATE = 12/15/2022	CHECKED - DDH	REVISED -
	DATE - 12/15/2022	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**BRIGGS STREET
SUMMARY OF QUANTITIES**

SCALE: N.T.S. SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.		SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80		FAI 80 22 BR	WILL	133	10
				CONTRACT NO. 62R55	
		ILLINOIS FED. AID PROJECT			

 REVISED SHEET 2/24/2023