

SUMMARY OF QUANTITIES					URBAN 90% FED 10% STATE	CONSTRUCTION TYPE CODES				
+	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	RETAINING WALL Y007	BRIDGE X701-2A	TRAFFIC SIGNAL- Y031-1F	HIGHWAY LIGHTING Y030-1E	
	M2500750	MOWING	HA	0.5	0.5					
	M2510630	EROSION CONTROL BLANKET	SO M	1,823	1,823					
	M2520110	SODDING, SALT TOLERANT	SO M	488	488					
	M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	2	2					
	M2800400	PERIMETER EROSION BARRIER	METER	346	346					
	M3111100	SUB-BASE GRANULAR MATERIAL, TYPE B, 100MM	SO M	1,430	1,430					
	M3530245	PORTLAND CEMENT CONCRETE BASE COURSE, 245MM	SO M	1,356	1,356					
	M4030200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	1.3	1.3					
	M4060300	AGGREGATE (PRIME COAT)	M TON	6	6					
	M4060990	TEMPORARY RAMP	SO M	113	113					
	M4060400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	M TON	9.4	9.4					
	M4060980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SO M	89	89					
	M4061000	BITUMINOUS REPLACEMENT OVER PATCHES	M TON	0.9	0.9					
	M4205050	BRIDGE APPROACH PAVEMENT (SPECIAL)	SO M	540	540					
	M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SO M	48	48					
	M4240125	PORTLAND CEMENT CONCRETE SIDEWALK 125MM	SO M	444.0	444.0					
	M4400065	BITUMINOUS SURFACE REMOVAL 65MM	SO M	1395	1395					
	M4400415	BITUMINOUS REMOVAL OVER PATCHES 115MM	SO M	34	34					
	M4402000	PAVEMENT REMOVAL	SO M	1,452	1,452					
	M4402010	DRIVEWAY PAVEMENT REMOVAL	SO M	32	32					
	M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	415	415					
	M4402050	SIDEWALK REMOVAL	SO M	481	481					
	M4402060	APPROACH SLAB REMOVAL	SO M	224	224					
	M4402530	PAVED SHOULDER REMOVAL	SO M	6	6					
	M4402420	MEDIAN REMOVAL	SO M	90	90					
	M4427025	CLASS C PATCHES, TYPE I, 250MM	SO M	50	50					
	M4427225	CLASS C PATCHES, TYPE II, 250MM	SO M	40	40					
	M4427325	CLASS C PATCHES, TYPE III, 250MM	SO M	45	45					
	M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	575	575					
	M5010240	CONCRETE REMOVAL	CU M	145.2			145.2			
	M5010465	SLOPE WALL REMOVAL	SO M	18			18			
	M5020100	STRUCTURE EXCAVATION	CU M	1,285		63	1,222			
	M5030040	PREFORMED JOINT SEAL 102MM	METER	50.2			50.2			
	M5030350	CONCRETE STRUCTURES	CU M	311.3		47.7	263.6			
	M5030360	CONCRETE SUPERSTRUCTURE	CU M	590.1			590.1			
	M5030390	BRIDGE DECK GROOVING	SO M	1,453			1,453			
	M5030450	PROTECTIVE COAT	SO M	3,238	1,263		1,975			
	M5041219	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 1219MM	METER	863.5			863.5			
	M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	KG	950			950			

\* = SPECIALTY ITEM  
+ = NON PARTICIPATING ITEM  
x = SAFETY FUND CODE - SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
F.A.I. 90 (I-90) AT NAGLE AVENUE  
DATE: DECEMBER 2004  
DRAWN BY: ML, DR, FD  
CHECKED BY: JMH, MDK



Rev.