

FAI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	1314B	COOK	160	6
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
		CONTRACT 60293		

SUMMARY OF QUANTITIES				URBAN 90% FED 10% STATE	CONSTRUCTION TYPE CODES				
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	<del>SN016-0779</del> RETAINING WALL Y007	<del>SN016-0708</del> BRIDGE X781-2A	TRAFFIC SIGNAL- Y031-1F	HIGHWAY LIGHTING Y030-1E	
M5070211	FURNISHING SOLDIER PILES (HP SECTION)	METER	107.5		107.5				
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	90,430		3,300	87,130			
M5090050	PEDESTRIAN RAILING	METER	63		44	19			
M5110100	SLOPE WALL 100MM	SQ M	125			125			
M5120900	TEMPORARY SHEET PILING	SQ M	125			125			
M5503050	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 300MM	METER	21	21					
+ M5504800	STORM SEWERS TO BE CLEANED	METER	804	804					
M5870020	BRIDGE SEAT SEALER	SQ M	74			74			
M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	31		31				
<del>M6010080</del>	<del>FRENCH DRAINS</del>	<del>SQ M</del>	<del>1</del>						
M6010085	GEOTECHNICAL FABRIC FOR FRENCH DRAINS	<del>SQ M</del>	102		102				
M6010610	PIPE UNDERDRAINS 150MM	METER	199.5	199.5					
M6010710	PIPE UNDERDRAINS 150MM (SPECIAL)	METER	3.0	3.0					
M6011205	BACKSLOPE DRAINS, TYPE 1 100MM	METER	19.5	19.5					
M6020140	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 8 GRATE	EACH	2	2					
M6020230	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	4	4					
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	372.4	372.4					
M6060520	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30 (SPECIAL)	METER	53.5	53.5					
M6320030	GUARDRAIL REMOVAL	METER	27	27					
M6640100	CHAIN LINK FENCE, 1.2 METER	METER	55	55					
M6641920	CHAIN LINK FENCE REMOVAL	METER	138.5	138.5					
M7030100	SHORT-TERM PAVEMENT MARKING	METER	2,266	2,266					
M7030210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	28	28					
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	4,255	4,255					
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	52	52					
M7030280	TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	54	54					
M7030510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ M	7	7					
M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	274	274					
M7030540	PAVEMENT MARKING TAPE, TYPE III 150MM	METER	50	50					
M7030580	PAVEMENT MARKING TAPE, TYPE III 600MM	METER	12	12					
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	338	338					
M7040100	TEMPORARY CONCRETE BARRIER	METER	259.25	259.25					
M7040200	RELOCATE TEMPORARY CONCRETE BARRIER	METER	82.35	82.35					
* M7800100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	29	29					
* M7800105	THERMOPLASTIC PAVEMENT MARKING - LINE 100 MM	METER	1,567	1,567					
* M7800115	THERMOPLASTIC PAVEMENT MARKING - LINE 150 MM	METER	414	414					
* M7800120	THERMOPLASTIC PAVEMENT MARKING - LINE 200 MM	METER	64	64					
* M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300 MM	METER	86	86					
* M7800140	THERMOPLASTIC PAVEMENT MARKING - LINE 600 MM	METER	45	45					

- \* = SPECIALTY ITEM
- + = NON PARTICIPATING ITEM
- x = SAFETY FUND CODE - SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
F.A.I. 90 (I-90) AT NAGLE AVENUE

**COLLINS ENGINEERS**  
123 N. WACKER DR., SUITE 300  
CHICAGO, IL 60606  
(312) 704-9300  
ILLINOIS PROFESSIONAL DESIGN FIRM  
LICENSE NO. 184-000993

DRAWN BY: ML, DR, FD  
DATE: DECEMBER 2004  
CHECKED BY: JMH, MDK