

SUMMARY OF QUANTITIES				URBAN 90% FED 10% STATE	CONSTRUCTION TYPE CODES				
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	SN 016-11779 RETAINING WALL Y007	SN 016-0708 BRIDGE X781-2A	TRAFFIC SIGNAL- Y031-1F	HIGHWAY LIGHTING Y030-1E	
• MX033524	ELECTRICAL MANHOLE, 1M X 1.2M X 1.2M	EACH	7				7		
• X0324896	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE 2-SECTION, BRACKET MOUNTED (SYMBOLIC)	EACH	3				3		
• MX033525	POLE, STEEL ANCHOR BASE 250MM DIAMETER, 3 GAUGE, 10.5M	EACH	4					4	
	TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	2						
• MX032500	POLE, STEEL, ANCHOR BASE 292 MM DIAMETER, 7 GAUGE (9.9M) CITY DRG. #762, INSTALL ONLY	EACH	2					2	
• MX033527	POLE, STEEL, ANCHOR BASE 381 MM DIAMETER, 7 GAUGE (10.5M) CITY DRG. #808, INSTALL ONLY	EACH	2					2	
• X0324901	REMOVE EXISTING STREET LIGHTING FOUNDATION	EACH	5					5	
• X0324902	REMOVE EXISTING TRAFFIC SIGNAL FOUNDATION	EACH	10				10		
• X0322709	CONTROLLER, STREET LIGHTING, BASE MOUNTED, 1 PHASE 100 AMP	EACH	1					1	
• X0324900	SERVICE CONNECTION TO CECO LINE	EACH	1					1	
• X0321191	CONCRETE FOUNDATION FOR BASE MOUNTED STREET LIGHT CONTROLLER CABINET	EACH	1					1	
• MX033526	POLE, STEEL ANCHOR BASE 250 MM DIAMETER, 7 GAUGE, 10.5	EACH	1				1		

• = SPECIALTY ITEM
+ = NON PARTICIPATING ITEM
X = SAFETY FUND CODE - SFTY-3N

REVISIONS	
NAME	DATE

COLLINS ENGINEERS
123 N. WACKER DR., SUITE 300
CHICAGO, IL 60606
(312) 704-9300
ILLINOIS PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-000993

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.I. 90 (I-90) AT NAGLE AVENUE
DATE: DECEMBER 2004
DRAWN BY: ML, DR, FD
CHECKED BY: JMH, MDK