

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	5
STA.		TO STA.		60997
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED 20% STATE J000-2A	BRIDGE 80% FED 20% STATE X771-5B	RETAINING WALL 80% FED 20% STATE Y007	LIGHTING 100% VILLAGE Y030-1E	TRAFFIC SIGNALS IL 22 @ MALL DR. 100% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ US 12 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ ELA 80% FED 10% STATE 5% VILL. 5% COUNTY Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN WEST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ OLD RAND 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN EAST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ BUESCHING 80% FED 10% STATE 10% VILL. Y031-1F	TRAFFIC SIGNAL EVF EQUIPMENT 100% VILL. Y031-3D	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE Y031-1F	NEW SIDEWALK & BIKE PATH 50% STATE 50% VILL. SFTY-1B	WATER MAIN/SAN. SEWER 80% FED 20% STATE Y060	WATER MAIN/SAN. SEWER 100% VILL. Y060	TURN LANE FOR TARGET RENTAL 50% STATE 50% TARGET RENTAL J000-1A	100% VILLAGE OF LAKE ZURICH Y031-1F
M5050105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1																
50500505	STUD SHEAR CONNECTORS	EACH	1447		144	1303															
* M5070209	UNTREATED TIMBER LAGGING	SQ M	525		88	437															
* M5070213	FURNISHING SOLDIER PILES (BUILT-UP SECTION)	METER	172.5		67.0	105.5															
* M5070215	FURNISHING SOLDIER PILES (W SECTION)	METER	605		7.5	597.5															
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	48,690		24770	23,920															
M5100305	PIPE HANDRAIL, SPECIAL	METER	353.7		61.9	291.8															
M5120115	FURNISHING METAL PILE SHELLS 356MM	METER	994		994																
51203200	TEST PILE METAL SHELLS	EACH	2		2																
M5120340	DRIVING AND FILLING SHELLS	METER	994		994																
51500100	NAME PLATES	EACH	2		1	1															
54001000	BOX CULVERT END SECTIONS	EACH	2			2															
M5401050	PRECAST CONCRETE BOX CULVERT 1.5M X 1.5M	METER	7.3			7.3															
M5401090	PRECAST CONCRETE BOX CULVERT 2.1M X 2.1M	METER	5.5			5.5															
M542E112	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 300MM	EACH	4	4																	
M542E116	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 375MM	EACH	2	2																	
M542E120	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 450MM	EACH	1	1																	
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM	EACH	3	3																	
M542E144	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 900MM	EACH	2	2																	
M542G035	GRATING FOR CONCRETE FLARED END SECTION 600MM	EACH	3	3																	
M542G055	GRATING FOR CONCRETE FLARED END SECTION 900MM	EACH	2	2																	
M5500010	STORM SEWERS, CLASS A, TYPE 1 100MM	METER	27	27																	
M5500015	STORM SEWERS, CLASS A, TYPE 1 150MM	METER	3	3																	
M5502820	STORM SEWERS, TYPE 1, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS IV 200MM	METER	10	10																	
M5502840	STORM SEWERS, TYPE 1, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS IV 300MM	METER	2086	2086																	
M5502850	STORM SEWERS, TYPE 1, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS IV 375MM	METER	190	190																	

* SPECIALTY ITEMS
VILL. OR VILLAGE = VILLAGE OF LAKE ZURICH

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 22
FROM US RTE 12 TO BUESCHING RD
SUMMARY OF QUANTITIES #3

SCALE : NA
DATE : 08/21/04
DESIGNED BY KLM
CHECKED BY DDL

Rev.