

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	6
STA.	TO STA.		60997	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED 20% STATE J000-2A	BRIDGE 80% FED 20% STATE X771-5B	RETAINING WALL 80% FED 20% STATE Y007	LIGHTING 100% VILLAGE Y030-1E	TRAFFIC SIGNALS IL 22 @ MALL DR. 100% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ US 12 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ ELA 80% FED 10% STATE 5% VILL. 5% COUNTY Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN WEST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ OLD RAND 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN EAST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ BUESCHING 80% FED 10% STATE 10% VILL. Y031-1F	TRAFFIC SIGNAL EVP EQUIPMENT 100% VILL. Y031-3D	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE Y031-1F	NEW SIDEWALK & BIKE PATH 50% STATE 50% VILL. SFTY-1B	WATER MAIN/SAN. SEWER 80% FED 20% STATE Y060	WATER MAIN/SAN. SEWER 100% VILL. Y060	TURN LANE FOR TARGET RENTAL 50% STATE 50% TARGET RENTAL J000-1A	100% VILLAGE OF LAKE ZURICH Y031-1F
M5502860	STORM SEWERS, TYPE 1, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS IV 450MM	METER	2	2																	
M5502880	STORM SEWERS, TYPE 1, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS IV 600MM	METER	83	83																	
M5502920	STORM SEWERS, TYPE 1, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS III 900MM	METER	22	22																	
M5503050	STORM SEWERS, TYPE 2, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS III 300MM	METER	732	732																	
M5503060	STORM SEWERS, TYPE 2, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS III 375MM	METER	262	262																	
M5503070	STORM SEWERS, TYPE 2, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS III 450MM	METER	446	446																	
M5503080	STORM SEWERS, TYPE 2, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS III 525MM	METER	74	74																	
M5503090	STORM SEWERS, TYPE 2, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS III 600MM	METER	140	140																	
M5503111	STORM SEWERS, TYPE 2, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS III 750MM	METER	473	473																	
M5503130	STORM SEWERS, TYPE 2, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS III 900MM	METER	267	267																	
M5503140	STORM SEWERS, TYPE 2, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS III, 1050MM	METER	103	103																	
M5503260	STORM SEWERS, TYPE 3, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS IV 300MM	METER	53	53																	
M5503270	STORM SEWERS, TYPE 3, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS IV 375MM	METER	160	160																	
M5503300	STORM SEWERS, TYPE 3, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS IV 600MM	METER	212	212																	
M5503320	STORM SEWERS, TYPE 3, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS IV 750MM	METER	59	59																	
M5503340	STORM SEWERS, TYPE 3, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS IV 900MM	METER	162	162																	
M5503350	STORM SEWERS, TYPE 3, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS IV, 1050MM	METER	91	91																	
M5503510	STORM SEWERS, TYPE 4, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS V 600MM	METER	48	48																	
M5503530	STORM SEWERS, TYPE 4, REINFORCED CONCRETE STORM DRAIN, AND SEWER PIPE, CLASS V 750MM	METER	697	697																	
* M5504800	STORM SEWERS TO BE CLEANED	METER	50	50																	
M5510025	STORM SEWER REMOVAL 300MM	METER	903	903																	

VILL. OR VILLAGE = VILLAGE OF LAKE ZURICH  
\* = NON - PARTICIPATING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
ILLINOIS ROUTE 22  
FROM US RTE 12 TO BUESCHING RD  
SUMMARY OF QUANTITIES #4

SCALE : NA  
DATE : 08/21/04  
DESIGNED BY KLM  
CHECKED BY DDL

Rev.