

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	18
STA.		TO STA.		60997
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED 20% STATE J000-2A	BRIDGE 80% FED 20% STATE X771-5B	RETAINING WALL 80% FED 20% STATE Y007	LIGHTING 100% VILLAGE Y030-1E	TRAFFIC SIGNALS IL 22 @ MALL DR. 100% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ US 12 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ ELA Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN WEST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ OLD RAND 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS IL 22 @ MAIN EAST 80% FED 13.3% STATE 6.7% VILL. Y031-1F	TRAFFIC SIGNALS IL 22 @ BUESCHING 80% FED 10% STATE 10% VILL. Y031-1F	TRAFFIC SIGNAL EQUIPMENT 100% VILL. Y031-3D	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE Y031-1F	NEW SIDEWALK & BIKE PATH 50% STATE 50% VILL. SFTY-1B	WATER MAIN/ SAN. SEWER 80% FED 20% STATE Y060	WATER MAIN/ SAN. SEWER 100% VILL. Y060	TURN LANE FOR TARGET RENTAL 50% STATE 50% TARGET RENTAL J000-1A	100% VILLAGE OF LAKE ZURICH Y031-1F
<del>Z0007625</del>	<del>BUILDING REMOVAL NO. 25</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>																	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1																	
* Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	130	130																	
Z0018800	DRAINAGE SYSTEM	L SUM	1		1																
□ Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4																	
□ Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	7	7																	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1																	
△ Z0076600	TRAINEES	HOUR	4-000	4-000																	
MX500142	FLOATING BEARINGS, FIXED, 2,600KN	EACH	2		2																
MX500343	FLOATING BEARINGS, GUIDED EXPANSION, 2,600KN	EACH	2		2																
MX032134	BRACED EXCAVATION	CU M	1100		1100																
<del>MX033222</del>	<del>BRACED EXCAVATION, SPECIAL</del>	<del>CU M</del>	<del>1000</del>		<del>1000</del>																
MX030546	SANITARY SEWER, DUCTILE IRON PIPE, 150MM DIAMETER	METER	30																	30	
MX030547	SANITARY SEWER, DUCTILE IRON PIPE, 200MM DIAMETER	METER	127																	77	50
MX030548	SANITARY SEWER, DUCTILE IRON PIPE, 250MM DIAMETER	METER	7																		7
MX030550	SANITARY SEWER, DUCTILE IRON PIPE, 150MM DIAMETER, AUGERED	METER	120																		120
MX030551	SANITARY SEWER, DUCTILE IRON PIPE, 200MM DIAMETER, AUGERED	METER	86																		86
MX030552	SANITARY SEWER, DUCTILE IRON PIPE, 300MM DIAMETER, AUGERED	METER	80																		80
MX030549	SANITARY SEWER, DUCTILE IRON PIPE, 350MM DIAMETER	METER	8																		8
MX030554	SANITARY SEWER, DUCTILE IRON PIPE, EPOXY COATED, 450MM DIAMETER	METER	21																		21
MX030553	SANITARY SEWER, SPECIAL 200MM	METER	45																	8	37
<del>MX030555</del>	<del>DUCTILE IRON WATER MAIN 250MM AUGERED AND JACKED</del>	<del>METER</del>	<del>20</del>																		<del>20</del>
MX030556	DUCTILE IRON WATER MAIN 300MM AUGERED AND JACKED	METER	20																		
MZ067800	STEEL CASING 550MM	METER	119																	55	64

⊗ SPECIALTY ITEMS  
 VILL. OR VILLAGE = VILLAGE OF LAKE ZURICH  
 △ = Y080  
 \* = NON - PARTICIPATING  
 □ - SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 ILLINOIS ROUTE 22  
 FROM US RTE 12 TO BUESCHING RD  
 SUMMARY OF QUANTITIES #16

SCALE : NA  
 DATE : 03/21/04

DESIGNED BY KLM  
 CHECKED BY DDL

Rev.