

| | | | | |
|---------------------|---------|---------------------------|--------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 337 | 19R-1 | LAKE | 800 | 18A |
| STA. | | TO STA. | | 60997 |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

| CODE NO. | PAY ITEM | UNIT | URBAN TOTAL QUANTITY | ROADWAY & DRAINAGE 80% FED 20% STATE | BRIDGE 80% FED 20% STATE | RETAINING WALL 80% FED 20% STATE | LIGHTING 100% VILLAGE | TRAFFIC SIGNALS IL 22 @ MALL DR. 100% VILL. | TRAFFIC SIGNALS IL 22 @ US 12 80% FED 20% STATE | TRAFFIC SIGNALS IL 22 @ ELA | TRAFFIC SIGNALS IL 22 @ MAIN WEST 80% FED 13.3% STATE 6.7% VILL. | TRAFFIC SIGNALS IL 22 @ OLD RAND 80% FED 20% STATE | TRAFFIC SIGNALS IL 22 @ MAIN EAST 80% FED 13.3% STATE 6.7% VILL. | TRAFFIC SIGNALS IL 22 @ BUESCHING 80% FED 10% STATE 10% VILL. | TRAFFIC SIGNAL E/VP EQUIPMENT 100% VILL. | TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE | NEW SIDEWALK & BIKE PATH 50% STATE 50% VILL. | WATER MAIN/ SAN. SEWER 80% FED 20% STATE | WATER MAIN/ SAN. SEWER 100% VILL. | TURN LANE FOR TARGET RENTAL 50% STATE 50% TARGET RENTAL | 100% VILLAGE OF LAKE ZURICH |
|------------|--|-------|----------------------|--------------------------------------|--------------------------|----------------------------------|-----------------------|---|---|-----------------------------|--|--|--|---|--|--|--|--|-----------------------------------|---|-----------------------------|
| * MX030557 | DUCTILE IRON FORCE MAIN 250MM | METER | 647 | | X771-58 | Y007 | Y030-1E | Y031-1F | Y031-1F | Y031-1F | Y031-1F | Y031-1F | Y031-1F | Y031-1F | Y031-3D | Y031-1F | SFTY-1B | Y060 | Y060 | 647 | |
| MX030558 | TEMPORARY MANHOLES, TYPE A, 1.5M DIAMETER TYPE 1 FRAME, OPEN LID | EACH | 1 | 1 | | | | | | | | | | | | | | | | | |
| * X0324769 | SANITARY SEWER LIFT STATION | L SUM | 1 | | | | | | | | | | | | | | | | | | 1 |
| * X0324770 | LIFT STATION ELECTRICAL | L SUM | 1 | | | | | | | | | | | | | | | | | | 1 |
| * MX030560 | EARTH RETENTION SYSTEM, HEIGHT 5M TO 8M | SQ M | 300 | | | | | | | | | | | | | | | | | | 300 |
| * MX030561 | EARTH RETENTION SYSTEM, HEIGHT 8M TO 11M | SQ M | 155 | | | | | | | | | | | | | | | | | | 155 |
| X0545005 | BOX CULVERT REMOVAL | L SUM | 1 | 1 | | | | | | | | | | | | | | | | | |
| MX030559 | TEMPORARY MANHOLES, TYPE A, 1.5M DIAMETER TYPE 1 FRAME, CLOSED LID | EACH | 4 | 4 | | | | | | | | | | | | | | | | | |
| MX560161 | TEMPORARY STORM SEWER, 300MM | METER | 262 | 262 | | | | | | | | | | | | | | | | | |
| X0324771 | FRAMES AND GRATES TO BE REMOVED AND REPLACED WITH TYPE 1 FRAME, OPEN LID | EACH | 7 | 7 | | | | | | | | | | | | | | | | | |
| X0324772 | TYPE 1 FRAME, OPEN LID (TEMPORARY) | EACH | 20 | 20 | | | | | | | | | | | | | | | | | |
| * X0324773 | FLASHING BEACON INSTALLATION | EACH | 4 | | | | | | | | 2 | 2 | | | | | | | | | |
| * MX030562 | TEMPORARY AERIAL FIBER OPTIC CABLE NO. 625/125, 12F ON MESSENGER | METER | 1490 | | | | | | | | | | | | | | | | | | 1490 |
| * MX030563 | TEMPORARY FIBER OPTIC CABLE IN CONDUIT NO. 625/125 12F | METER | 520 | | | | | | | | | | | | | | | | | | 520 |
| * 66900450 | SPECIAL WASTE PLANS AND REPORTS | L SUM | 1 | 1 | | | | | | | | | | | | | | | | | |
| * M6690100 | BACKFILL PLUGS | CU M | 17 | 17 | | | | | | | | | | | | | | | | | |
| * 66900530 | SOIL DISPOSAL ANALYSIS | EACH | 3 | 3 | | | | | | | | | | | | | | | | | |
| MX406770 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50 | M TON | 600 | 600 | | | | | | | | | | | | | | | | | |
| Z0049806 | REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO.6 | L SUM | 1 | 1 | | | | | | | | | | | | | | | | | |
| Z0049906 | REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO.6 | L SUM | 1 | 1 | | | | | | | | | | | | | | | | | |
| Z0049907 | REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO.7 | L SUM | 1 | 1 | | | | | | | | | | | | | | | | | |
| Z0049908 | REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO.8 | L SUM | 1 | 1 | | | | | | | | | | | | | | | | | |
| Z0049914 | REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO.14 | L SUM | 1 | 1 | | | | | | | | | | | | | | | | | |
| Z0049915 | REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO.15 | L SUM | 1 | 1 | | | | | | | | | | | | | | | | | |

* SPECIALTY ITEMS
VILL. OR VILLAGE = VILLAGE OF LAKE ZURICH

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 22
FROM US RTE 12 TO BUESCHING RD
SUMMARY OF QUANTITIES #17

SCALE : NA
DATE : 05/21/04

DESIGNED BY KLM
CHECKED BY DDL

Rev.