

#60997

### EARTHWORK SCHEDULE

LOCATION	STAGE 1A				STAGE 1B				STAGE 2A				STAGE 2B			
	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)
ILLINOIS 22																
STA. 6+927.80 TO STA. 8+800	9422	23117	414	22703	668	185	368	-183	3722	193	501	-308	0	57	0	57
STA. 8+800 TO STA. 10+200	8264	20432	1246	19186	0	0	0	0	1182	154	412	-259	0	0	0	0
-----																
CAROLYN	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
CORTLAND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
BUESCHING	0	0	0	0	0	0	0	0	0	67	0	67	0	0	0	0
ELA	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
EAST MAIN STREET	0	408	0	408	0	0	0	0	0	0	0	0	0	0	0	0
WEST MAIN STREET	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
OLD RAND ROAD	0	0	0	0	0	0	0	0	170	306	10	295	0	0	0	0
RAND ROAD	291	300	26	274	1007	12	288	-276	1608	3108	982	2126	0	0	0	0
WHITNEY	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
EJ & E RAILROAD	0	2075	2200	-125	0	0	0	0	0	0	0	0	0	0	0	0
TOTAL:	17977	46332	3886	42446	1675	197	656	-459	6682	3827	1905	1921	0	57	0	57

LOCATION	STAGE 3A				STAGE 3B				STAGE 4A				STAGE 4B			
	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)
ILLINOIS 22																
STA. 6+927.80 TO STA. 8+800	1524	205	368	-163	1672	1879	1140	739	2259	2652	1947	705	0	0	0	0
STA. 8+800 TO STA. 10+200	5327	5586	847	4739	22	40	0	40	0	0	0	0	0	0	0	0
-----																
CAROLYN	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
CORTLAND	0	0	0	0	0	0	0	0	14	8	0	8	0	0	0	0
BUESCHING	98	189	0	189	0	0	0	0	0	0	0	0	0	0	0	0
ELA	0	0	0	0	0	0	0	0	71	199	46	153	0	0	0	0
EAST MAIN STREET	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
WEST MAIN STREET	0	0	0	0	0	0	0	0	497	2042	6	2036	0	0	0	0
OLD RAND ROAD	129	380	34	346	0	0	0	0	0	0	0	0	0	0	0	0
RAND ROAD	1269	2348	1004	1343	0	0	0	0	0	247	58	189	0	4	303	-299
WHITNEY	0	0	0	0	58	197	5	192	0	0	0	0	0	0	0	0
EJ & E RAILROAD	0	0	0	0	0	0	0	0	0	0	0	0	0	3664	1831	1834
TOTAL:	8346	8708	2253	6454	1752	2116	1145	971	2841	5148	2057	3091	0	3668	2134	1534

\* 15% SHRINKAGE FACTOR USED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION ILLINOIS ROUTE 22 FROM US RTE 12 TO BUESCHING RD SCHEDULE OF QUANTITIES
NAME	DATE	
		SCALE : DATE : 07/21/04 DESIGNED BY CHECKED BY