

### EARTHWORK SCHEDULE CONTINUED

#60997

LOCATION	STAGE 5A				STAGE 5B				STAGE 5C				STAGE 6A			
	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)
ILLINOIS 22																
STA. 6+927.80 TO STA. 8+800	608	1731	69	1662	0	0	0	0	0	0	0	0	0	0	0	0
STA. 8+800 TO STA. 10+200	4754	3903	986	2917	288	771	0	771	0	0	0	0	0	0	0	0
-----																
CAROLYN	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
CORTLAND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
BUESCHING	123	291	47	244	0	0	0	0	0	0	0	0	0	0	0	0
ELA	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
EAST MAIN STREET	0	0	0	0	0	0	0	0	0	0	0	0	297	684	0	684
WEST MAIN STREET	0	0	0	0	198	930	30	900	167	231	61	169	0	0	0	0
OLD RAND ROAD	84	153	23	131	217	234	8	227	0	0	0	0	0	0	0	0
RAND ROAD	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
WHITNEY	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
EJ & E RAILROAD	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
<b>TOTAL:</b>	<b>5569</b>	<b>6078</b>	<b>1125</b>	<b>4953</b>	<b>703</b>	<b>1935</b>	<b>38</b>	<b>1897</b>	<b>167</b>	<b>231</b>	<b>61</b>	<b>169</b>	<b>297</b>	<b>684</b>	<b>0</b>	<b>684</b>

### EARTHWORK SCHEDULE CONTINUED

LOCATION	STAGE 6B				STAGE 6
	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU. M)	* EARTH EXCAVATION (SUITABLE) (CU. M)	EMBANKMENT (CU. M)	EXCESS (+) SHORTAGE (-) (CU. M)	TOPSOIL FURNISH AND PLACE (CU. M)
ILLINOIS 22					
STA. 6+927.80 TO STA. 8+800	0	0	0	0	2894
STA. 8+800 TO STA. 10+200	0	0	0	0	4249
-----					
CAROLYN	0	172	0	172	
CORTLAND	0	0	0	0	
BUESCHING	0	0	0	0	
ELA	0	0	0	0	
EAST MAIN STREET	229	777	19	758	147
WEST MAIN STREET	0	0	0	0	171
OLD RAND ROAD	0	0	0	0	115
RAND ROAD	0	0	0	0	3497
WHITNEY	0	0	0	0	
EJ & E RAILROAD	0	0	0	0	
<b>TOTAL:</b>	<b>229</b>	<b>949</b>	<b>19</b>	<b>930</b>	<b>11073</b>

\* 15% SHRINKAGE FACTOR USED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION ILLINOIS ROUTE 22 FROM US RTE 12 TO BUESCHING RD SCHEDULE OF QUANTITIES
NAME	DATE	
		SCALE : DATE : 07/21/04 DESIGNED BY JRP CHECKED BY DDL