F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	39
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

#60997

PAVEMENT SCHEDULE

LOCATION	PAVEMENT REMOVAL (S.M.)	CONCRETE MEDIAN REMOVAL (S.M.)	BITUMINOUS SURFACE REMOVAL 65mm (S.M.)	CURB REMOVAL (METER)	CURB & GUTTER REMOVAL (METER)	SIDEWALK REMOVAL (S.M.)	PROPOSED PAVEMENT AREA (S.M.)	BITUMINOUS BASE COURSE WIDENING 200mm (S.M.)	PCC BASE COURSE WIDENING 230mm (S.M.)	POLY. BIT. SURF. CSE. SUPERPAVE MIX. "F", N90 45mm (M TON)	BIT. CONC. SURF. CSE. SUPERPAVE MIX. D, N50 50mm (M TON)	BIT. CONC. BINDER CSE. SUPERPAVE IL-19.0, N 90 150mm (M TON)	BIT. CONC. BINDER CSE. SUPERPAVE IL-19.0, N 50 200mm (M TON)	BITUMINOUS SHOULDERS SUPERPAVE 200mm (S.M.)	AGGREGATE SUBGRADE 300mm (S.M.)	SUB-BASE GRANULAR MATERIAL TYPE B 100mm (S.M.)	AGGREGATE BASE CSE. TYPE B 150mm (S.M.)	P.C.C. PAVEMENT (JOINTED) 250mm (S.M.)
ROUTE 22																		
STA. 6+927.8 TO 7+440.82			5171				7714		2741	875		1012		1701		2741		
STA. 7+440.82 TO 10+200	23,828			163	1573	1513	50,956				369	211			59,733		2427	51,086
CORTLAND DRIVE			483		161	9	841	89			104					126		
US 12 (RAND ROAD)	19,547	218	7710	64	2109		21,587		254	874				709	20,703	322		17,905
ELA ROAD	905				137		1096								1180			1096
WHITNEY ROAD	559				103	119	515								583			515
MAIN STREET WEST	1568		1415	29	218	153	2241			161					2478			2241
ROBERTSON DRIVE	122					48	292				17		68		193	135		160
GENESEE STREET	2575					25	182								267			182
MEADOW LANE	355						421				52		207			465		
PRAIRIE STREET	363						439				54		216			487		
OLD RAND ROAD	2935				120	252	4036								4777			4036
MOHAWK TRAIL	491				176	236	1340				169		659			1481		
MAIN STREET EAST							4105								4678			4105
CAROLYN COURT	127						483				60		237			456		
BUESCHING ROAD	1708				284	161	2155								2391			2155
TOTAL	55083	218	14779	256	4881	2516	98403	89	2995	1910	825	1223	1387	2410	96983	6213	2427	83481

PAVEMENT SCHEDULE

LOCATION	COMB. CONC. C&G TY. M-5.60 (METER)	COMB. CONC. C&G TY. M-10.30 (METER)	COMB. CONC. C&G TY. M-10.60 (METER)	COMB. CONC. C&G TY. B-15.30 (METER)	COMB. CONC. C&G TY. B-15.60 (METER)	CONCRETE MEDIAN TY. SB-15.60 (S.M.)	CORRUGATED MEDIAN (S.M.)	CORRUGATED MEDIAN MODIFIED (S.M.)	CONCRETE MEDIAN SURFACE 100mm (S.M.)	P.C.C. SIDEWALK 125mm (S.M.)
ROUTE 22										
STA. 6+927.8 TO 7+440.82					340			0		297
STA. 7+440.82 TO 10+200	290				7360	1356	206		376	4904
CORTLAND DRIVE				94	57				5	16
US 12 (RAND ROAD)					2709	687			134	
ELA ROAD				77						
WHITNEY ROAD				68						147
MAIN STREET WEST					343.5					410
ROBERTSON DRIVE										48
GENESEE STREET					72.5				29	
MEADOW LANE				86						
PRAIRIE STREET				97						
OLD RAND ROAD		45	45	86	697				139	601
MOHAWK TRAIL				103						58
MAIN STREET EAST		45	45	85	558				105	568
CAROLYN COURT				66						15
BUESCHING ROAD					304					106
TOTAL	290	90	90	762	12441	2043	206	0	788	7170

REVISIONS	
NAME	DATE
1 REVISED GEOMETRY	11/24/04
FROM STA. 6+922.366 TO	
STA. 7+440.820	

ILLINOIS DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 22

FROM US RTE 12 TO BUESCHING RD

SCHEDULE OF QUANTITIES

SCALE :

DATE : 07/21/04

DESIGNED BY JRP

CHECKED BY DDL