

### MAINTENANCE OF TRAFFIC / TEMPORARY DRAINAGE SCHEDULE

# #60997

PAY ITEM	UNIT	STAGE 3A				STAGE 3B			
		ILL. RT. 22 - BEGINNING TO MAIN ST. WEST	ILL. RT. 22 - MAIN ST. WEST TO END	U.S. RT. 12 (RAND RD.)	TOTAL	ILL. RT. 22 - BEGINNING TO MAIN ST. WEST	ILL. RT. 22 - MAIN ST. WEST TO END	U.S. RT. 12 (RAND RD.)	TOTAL
TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	1859	4119	1332	7310	1909	449	455	2813
TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	0	0	0	0	0	0	0	0
TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	0	0	0	0	0	0	0	0
TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	30	34	14	78	30	16	14	60
PAVEMENT MARKING TAPE TYPE III - LINE 100MM	METER	1280	1512	3322	6114	0	246	0	246
PAVEMENT MARKING TAPE TYPE III - LINE 150MM	METER	0	0	34	34	0	0	0	0
PAVEMENT MARKING TAPE TYPE III - LINE 300MM	METER	0	12	0	12	0	0	0	0
PAVEMENT MARKING TAPE TYPE III - LINE 600MM	METER	0	0	18	18	0	0	0	0
PAVEMENT MARKING REMOVAL	SQ M	198	601	97	896	193	95	0	288
TEMPORARY PAVEMENT	SQ M	78	1818		1896	1808			1808
TEMPORARY MANHOLES, TYPE A, 1.2 m DIA, TYPE 1 FRAME, CLOSED LID	EACH	1			1				0
TEMPORARY CONCRETE BARRIER	METER	0			0				
IMPACT ATTENUATOR TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3 - RELOCATE	EACH	0			0				

PAY ITEM	UNIT	STAGE 4A				STAGE 4B			
		ILL. RT. 22 - BEGINNING TO MAIN ST. WEST	ILL. RT. 22 - MAIN ST. WEST TO END	U.S. RT. 12 (RAND RD.)	TOTAL	ILL. RT. 22 - BEGINNING TO MAIN ST. WEST	ILL. RT. 22 - MAIN ST. WEST TO END	U.S. RT. 12 (RAND RD.)	TOTAL
TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	1480	1771	167	3418	0	0	0	0
TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	0	0	58	58	0	0	0	0
TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	0	0	0	0	0	0	0	0
TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	20	8	10	38	0	0	0	0
PAVEMENT MARKING TAPE TYPE III - LINE 100MM	METER	5328	1674	3876	10878	1710	0	4553	6263
PAVEMENT MARKING TAPE TYPE III - LINE 150MM	METER	78	0	264	342	0	0	375	375
PAVEMENT MARKING TAPE TYPE III - LINE 300MM	METER	0	0	0	0	0	0	0	0
PAVEMENT MARKING TAPE TYPE III - LINE 600MM	METER	41	16	51	108	17	0	55	72
PAVEMENT MARKING REMOVAL	SQ M	761	0	490	1251	0	0	203	203
TEMPORARY PAVEMENT	SQ M	32			32				0
TEMPORARY CONCRETE BARRIER (RELOCATE)	METER	82			82	61			61
IMPACT ATTENUATOR TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3 - RELOCATE	EACH	3			3	2			2
TEMPORARY CONCRETE BARRIER	METER	0			0				

REVISIONS	
NAME	DATE
REVISOR: GEOMETRY	11/24/04
FROM STA. 6+922.366 TO STA. 7+440.820	

ILLINOIS DEPARTMENT OF TRANSPORTATION  
ILLINOIS ROUTE 22  
FROM US RTE 12 TO BUESCHING RD

MAINTENANCE OF TRAFFIC  
SCHEDULE OF QUANTITIES

DRAWN BY MBF  
CHECKED BY SMK

DATE 7/21/04