

F.A. . RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	19R-1	LAKE	800	50
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

#60997

PAY ITEM	UNIT	ALL STAGES
		PROJECT TOTALS
TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	41268
TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	1031
TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	106
TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	678
PAVEMENT MARKING TAPE TYPE III - LINE 100MM	METER	60218
PAVEMENT MARKING TAPE TYPE III - LINE 150MM	METER	3833
PAVEMENT MARKING TAPE TYPE III - LINE 300MM	METER	20
PAVEMENT MARKING TAPE TYPE III - LINE 600MM	METER	698
WORKZONE PAVEMENT MARKING REMOVAL	SQ M	11098
TEMPORARY PAVEMENT	SQ M	23264
TEMPORARY CONCRETE BARRIER	METER	339
IMPACT ATTENUATOR TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH	4
RELOCATE TEMPORARY CONCRETE BARRIER	METER	353
IMPACT ATTENUATOR TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3 - RELOCATE	EACH	7
CATCH BASINS TO BE ADJUSTED	EACH	3
MANHOLES TO BE ADJUSTED	EACH	7
FRAMES AND GRATES TO BE REMOVED	EACH	6
TEMPORARY MANHOLES, TYPE A, 1.2 m DIA, TYPE 1 FRAME, CLOSED LID	EACH	1
TEMPORARY MANHOLES, TYPE A, 1.5 m DIA, TYPE 1 FRAME, OPEN LID	EACH	1
TEMPORARY MANHOLES, TYPE A, 1.5 m DIA, TYPE 1 FRAME, CLOSED LID	EACH	4
TEMPORARY END SECTION	EACH	1
TEMPORARY INLET	EACH	14
TEMPORARY STORM SEWER, 300 mm	EACH	262.2
END SECTIONS TO BE RELOCATED	EACH	1
FRAMES AND GRATES TO BE REMOVED AND REPLACED WITH TYPE 1 FRAME, OPEN LID	EACH	7
TYPE 1 FRAME, OPEN LID (TEMPORARY)	EACH	20

REVISIONS	
NAME	DATE
△ REVISED GEOMETRY	11/24/04
FROM STA. 6+922.366 TO STA. 7+440.820	

ILLINOIS DEPARTMENT OF TRANSPORTATION  
ILLINOIS ROUTE 22  
FROM US RTE 12 TO BUESCHING RD  
MAINTENANCE OF TRAFFIC  
SCHEDULE OF QUANTITIES

DATE 7/21/04  
DRAWN BY MBF  
CHECKED BY SMK